

**Name of the Work "Construction of AWC Building at Diamunda-II of Jhurimal
G.P,Lephripara block**

TENDER SCHEDULE

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work excavation in foundation in hard soil within initial lead 50m. & lift 1.5 m. including rough dressing, breaking clods, laying in layers. Etc. Complete	cum	105.295	184.60	19437.00
2	Filling F & P with sand, well watered and rammed with cost, carriage and royalty etc. complete	cum	65.589	275.00	18037.00
3	Cement Concrete in (1:3:6) using 40mm. Size CBHG metal including laying compacting, Curing with cost, carriage and royalty etc. complete	cum	21.402	4631.50	99123.00
4	R.C.C. M-20 Grade With 20mm and down Grade C.B. Chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator watering, curing and cost of all materials and labour, T & P etc Complete but excluding cost of reinforcement complete.	cum	30.310	4787.30	145103.00
5	Labour for straightening , Cutting, bending & binding the M.S. Road including cost of binding wire and cost of MS Road	Qtnl	29.686	7686.30	228176.00
6	Rigid and smooth centering and shuttering for R.C.C. work and dismantling then after casting including cost of all materials complete				
	(A) Mass Concrete	Sqm	102.659	99.90	10256.00
	(B) Column & Beam	Sqm	69.638	718.50	50035.00
	(C) Lintel	Sqm	15.803	258.70	4088.00
	(D) Roof slab & Chajja	Sqm	87.914	419.70	36898.00
7	Brick work with Fly Ash Bricks 23cm x 11cm x 8cm size having crusing strength not less than 75kg/cm ² with dimensional tolerance \pm 8 percent in cement mortar (1:6) in Foundation and Plinth including water curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of EIC.	cum	26.370	4119.60	108634.00

8	Brick work with Fly Ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75kg/cm ² with dimensional tolerance \pm 8 percent in cement mortar (1:6) in Superstructure including water curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of EIC.	cum	59.750	4153.00	248142.00
9	16mm thick C.P. in C.M. (1:6) over brick masonry to the rough surface including all cost.	Sqm	108.601	191.80	20830.00
10	12mm thick C.P. in C.M (1:6) Over brick Masonry to the smooth surface including all cost.	Sqm	410.535	134.20	55094.00
11	6mm thick cement plaster (1:4) to RCC surfaces finisher smooth including closed deep chipping and slurry treatment, watering, curing cost, carriage, royalty and taxes of all materials	Sqm	82.324	149.80	12332.00
12	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conforming to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	Sqm	77.920	938.30	73112.00
13	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqm	18.081	1037.20	18754.00
14	Fixing glazed tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm conforming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	Sqm	17.194	730.80	12565.00
15	Fixing of granite in floor above 0.10 to 0.40 sqm over 20mm thick Cement Plaster (1:4) with all cost of materials, labour etc. complete.	Sqm	11.713	1508.80	17673.00

16	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc.	RM	6.000	3495.10	20971.00
17	P/F 60mm thick factory made C.C interlocking paver block of M30	Sqm	9.850	530.30	5223.00
18	2.5cm thic grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken Granite chips on new work including all cost of all materials, water proofing compounds T&P required for the works etc complete	Sqm	31.682	294.30	9324.00
19	Roofing with an Flat tiles and cement mortar (1:6) boarders 23 cmx5 cm at 1.80 mt intervals,complete per 1 sqm.	Sqm	36.938	532.30	19662.00
20	C.C. (1:2:4) with 12mm and down grade C.B. chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C.	cum	1.758	5886.40	10348.00
21	12mm thick C.P. in C.M.(1:4) over brick masonry to the smooth surface with neat cement punning including watering curing, cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of Engg-in -charge.	Sqm	21.012	151.50	3183.00
22	Priming 1 coat with wall primer water bond cement primer including all labour, Materials, T&P etc Complete	Sqm	240.500	57.80	13901.00
23	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to given an even shade in cluding cost of weather coat all cost of labours,T&P etc complete.	Sqm	240.500	70.70	17003.00
24	MS-Gate	Kg	110.530	56.60	6256.00
25	Enamel paint for Door	Sqm	4.800	133.00	638.00
26	Display Board	No.	1	5000.00	5000.00

Total

1289798.00

Bore well

27	#REF!				
	125mm dia oomtr 100th mtr	100.00	mtr	480.00	48000.00
28	#REF!				
	125 mm dia PVC casing pipe	30.00	mtr	72.00	2160.00
29	#REF!	1	each	2000.00	2000.00
30	#REF!	30	mtr	568.00	17040.00
31	#REF!	1	no	25000.00	25000.00

				For 1 no	94200.00
(For 1 no)	1	x		94200.00	94200.00

1383998.00

<u>32</u>	Electrification	1	x	56073.00	56073.00
<u>33</u>	PH Work 6%	1	x	77966.00	77966.00
<u>33</u>	Add GST 12%	1	x	182169.00	182169.00

1700206.00

Limited to **1700000.00**

The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender document will be rejected.

My/Our quoted rate is _____%(Figure) _____ (In words)

***Less than/Excess over/ Equal to the amount put to tender.**

Total number of Items:..... Number of Corrections:..... Number of interpolation:..... Number of over writings:..... E.M.D Funnished/EMD Exempted (A)Demand Draft No..... (B)Ammount Rs..... Copy of PAN card:furnished/not furnished Copy of GST Registration:furnished/not furnished Copy of Contractor's Licecence:furnished/not furnished Copy of Experience certificate:furnished/not furnished Total No of sheets in the Tender Papers:.....	
--	--

Full Signeture of Contractor

Signature of the Bidder/Tenderer

**Signature of the B.D.O
Lephrpara**