

## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF MARKET COMPLEX AT LASSEY-1 GP KUMJHARIA "**

<b>Bidder Name</b>		Less(-)			%
--------------------	--	---------	--	--	---

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	50.060	1CUM	126.69	6342.10
2	Filling foundation and plinth with sand well watered and rammed etc complete	50.47	1cum	373.2	18835.40
3	Cement Concrete (1:3:6) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	18.620	1cum	3533.65	65796.56
4	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	16.310	1cum	3392.6	55333.31
5	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	35.72	1cum	3425.6	122362.43
6	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	37.160	1cum	3977.6	147807.62
7	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	31.58	1qntl	6148.60	194172.79
8.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-A.Foundation and plinth	84.91	1sqm	84.00	7132.44
8.B	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	22.21	1sqm	208.4	4628.56
8.C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-C.Beam and Column	67.75	1sqm	516.4	34986.10

**NAME OF WORK :- "CONSTRUCTION OF MARKET COMPLEX AT LASSEY-1 GP KUMJHARIA "**

Bidder Name		Less(-)			%
-------------	--	---------	--	--	---

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
8.D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. D.Roof slab	101.86	1sqm	324.5	33053.57
E	chajja	10.3	1sqm	324.5	3342.35
9	2.5 cm thick grading concrete(1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials,water proofing compounds T&P required for the work etc.complete.	118.87	1Sqm	209.70	24927.04
10	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	194.45	1sqm	94.8	18433.86
11	16mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	300.41	Sqm	135.1	40585.39
12	Cost of Iron Door	10.32	Qntl	LS	70000.00
13	Labour charges for fitting,fixing of MS door ,window	25.8	Sqm	67.4	1738.92
14	Painting two coats with enamel paint of approved shade on new work to give an even shade to including cost of paint etc. complete.	58.05	1sqm	90.30	5241.92
15	2.5cm thick AS Flooring with cement concrete (1:2:4) including punning using 12mm size HG chips including cost,conveyance,royalty labour all taxes	107.54	1sqm	215.50	23174.87
16	12mm thick cement plaster in CM (1:4) including cost,carriage,royalty etc completed	21.01	1sqm	110.60	2323.71

**NAME OF WORK :- "CONSTRUCTION OF MARKET COMPLEX AT LASSEY-1 GP KUMJHARIA "**

Bidder Name		Less(-)			%
-------------	--	---------	--	--	---

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
17	Finishing wall with water proffing cement paint in new work 2 coats to give an even shade including cost of paint	194.45	1sqm	23.8	4627.91
18	Distempering 2 coats to wall with distemper of approved shade on new work to give an even shade including cost of distemper	435.14	1sqm	44.60	19407.24
20	Add for display board	1	L/S	3000.00	
21	Add 1% Cess	1	L/S	10161.00	10161.00
					914415.09
22	Add for G.S.T @ 12%				
				TOTAL	914415.09

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development officer  
Kuarmunda Block**