

TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "RENOVATION OF DEVELOPMENT OF SURPLUS OF PODMARA TANK, KUARMUNDA GP

Bidder
Name

Less(-)

%

SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate (Rs)	Amount (Rs)
1	2	3	4	5	6
1	clearing and rubbing road land including uprooting rank,vegetation,grass,bushes,shrubs,stumps of trees girth upto 300mm and disposed unserviceable materials up to a lift 100 mtr.	725.00	Sqm	3.87	2805.75
2	Earth work in slushy soil(in water upto .6m depth requiring the aids of pans and vessels)within 50meter initial lead and 1.5 meter initial lift as per the direction and specification of the department.	1950.00	Cum	108.03	210658.50
3	Earth work in hard soil or gravelly soil with in 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding .30m depth as per the direction of Engineer in charge.	4706.00	Cum	105.58	496859.48
4	Earth work excavation in foundation in hard soil with initial lead and lift including rough dressing and levelling the bed etc.complete as directed.	124.20	cum	126.69	15734.90
5	Filling foundation and plinth with sand with well watered and rammed including cost,conveyance,royalty etc. Complete as directed.	13.80	cum	276.43	3814.73
6	Cement Concrete (1:3:6) using 2.5cm size HBG metal including Cost,Coveyance, royalty etc complete	91.430	Cum	3606.2	329714.87
7	Cement Concrete (1:2:4) using 12mm size HBG chips including Cost,Coveyance, royalty etc complete	3.450	Cum	4645.1	16025.60
8	Rough stone packing in aprons revetment with quarried and blasted other than granite stone boulder of size 30cm above including dumping on slopes filling interstics with small stone and wedges and packing surface proper line and levels complete.	185.15	Cum	1061.9	196610.79
#####	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	414.00	Sqm	83.9	34734.60
10	Add for Display Board(Made from R.C.C& WRITTEN IN ENGLISH & ODIA)	1	EACH	6000.00	6000.00
13	TOTAL				1312959.21
14	Cess 1%				13129.22
16	TOTAL				1326088.43
17					

NAME OF WORK :- "RENOVATION OF DEVELOPMENT OF SURPLUS OF PODMARA TANK, KUARMUNDA GP

**Bidder
Name**

Less(-)

%

SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate (Rs)	Amount (Rs)
	Total				1326088.428
	Limited to Rs				1326088.00

**Junior Engineer
Kuarmunda Block**

**Asst.Executive Engineer
Kuarmunda Block**

**Block Development Officer
Kuarmunda Block**