

TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF MARKET COMPLEX AT GOBIRA GP KHUKHUNDUBAHAL "

Bidder Name		Less(-)			%
--------------------	--	---------	--	--	---

SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate (Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	62.590	1CUM	126.70	7930.15
2	Filling foundation and plinth with sand well watered and rammed etc complete	30.35	1cum	329.2	9991.22
3	Cement Concrete (1:3:6) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	16.660	1cum	3599.79	59972.50
4	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	11.860	1cum	3372.3	39995.48
5	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	32.26	1cum	3405.3	109854.978
6	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	34.250	1cum	4036.4	138246.70
7	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	30.83	1qntl	6158.20	189857.31
8.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-A.Foundation and plinth	88.61	1sqm	84.41	7479.57
8.B	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	20.5	1sqm	209.37	4292.09
8.C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-C.Beam and Column	69.35	1sqm	517.62	35896.95

NAME OF WORK :- "CONSTRUCTION OF MARKET COMPLEX AT GOBIRA GP KHUKHUNDUBAHAL "

Bidder Name		Less(-)			%
-------------	--	---------	--	--	---

SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate (Rs)	Amount (Rs)
8.D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. D.Roof slab	86.41	1sqm	325.94	28164.48
E	chajja	9.38	1sqm	325.94	3057.3172
9	2.5 cm thick grading concrete(1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials,water proofing compounds T&P required for the work etc.complete.	100.8	1Sqm	210.30	21198.24
10	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	174.19	1sqm	94.07	16386.05
11	16mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	236.39	Sqm	134.17	31716.45
12	Cost of Rolling Shutter including all accessories ,fabrication and locking arrangement complete in all respect	10.64	Qntl	7000	74480.00
13	Labour charges for fitting,fixing of MS door ,window	19.35	Sqm	67.4	1304.19
14	Painting two coats with enamel paint of approved shade on new work to give an even shade to including cost of paint etc. complete.	43.54	1sqm	90.30	3931.66
15	2.5cm thick AS Flooring with cement concrete (1:2:4) including punning using 12mm size HG chips including cost,conveyance,royalty labour all taxes	92.07	1sqm	216.99	19978.27
16	12mm thick cement plaster in CM (1:4) including cost,carriage,royalty etc completed	16.89	1sqm	109.82	1854.86

NAME OF WORK :- "CONSTRUCTION OF MARKET COMPLEX AT GOBIRA GP KHUKHUNDUBAHAL "

Bidder Name		Less(-)			%
-------------	--	---------	--	--	---

SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate (Rs)	Amount (Rs)
17	Finishing wall with water proffing cement paint in new work 2 coats to give an even shade including cost of paint	174.19	1sqm	23.82	4149.21
18	Distempering 2 coats to wall with distemper of approved shade on new work to give an even shade including cost of distemper	371.12	1sqm	44.56	16537.11
19	Writing Charges for shop numbering and board				500
20	Add for display board	1	L/S	2500.00	
21	Add 1% Cess	1	L/S	9288.00	9288.00
					836062.76
22	Add for G.S.T @ 12%				
				TOTAL	836062.76

**Junior Engineer
Kuarmunda Block**

**Asst.Executive Engineer
Kuarmunda Block**

**Block Development officer
Kuarmunda Block**