

# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "RENOVATION OF TANK AT TELIPOSH, KUARMUNDA GP

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	clearing and rubbing road land including uprooting rank,vegetation,grass,bushes,shrubs,stumps of trees girth upto 300mm and disposed unserviceable materials up to a lift 100 mtr.	785.00	Sqm	3.87	3037.95
2	Earth work in slushy soil(in water upto .6m depth requiring the aids of pans and vessels)within 50meter initial lead and 1.5 meter initial lift as per the direction and specification of the department.	1188.00	Cum	108.03	128339.64
3	Earth work in hard soil or gravelly soil with in 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding .30m depth as per the direction of Engineer in charge.	3582.00	Cum	105.58	378187.56
4	Earth work excavation in foundation in hard soil with initial lead and lift including rough dressing and levelling the bed etc.complete as directed.	127.91	cum	126.69	16204.92
5	Filling foundation and plinth with sand with well watered and rammed including cost,conveyance,royalty etc. Complete as directed.	13.19	cum	276.43	3646.11
6	Cement Concrete (1:3:6) using 2.5cm size HBG metal including Cost,Coveyance, royalty etc complete	76.440	Cum	3606.2	275657.93
7	Cement Concrete (1:2:4) using 12mm size HBG chips including Cost,Coveyance, royalty etc complete	5.570	Cum	4645.1	25873.21
8	Rigid smooth centering &shuttering for R.C.C Work including false work &dismentaling then after casting including cost of material complete-Foundation and plinth	205.26	Sqm	83.9	17221.31
9	16mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.	63.4	Sqm	133.2	8444.88
10	Earth filling in aprons and revetments	116.64	Cum	70.38	8209.12
11	Rough stone packing in aprons revetment with quarried and blasted other than granite stone boulder of size 30cm above including dumping on slopes filling interstics with small stone and wedges and packing surface proper line and levels complete.	7.2	Cum	1061.9	7645.68
12	Add for Display Board(Made from R.C.C& WRITTEN IN ENGLISH & ODIA)	1	EACH	6000.00	6000.00

**NAME OF WORK :- "RENOVATION OF TANK AT TELIPOS, KUARMUNDA GP**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
13	TOTAL				878468.31
14	Cess 1%				8784.25
16	TOTAL				887252.56
17					
Total					887252

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**