

# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF BOUNDARY WALL & DEVELOPMENT OF ROAD AT KUARMUNDA-VI  
A.W.C KUARMUNDA GP

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	69.110	Cum	126.70	8756.24
2	Filling foundation and plinth with sand well watered and rammed etc complete	16.4	Cum	276.42	4533.29
3	Cement Concrete (1:3:6) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	18.820	Cum	3555.63	66916.96
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	12.81	Cum	4645.08	59503.47
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	8.690	Cum	3993.93	34707.25
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	7.39	Qntl	6174.59	45630.22
7	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	12.350	Cum	3350.59	41379.79
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	15.22	Cum	3383.6	51498.39
9.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-Foundation and plinth	51.85	Sqm	84.41	4376.66
9.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-Beam and Column	26.5	Sqm	517.62	13716.93
10	16mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	86.28	Sqm	133.17	11489.91
11	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty	86.28	Sqm	93.24	8044.75
12	Pre fabricated M.S door>window,grill& Ventilator	291.83	Kg	56.82	16581.78
13	Labour for fitting,fixing pre fabricated M.S Door>window,Grill etc complete	8.22	Sqm	67.40	554.03
14	priming one coat with all primer water bond cement primer including all labour,material,T&P etc.complete	10.38	Sqm	35.37	367.14

**NAME OF WORK :- "CONSTRUCTION OF BOUNDARY WALL & DEVELOPMENT OF ROAD AT KUARMUNDA-VI  
A.W.C KUARMUNDA GP**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
15	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	172.57	Sqm	51.58	8901.16
16	Painting Two coats with approved paint over one coat priming over M.S Door,window and grill,ventillator	10.38	sqm	90.30	937.31
17	Earth filling inside boundary premises borrow from outside including transportation,royalty,levelling complete.	55.92	Cum	290.20	16227.98
18	Collecting,conveying good quality moorum & spreading on road for work including transportation,royalty,taxes etc.complete.	125.00	Cum	537.32	67165.00
19	Cost of RCC sign board with writeing charges with DMF Drawing and Colour	1	Each	3000.00	3000.00
20	<b>TOTAL</b>				<b>464288.26</b>
21	<b>CESS 1%</b>				<b>4612.71</b>
22	<b>TOTAL</b>				<b>468900.97</b>
23					
24	<b>TOTAL</b>				<b>468900.97</b>
				<b>Limited to Rs</b>	<b>468900.00</b>

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**