

TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "SINKING OF TUBE WELL AT KUARMUNDA-VI A.W.C KUARMUNDA GP

Bidder
Name

Less(-)

%

SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate (Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	6.520	Cum	126.70	826.08
2	Filling foundation and plinth with sand well watered and rammed etc complete	2.7	Cum	276.42	746.33
3	Cement Concrete (1:3:6) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	0.940	Cum	3557.71	3344.25
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0.65	Cum	4648.01	3021.21
5	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	1.880	Cum	3351.2	6300.26
6	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	5.19	Sqm	109.03	565.87
Boring					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation (PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				

NAME OF WORK :- "SINKING OF TUBE WELL AT KUARMUNDA-VI A.W.C KUARMUNDA GP

**Bidder
Name**

Less(-)

%

SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate (Rs)	Amount (Rs)
	125mm dia 00 mtr. To 100 mtr	100	Mtr	485.00	48500.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
	Cost of Materials				
4	125 mm dia PVC Casing pipe (Sch 80)	30	Mtr	568.10	17043.00
5	Supplying of Hand pump "KHOSLA" make including all accessories,fitting complete in all respect.	1	Nos	12229.00	12229.00
6	Add for Display board	1	Nos	1772.00	1772.00
TOTAL					99073.86
Cess 1 %					0.00
Total					99074

**Junior Engineer
Kuarmunda Block**

**Asst.Executive Engineer
Kuarmunda Block**

**Block Development Officer
Kuarmunda Block**