

# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "RENOVATION OF GOBIRA KHARUABERNA TANK, KHUKHUNDUBAHAL GP

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

| SL.No | Description of item   | Quantity | Unit | Rate ( Rs) | Amount (Rs)      |
|-------|---|----------|------|------------|------------------|
| 1     | 2   | 3        | 4    | 5          | 6                |
| 1     | clearing and rubbing road land including uprooting rank,vegetation,grass,bushes,shrubs,stumps of trees girth upto 300mm and disposed unserviceable materials up to a lift 100 mtr.  | 1015.00  | Sqm  | 3.87       | 3928.05          |
| 2     | Earth work in slushy soil(in water upto .6m depth requiring the aids of pans and vessels)within 50meter initial lead and 1.5 meter initial lift as per the direction and specification of the department.   | 3260.00  | Cum  | 108.03     | 352177.80        |
| 3     | Earth work in hard soil or gravelly soil with in 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding .30m depth as per the direction of Engineer in charge. | 4304.70  | Cum  | 105.58     | 454490.23        |
| 4     | Earth work excavation in foundation in hard soil with initial lead and lift including rough dressing and levelling the bed etc.complete as directed.  | 16.20    | cum  | 126.69     | 2052.38          |
| 5     | Filling foundation and plinth with sand with well watered and rammed including cost,conveyance,royalty etc. Complete as directed.   | 1.80     | cum  | 329.23     | 592.61           |
| 6     | Cement Concrete (1:3:6) using 2.5cm size HBG metal including Cost,Coveyance, royalty etc complete   | 1.800    | Cum  | 3650.3     | 6570.54          |
| 7     | R.C.C work of M-15 (1:2:4) grade concrete with 20mm & down grade black hard granite stone chips including hosting & laying including cost,conveyance& royalty.  | 5.850    | Cum  | 4687.4     | 27421.29         |
| 8     | Supplying,cutting,bending,binding & straightening & tying the H.Y.S.D reinforcement in proper position including cost of binding wire.  | 2.925    | qtl. | 6162.5     | 18025.31         |
| ##### | Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-Foundation and plinth  | 54.00    | Sqm  | 83.9       | 4530.60          |
| 10    | Add for Display Board(Made from R.C.C& WRITTEN IN ENGLISH & ODIA)   | 1        | EACH | 6000.00    | 6000.00          |
| 11    | <b>TOTAL</b>  |          |      |            | <b>875788.81</b> |
| 12    | Cess 1%   |          |      |            | <b>8757.74</b>   |
| 13    | <b>TOTAL</b>  |          |      |            | <b>884546.55</b> |

**NAME OF WORK :- "RENOVATION OF GOBIRA KHARUABERNA TANK, KHUKHUNDUBAHAL GP**

**Bidder  
Name**

**Less(-)**

**%**

**SCHEDULE OF WORKS**

| <b>SL.No</b>         | <b>Description of item</b> | <b>Quantity</b> | <b>Unit</b> | <b>Rate ( Rs)</b> | <b>Amount (Rs)</b> |
|----------------------|----------------------------|-----------------|-------------|-------------------|--------------------|
| 14                   |                            |                 |             |                   |                    |
| <b>Total</b>         |                            |                 |             |                   | <b>884546.5505</b> |
| <b>Limited to Rs</b> |                            |                 |             |                   | <b>884546.00</b>   |
|                      |                            |                 |             |                   |                    |

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**