

# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "SINKING OF TUBE WELL AT KUARMUNDA-VI A.W.C KUARMUNDA GP

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	6.520	Cum	126.70	826.08
2	Filling foundation and plinth with sand well watered and rammed etc complete	2.7	Cum	276.42	746.33
3	Cement Concrete (1:3:6) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	0.940	Cum	3557.71	3344.25
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0.65	Cum	4648.01	3021.21
5	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	1.880	Cum	3351.2	6300.26
6	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	5.19	Sqm	109.03	565.87

**NAME OF WORK :- "SINKING OF TUBE WELL AT KUARMUNDA-VI A.W.C KUARMUNDA GP**Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
7	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	485.00	48500.00
8	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
9	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
10	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.10	17043.00
11	Supplying of Hand pump "KHOSLA" make including all accessories,fitting complete in all respect.	1	Nos	12229.00	12229.00
12	Add for Display board	1	Nos	1772.00	1772.00
<b>TOTAL</b>					<b>99074</b>
<b>Cess 1 %</b>					<b>990.74</b>
<b>Total</b>					<b>100065</b>
<b>GST 12 %</b>					
<b>Total</b>					<b>100065</b>

**NAME OF WORK :- "SINKING OF TUBE WELL AT KUARMUNDA-VI A.W.C KUARMUNDA GP**

**Bidder  
Name**

**Less(-)**

**%**

**SCHEDULE OF WORKS**

<b>SL.No</b>	<b>Description of item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate ( Rs)</b>	<b>Amount (Rs)</b>
<b>Limited to Rs</b>					
<b>(Rupees one lakh sixty five thousand ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "WIDENING OF ROAD & GUARD WALL FROM R.D ROAD TO DON BOSCO SCHOOL,  
KUARMUNDA GP

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earth work excavation in foundation in hard soil with initial lead and lift including rough dressing and levelling the bed etc.complete as directed.	270.00	cum	126.7	34209.00
2	Filling foundation and plinth with sand with well watered and rammed including cost,conveyance,royalty etc. Complete as directed.	585.00	cum	276.42	161705.70
3	Cement concrete(1:3:6) with 4cm size H.G metal including cost,carriage &royalty of materials etc. Complete as per the direction of Engineer-in -charge.	95.00	cum	3555.63	337784.85
4	Cement Concrete (1:3:6) using 2.5cm size HBG metal including Cost,Coveyance, royalty etc complete	300.000	Cum	3606.13	1081839.00
5	Cement Concrete (1:2:4) using 12mm size HBG chips including Cost,Coveyance, royalty etc complete	126.240	Cum	4645.08	586394.90
12:00 AM	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-Foundation and plinth	2499.9	Sqm	84.41	211016.56
7	Priming one coat with wall primer water bond cement primer including all labours,materials,T&P etc. Complete.	99.9	Sqm	40.02	3998.00
8	Painting two coats with any approved paint in iron works including sand papering,polishing,surface,cost of paint,cost of all labours etc. Complete.	99.9	Sqm	90.3	9020.97
9	Add for Display Board(Made from R.C.C& WRITTEN IN ENGLISH & ODIA)	1	EACH	5110.00	5110.00
10	TOTAL				2431078.98
11	Cess 1%				24280.00
12	TOTAL				2455358.98
13	G.S.T 12%				
Total					2455359.00

**NAME OF WORK :- "WIDENING OF ROAD & GUARD WALL FROM R.D ROAD TO DON BOSCO SCHOOL,  
KUARMUNDA GP**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
(Rupees Twenty four lakhs fifty five thousand three fifty nine) Only					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF CULVERT AT SIHALJORE DAIRTOLA.

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	144.120	Cum	134.43	19374.05
2	Filling foundation and plinth with sand well watered and rammed etc complete	90.00	Cum	269.6	24264.00
3	Cement Concrete (1:3:6) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	31.360	Cum	3784.81	118692
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	11.25	Cum	4894.22	55060
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	3.700	Cum	4189.62	15502
6	RCC work for M-15 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	165.630	Cum	3824.82	633505
7	Supply,cutting,bending,binding of M.S Rod	24.890	Qtl	6220.2	154821
8	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	329.76	Sqm	86.77	28613
9	Cost of 1200mm dia hume pipe	20.00	Rmt	7882	157640.00
10	Transportation of Hume pipe from factory to site.	20.00	Rmt	320.1	6402.00

**NAME OF WORK :- "CONSTRUCTION OF CULVERT AT SIHALJORE DAIRTOLA.**

**Bidder  
Name**

**Less(-)**

**%**

**SCHEDULE OF WORKS**

<b>SL.No</b>	<b>Description of item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate ( Rs)</b>	<b>Amount (Rs)</b>
11	Labour for fixing of 1200mm dia h.p	20.000	Rmt	73.2	1464.00
12	Providing weep holes in Brick masonry/plain/Reinforcement concrete abutment & wing wall/return wall	20	Rmt	79.2	1584.00
13	Provision for diversion & dismantling of existing structure	1	each	7700	7700.00
14	Construction of project pillar& writeing charges.	1	each	4000.00	4000.00

**NAME OF WORK :- "CONSTRUCTION OF CULVERT AT SIHALJORE DAIRTOLA.**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	TOTAL				1228620.25
	GST 12 %				
	Total				1228620.25
<b>(Rupees Twelve Lakhs twenty eight thousand six hundred and twenty ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- Const. of CC road Jamuna Naki Makhan Dash house road ,Jamunanaki,PADAMPUR.

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earth work excavation in foundation in hard soil with initial lead and lift including rough dressing and levelling the bed etc.complete as directed.	165.60	cum	133.1	22041.00
2	Filling foundation and plinth with sand with well watered and rammed including cost,conveyance,royalty etc. Complete as directed.	102.20	cum	330.8	33808.00
3	Cement concrete(1:3:6) with 4cm size H.G metal including cost,carriage &royalty of materials etc. Complete as per the direction of Engineer-in -charge.	137.21	cum	3661.5	502394.00
4	Cement Concrete (1:2:4) using 12mm size HBG chips including Cost,Coveyance, royalty etc complete	101.870	Cum	4760.5	484952.00
12:00 AM	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-Foundation and plinth	334	Sqm	85.4	28524.00
7	Labour for spreading moorum on road surface in layer not exceeding 0.1meter etc	16.7	Sqm	497.5	8308.00
9	Add for Display Board(Made from R.C.C& WRITTEN IN ENGLISH & ODIA)	1	EACH	2500.00	2500.00
	cost of thermocol,photography etc				1000.00
10	TOTAL				1083527.00
11	Cess 1%				12133.00
12	TOTAL				1095660.00
13	G.S.T 12%				0.00
Total					1095660.00
(Rupees Ten lakhs ninety five thousand six hundred sixty ) Only					

**NAME OF WORK :- Const. of CC road Jamuna Naki Makhan Dash house road ,Jamunanaki,PADAMPUR.**

**Bidder  
Name**

**Less(-)**

**%**

**SCHEDULE OF WORKS**

<b>SL.No</b>	<b>Description of item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate ( Rs)</b>	<b>Amount (Rs)</b>
--------------	----------------------------	-----------------	-------------	-------------------	--------------------

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



# TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- Const. of CC road from Mobile factory to saroj house ,Jamunanaki,PADAMPUR.

Bidder  
Name

Less(-)

%

## SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earth work excavation in foundation in hard soil with initial lead and lift including rough dressing and levelling the bed etc.complete as directed.	147.25	cum	133.1	19599.00
2	Filling foundation and plinth with sand with well watered and rammed including cost,conveyance,royalty etc. Complete as directed.	90.88	cum	330.8	30063.00
3	Cement concrete(1:3:6) with 4cm size H.G metal including cost,carriage &royalty of materials etc. Complete as per the direction of Engineer-in -charge.	122.01	cum	3661.5	446740.00
4	Cement Concrete (1:2:4) using 12mm size HBG chips including Cost,Coveyance, royalty etc complete	90.590	Cum	4760.5	431254.00
12:00 AM	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantling then after casting including cost of material complete-Foundation and plinth	297	Sqm	85.4	25364.00
7	Labour for spreading moorum on road surface in layer not exceeding 0.1meter etc	14.85	Sqm	497.5	7388.00
9	Add for Display Board(Made from R.C.C& WRITTEN IN ENGLISH & ODIA)	1	EACH	2500.00	2500.00
	cost of thermocol,photography etc				1000.00
10	<b>TOTAL</b>				<b>963908.00</b>
11	Cess 1%				10793.00
12	<b>TOTAL</b>				<b>974701.00</b>
13	G.S.T 12%				0.00
<b>Total</b>					<b>974701.00</b>
<b>(Rupees Nine lakhs seventy four thousand seven hundred one ) Only</b>					

**NAME OF WORK :- Const. of CC road from Mobile factory to saroj house ,Jamunanaki,PADAMPUR.**

**Bidder  
Name**

**Less(-)**

**%**

**SCHEDULE OF WORKS**

<b>SL.No</b>	<b>Description of item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate ( Rs)</b>	<b>Amount (Rs)</b>
--------------	----------------------------	-----------------	-------------	-------------------	--------------------

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA JHAMANKERA -II.

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	307.4	8037.59
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3339.8	51576.53
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	3997.4	100386.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	22.708	Qntl	6221.90	141286.91
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	225.3	15834.08
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3705.6	108255.40
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3738.90	195241.62
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.89	26515.16
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	54.289	Sqm	86.26	4682.97
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	538.39	23629.94
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA JHAMANKERA -II.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	72.243	Sqm	109.9	7939.51
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	142.6	27650.57
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.937	Sqm	100	36093.70
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	874.90	40997.81
15	Pre fabricated M.S door, window, grill & Ventilator	839.388	Kg	56.60	47509.36
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	892.90	5760.10
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	632.30	11555.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	609.70	5526.93
20	Granite fixing on top	12.1	Sqm	1429.80	17300.58
21	Paver Blocks	11.742	Sqm	498.036	5847.94
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	58.10	23948.30
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	115	2416.38

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA JHAMANKERA -II.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA JHAMANKERA -II.**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	-				29908.55
	<b>TOTAL</b>				<b>1185365.82</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1185366.00</b>
<b>(Rupees Eleven Lakhs Eighty five thousand three hundred and sixty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -III

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	307.4	8037.59
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3339.8	51576.53
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	3997.4	100386.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	22.708	Qntl	6221.90	141286.91
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	225.3	15834.08
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3705.6	108255.40
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3738.90	195241.62
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.89	26515.16
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	54.289	Sqm	86.26	4682.97
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	538.39	23629.94
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -III**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	72.243	Sqm	109.9	7939.51
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	142.6	27650.57
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.937	Sqm	100	36093.70
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	874.90	40997.81
15	Pre fabricated M.S door, window, grill & Ventilator	839.388	Kg	56.60	47509.36
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	892.90	5760.10
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	632.30	11555.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	609.70	5526.93
20	Granite fixing on top	12.1	Sqm	1429.80	17300.58
21	Paver Blocks	11.742	Sqm	498.036	5847.94
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	58.10	23948.30
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	115	2416.38

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -III**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -III**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				29908.55
	<b>TOTAL</b>				<b>1185365.82</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1185366.00</b>
<b>(Rupees Eleven Lakhs Eighty five thousand three hundred and sixty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -IV

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	307.4	8037.59
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3339.8	51576.53
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	3997.4	100386.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	22.708	Qntl	6221.90	141286.91
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	225.3	15834.08
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3705.6	108255.40
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3738.90	195241.62
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.89	26515.16
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	54.289	Sqm	86.26	4682.97
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	538.39	23629.94
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -IV**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	72.243	Sqm	109.9	7939.51
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	142.6	27650.57
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.937	Sqm	100	36093.70
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	874.90	40997.81
15	Pre fabricated M.S door, window, grill & Ventilator	839.388	Kg	56.60	47509.36
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	892.90	5760.10
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	632.30	11555.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	609.70	5526.93
20	Granite fixing on top	12.1	Sqm	1429.80	17300.58
21	Paver Blocks	11.742	Sqm	498.036	5847.94
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	58.10	23948.30
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	115	2416.38

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -IV**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT RAIBOGA -IV**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				29908.55
	<b>TOTAL</b>				<b>1185365.82</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1185366.00</b>
<b>(Rupees Eleven Lakhs Eighty five thousand three hundred and sixty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT GOTITANGAR**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	307.4	8037.59
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3339.8	51576.53
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	3997.4	100386.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	22.708	Qntl	6221.90	141286.91
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	225.3	15834.08
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3705.6	108255.40
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3738.90	195241.62
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.89	26515.16
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	54.289	Sqm	86.26	4682.97
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	538.39	23629.94
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT GOTITANGAR**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	72.243	Sqm	109.9	7939.51
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	142.6	27650.57
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.937	Sqm	100	36093.70
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	874.90	40997.81
15	Pre fabricated M.S door, window, grill & Ventilator	839.388	Kg	56.60	47509.36
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	892.90	5760.10
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	632.30	11555.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	609.70	5526.93
20	Granite fixing on top	12.1	Sqm	1429.80	17300.58
21	Paver Blocks	11.742	Sqm	498.036	5847.94
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	58.10	23948.30
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	115	2416.38

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT GOTITANGAR**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT GOTITANGAR**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				29908.55
	<b>TOTAL</b>				<b>1185365.82</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1185366.00</b>
<b>(Rupees Eleven Lakhs Eighty five thousand three hundred and sixty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN SAGABEDA**

Bidder  
Name

Less(-)

%

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	396.3	10362.06
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3799.5	58675.68
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	4047.4	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	4204.3	105582.59
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	20.088	Qntl	6253.30	125616.29
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	228.8	16080.06
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3880.60	113367.85
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3914.00	204385.17
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.41	26477.27
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	44.485	Sqm	86.13	3831.49
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	537.97	23611.50
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.47	3077.64

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN SAGABEDA**

**Bidder  
Name**

**Less(-)**

**%**

**SCHEDULE OF WORKS**

<b>SL.No</b>	<b>Description of item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate ( Rs)</b>	<b>Amount (Rs)</b>
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	74.382	Sqm	110.1	8189.46
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	141.7	27476.06
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.93655	Sqm	99.3	35841.00
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	871.40	40833.80
15	Pre fabricated M.S door, window, grill & Ventilator	949.9216	Kg	56.60	53765.56
16	SS Railing	20	Kg	325.00	6500.00
17	Fixing of vitrified printed Tiles 600x 600 in dados, skirting and risers of steps on 12mm thick C.M(1:3) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	889.80	5740.10
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	631.00	11531.53
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	606.20	5495.20
20	Granite fixing on top	12.1079	Sqm	1427.50	17284.03
21	Paver Blocks	11.742	Sqm	494.71	5808.93
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	70.80	1309.80
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	77.30	31862.36
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	P.V.C Door for Toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	115.3	2422.68

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN SAGABEDA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
	<b>Cost of Materials</b>				
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	<b>Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)</b>	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN SAGABEDA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any to be paid as per actual</b>				20877.53
	<b>TOTAL</b>				<b>1202677.27</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1202677.00</b>
	<b>(Rupees Twelve Lakhs two thousand six hundred and seventy seven) Only</b>				

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN GHASITOLA**

Bidder  
Name

Less(-)

%

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	396.3	10362.06
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3799.5	58675.68
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	4047.4	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	4204.3	105582.59
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	20.088	Qntl	6253.30	125616.29
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	228.8	16080.06
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3880.60	113367.85
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3914.00	204385.17
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.41	26477.27
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	44.485	Sqm	86.13	3831.49
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	537.97	23611.50
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.47	3077.64

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN GHASITOLA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	74.382	Sqm	110.1	8189.46
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	141.7	27476.06
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.93655	Sqm	99.3	35841.00
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	871.40	40833.80
15	Pre fabricated M.S door, window, grill & Ventilator	949.9216	Kg	56.60	53765.56
16	SS Railing	20	Kg	325.00	6500.00
17	Fixing of vitrified printed Tiles 600x 600 in dados, skirting and risers of steps on 12mm thick C.M(1:3) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	889.80	5740.10
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	631.00	11531.53
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	606.20	5495.20
20	Granite fixing on top	12.1079	Sqm	1427.50	17284.03
21	Paver Blocks	11.742	Sqm	494.71	5808.93
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	70.80	1309.80
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	77.30	31862.36
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	P.V.C Door for Toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	115.3	2422.68

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN GHASITOLA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	<b>Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)</b>	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN GHASITOLA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any to be paid as per actual</b>				20877.53
	<b>TOTAL</b>				<b>1202677.27</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1202677.00</b>
<b>(Rupees Twelve Lakhs two thousand six hundred and seventy seven) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN DARANGAPADA**

Bidder  
Name

Less(-)

%

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	396.3	10362.06
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3799.5	58675.68
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	4047.4	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	4204.3	105582.59
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	20.088	Qntl	6253.30	125616.29
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	228.8	16080.06
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3880.60	113367.85
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3914.00	204385.17
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.41	26477.27
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	44.485	Sqm	86.13	3831.49
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	537.97	23611.50
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.47	3077.64

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN DARANGAPADA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	74.382	Sqm	110.1	8189.46
12	10mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	141.7	27476.06
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.93655	Sqm	99.3	35841.00
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	871.40	40833.80
15	Pre fabricated M.S door, window, grill & Ventilator	949.9216	Kg	56.60	53765.56
16	SS Railing	20	Kg	325.00	6500.00
17	Fixing of vitrified printed Tiles 600x 600 in dados, skirting and risers of steps on 12mm thick C.M(1:3) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	889.80	5740.10
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	631.00	11531.53
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	606.20	5495.20
20	Granite fixing on top	12.1079	Sqm	1427.50	17284.03
21	Paver Blocks	11.742	Sqm	494.71	5808.93
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	70.80	1309.80
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	77.30	31862.36
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	P.V.C Door for Toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	115.3	2422.68

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN DARANGAPADA**Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
	<b>Cost of Materials</b>				
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	<b>Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)</b>	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PUTRIKHAMAN DARANGAPADA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any to be paid as per actual</b>				20877.53
	<b>TOTAL</b>				<b>1202677.27</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1202677.00</b>
	<b>(Rupees Twelve Lakhs two thousand six hundred and seventy seven) Only</b>				

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR RANGIADHIPA.

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.157	Cum	134.40	8891.50
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.516	Cum	307.4	5384.42
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.455	Cum	3333.2	48181.41
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	4047.4	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.299	Cum	4047.4	86204.36
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	18.916	Qntl	6216.70	117595.10
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	228.1	16030.87
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	20.599	Cum	3645.8	75099.83
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	56.004	Cum	3679.10	206044.32
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	335.89	26347.21
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.826	Sqm	86.26	5074.33
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	538.39	22558.54
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR RANGIADHIPA.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost conveyance	71.068	Sqm	110.8	7874.33
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	143.3	24017.37
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	100.6	43094.53
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	875.80	41039.99
15	Pre fabricated M.S door, window, grill & Ventilator	942.843	Kg	56.60	53364.91
16	SS Railing	20	KG	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	893.50	5763.97
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.651	Sqm	634.70	20088.89
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	610.60	5535.09
20	Granite fixing on top	12.11	Sqm	1431.90	17340.31
21	Fixing Chequered in floors treads or steps and landing steps on 20mm thick bed of Cement Motar (1:4) jointed with neat cement slurry	27.606	Sqm	498.04	13748.89
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415.005	Sqm	58.00	24070.29
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	667.045	Sqm	41.80	27882.48
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.642	Sqm	53.60	22492.81
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	P.V.C Door for Toilet	3.36	sqm	1847.49	6207.57
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	58.376	Sqm	116.4	6794.97

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR RANGIADHIPA.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	48	Mtr	655.06	31442.88
5	<b>Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)</b>	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR RANGIADHIPA.**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	Electrical			LS	30000.00
	SANITARY FITTINGS AND PLUMBING ESTIMATE			LS	37304.00
	Other Unforeseen items if any to be paid as per actual			LS	34464.09
	<b>TOTAL</b>				<b>1169429.36</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1169429.36</b>
<b>(Rupees Eleven Lakhs Sixty nine thousand four hundred and twenty nine) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR MUGATOLI.**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.157	Cum	134.40	8891.50
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.516	Cum	307.4	5384.42
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.455	Cum	3333.2	48181.41
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	4047.4	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.299	Cum	4047.4	86204.36
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	18.916	Qntl	6216.70	117595.10
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	228.1	16030.87
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	20.599	Cum	3645.8	75099.83
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	56.004	Cum	3679.10	206044.32
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	335.89	26347.21
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.826	Sqm	86.26	5074.33
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	538.39	22558.54
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR MUGATOLI.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost conveyance	71.068	Sqm	110.8	7874.33
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc. Ground floor	167.602	Sqm	143.3	24017.37
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc. Ground floor	428.375	Sqm	100.6	43094.53
14	Fixing of vitrified printed Tiles 600x 600 in floors,tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing,polishing	46.86	Sqm	875.80	41039.99
15	Pre fabricated M.S door>window,grill& Ventilator	942.843	Kg	56.60	53364.91
16	SS Railing	20	KG	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors,tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing,polishing	6.451	Sqm	893.50	5763.97
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixedwith pigment to match the shades	31.651	Sqm	634.70	20088.89
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixedwith pigment to match the shades	9.065	Sqm	610.60	5535.09
20	Granite fixing on top	12.11	Sqm	1431.90	17340.31
21	Fixing Chequered in floors treads or steps and landing steps on 20mm thick bed of Cement Motar (1:4) jointed with neat cement slurry	27.606	Sqm	498.04	13748.89
22	Labour for fitting,fixing pre fabricated M.S Door>window,Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty(water based)of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415.005	Sqm	58.00	24070.29
24	priming one coat with all primer water bond cement primer including all labour,material,T&P etc.complete	667.045	Sqm	41.80	27882.48
25	Wall painting with two coats plasticemulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.642	Sqm	53.60	22492.81
27	Painting Two coats with approved paint over one coat priming over M.S Door>window and grill,ventillator	20.3	sqm	94.40	1916.32
28	P.V.C Door for Toilet	3.36	sqm	1847.49	6207.57
29	Cost of RCC sign board with writeing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	58.376	Sqm	116.4	6794.97

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR MUGATOLI.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	48	Mtr	655.06	31442.88
5	<b>Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)</b>	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR MUGATOLI.**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	Electrical			LS	30000.00
	SANITARY FITTINGS AND PLUMBING ESTIMATE			LS	
	Other Unforeseen items if any to be paid as per actual			LS	34464.09
	<b>TOTAL</b>				<b>1132125.36</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1132125.36</b>
<b>(Rupees Eleven Lakhs Sixty nine thousand four hundred and twenty nine) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR KHADIAPADA.**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.157	Cum	134.40	8891.50
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.516	Cum	307.4	5384.42
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.455	Cum	3333.2	48181.41
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	4047.4	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.299	Cum	4047.4	86204.36
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	18.916	Qntl	6216.70	117595.10
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	228.1	16030.87
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	20.599	Cum	3645.8	75099.83
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	56.004	Cum	3679.10	206044.32
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	335.89	26347.21
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.826	Sqm	86.26	5074.33
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	538.39	22558.54
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR KHADIAPADA.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	71.068	Sqm	110.8	7874.33
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	143.3	24017.37
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	100.6	43094.53
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	875.80	41039.99
15	Pre fabricated M.S door, window, grill & Ventilator	942.843	Kg	56.60	53364.91
16	SS Railing	20	KG	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	893.50	5763.97
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.651	Sqm	634.70	20088.89
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	610.60	5535.09
20	Granite fixing on top	12.11	Sqm	1431.90	17340.31
21	Fixing Chequered in floors treads or steps and landing steps on 20mm thick bed of Cement Motar (1:4) jointed with neat cement slurry	27.606	Sqm	498.04	13748.89
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415.005	Sqm	58.00	24070.29
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	667.045	Sqm	41.80	27882.48
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.642	Sqm	53.60	22492.81
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	P.V.C Door for Toilet	3.36	sqm	1847.49	6207.57
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	58.376	Sqm	116.4	6794.97

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR KHADIAPADA.**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	48	Mtr	655.06	31442.88
5	<b>Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)</b>	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT PRATAPPUR KHADIAPADA.**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	Electrical			LS	30000.00
	SANITARY FITTINGS AND PLUMBING ESTIMATE			LS	37304.00
	Other Unforeseen items if any to be paid as per actual			LS	34464.09
	<b>TOTAL</b>				<b>1169429.36</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1169429.36</b>
<b>(Rupees Eleven Lakhs Sixty nine thousand four hundred and twenty nine) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-PAHARTOLI**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.137	Cum	134.40	8888.81
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.51	Cum	636.3	11141.61
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.449	Cum	3583.7	51780.88
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.296	Cum	4331.8	92248.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	17.036	Qntl	6253.30	106531.22
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	236.1	16593.11
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	14.765	Cum	3705.6	54713.18
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	55.624	Cum	3826.40	212839.67
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	340.02	26671.17
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.824	Sqm	87.33	5137.10
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	541.93	22706.87
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.05	3071.62

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-PAHARTOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	71.068	Sqm	110.2	7831.69
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	147	24637.49
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	103.7	44422.49
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	884.60	41452.36
15	Pre fabricated M.S door, window, grill & Ventilator	865.373	Kg	56.60	48980.11
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	902.00	5818.80
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.65	Sqm	643.20	20357.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	619.40	5614.86
20	Granite fixing on top	12.1	Sqm	1440.70	17432.47
21	Paver Blocks	27.6	Sqm	498.036	13745.79
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415	Sqm	58.00	24070.00
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	415	Sqm	41.80	17347.00
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.64	Sqm	53.60	22492.70
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	120.3	2527.74

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-PAHARTOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	655.06	19651.80
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-PAHARTOLI**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				65608.00
	<b>TOTAL</b>				<b>1164285.51</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1164286.00</b>
<b>(Rupees Eleven Lakhs Sixty four thousand two hundred and eighty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KHADIATOLI**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.137	Cum	134.40	8888.81
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.51	Cum	636.3	11141.61
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.449	Cum	3583.7	51780.88
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.296	Cum	4331.8	92248.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	17.036	Qntl	6253.30	106531.22
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	236.1	16593.11
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	14.765	Cum	3705.6	54713.18
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	55.624	Cum	3826.40	212839.67
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	340.02	26671.17
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.824	Sqm	87.33	5137.10
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	541.93	22706.87
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.05	3071.62

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KHADIATOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	71.068	Sqm	110.2	7831.69
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	147	24637.49
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	103.7	44422.49
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	884.60	41452.36
15	Pre fabricated M.S door, window, grill & Ventilator	865.373	Kg	56.60	48980.11
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	902.00	5818.80
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.65	Sqm	643.20	20357.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	619.40	5614.86
20	Granite fixing on top	12.1	Sqm	1440.70	17432.47
21	Paver Blocks	27.6	Sqm	498.036	13745.79
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415	Sqm	58.00	24070.00
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	415	Sqm	41.80	17347.00
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.64	Sqm	53.60	22492.70
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	120.3	2527.74

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KHADIATOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	655.06	19651.80
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KHADIATOLI**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				65608.00
	<b>TOTAL</b>				<b>1164285.51</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1164286.00</b>
<b>(Rupees Eleven Lakhs Sixty four thousand two hundred and eighty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KADOMUNDA**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.137	Cum	134.40	8888.81
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.51	Cum	636.3	11141.61
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.449	Cum	3583.7	51780.88
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.296	Cum	4331.8	92248.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	17.036	Qntl	6253.30	106531.22
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	236.1	16593.11
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	14.765	Cum	3705.6	54713.18
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	55.624	Cum	3826.40	212839.67
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	340.02	26671.17
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.824	Sqm	87.33	5137.10
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	541.93	22706.87
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.05	3071.62

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KADOMUNDA**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	71.068	Sqm	110.2	7831.69
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	147	24637.49
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	103.7	44422.49
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	884.60	41452.36
15	Pre fabricated M.S door, window, grill & Ventilator	865.373	Kg	56.60	48980.11
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	902.00	5818.80
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.65	Sqm	643.20	20357.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	619.40	5614.86
20	Granite fixing on top	12.1	Sqm	1440.70	17432.47
21	Paver Blocks	27.6	Sqm	498.036	13745.79
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415	Sqm	58.00	24070.00
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	415	Sqm	41.80	17347.00
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.64	Sqm	53.60	22492.70
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	120.3	2527.74

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KADOMUNDA**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	655.06	19651.80
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-KADOMUNDA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				65608.00
	<b>TOTAL</b>				<b>1164285.51</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1164286.00</b>
<b>(Rupees Eleven Lakhs Sixty four thousand two hundred and eighty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-II

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.137	Cum	134.40	8888.81
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.51	Cum	636.3	11141.61
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.449	Cum	3583.7	51780.88
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.296	Cum	4331.8	92248.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	17.036	Qntl	6253.30	106531.22
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	236.1	16593.11
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	14.765	Cum	3705.6	54713.18
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	55.624	Cum	3826.40	212839.67
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	340.02	26671.17
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.824	Sqm	87.33	5137.10
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	541.93	22706.87
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.05	3071.62

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-II**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	71.068	Sqm	110.2	7831.69
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	147	24637.49
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	103.7	44422.49
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	884.60	41452.36
15	Pre fabricated M.S door, window, grill & Ventilator	865.373	Kg	56.60	48980.11
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	902.00	5818.80
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.65	Sqm	643.20	20357.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	619.40	5614.86
20	Granite fixing on top	12.1	Sqm	1440.70	17432.47
21	Paver Blocks	27.6	Sqm	498.036	13745.79
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415	Sqm	58.00	24070.00
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	415	Sqm	41.80	17347.00
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.64	Sqm	53.60	22492.70
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	120.3	2527.74

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-II**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	655.06	19651.80
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-II**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				65608.00
	<b>TOTAL</b>				<b>1164285.51</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1164286.00</b>
<b>(Rupees Eleven Lakhs Sixty four thousand two hundred and eighty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BUNDULTOLI**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.137	Cum	134.40	8888.81
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.51	Cum	636.3	11141.61
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.449	Cum	3583.7	51780.88
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.296	Cum	4331.8	92248.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	17.036	Qntl	6253.30	106531.22
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	236.1	16593.11
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	14.765	Cum	3705.6	54713.18
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	55.624	Cum	3826.40	212839.67
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	340.02	26671.17
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.824	Sqm	87.33	5137.10
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	541.93	22706.87
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.05	3071.62

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BUNDULTOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	71.068	Sqm	110.2	7831.69
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	147	24637.49
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	103.7	44422.49
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	884.60	41452.36
15	Pre fabricated M.S door, window, grill & Ventilator	865.373	Kg	56.60	48980.11
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	902.00	5818.80
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.65	Sqm	643.20	20357.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	619.40	5614.86
20	Granite fixing on top	12.1	Sqm	1440.70	17432.47
21	Paver Blocks	27.6	Sqm	498.036	13745.79
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415	Sqm	58.00	24070.00
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	415	Sqm	41.80	17347.00
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.64	Sqm	53.60	22492.70
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	120.3	2527.74

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BUNDULTOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	655.06	19651.80
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BUNDULTOLI**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				65608.00
	<b>TOTAL</b>				<b>1164285.51</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1164286.00</b>
<b>(Rupees Eleven Lakhs Sixty four thousand two hundred and eighty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BHAKTATOLI**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	66.137	Cum	134.40	8888.81
2	Filling foundation and plinth with sand well watered and rammed etc complete	17.51	Cum	636.3	11141.61
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	14.449	Cum	3583.7	51780.88
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	21.296	Cum	4331.8	92248.71
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	17.036	Qntl	6253.30	106531.22
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	236.1	16593.11
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	14.765	Cum	3705.6	54713.18
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	55.624	Cum	3826.40	212839.67
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.44	Sqm	340.02	26671.17
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	58.824	Sqm	87.33	5137.10
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	41.9	Sqm	541.93	22706.87
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	214.05	3071.62

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BHAKTATOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	71.068	Sqm	110.2	7831.69
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	167.602	Sqm	147	24637.49
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	428.375	Sqm	103.7	44422.49
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	884.60	41452.36
15	Pre fabricated M.S door, window, grill & Ventilator	865.373	Kg	56.60	48980.11
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	902.00	5818.80
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	31.65	Sqm	643.20	20357.28
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	619.40	5614.86
20	Granite fixing on top	12.1	Sqm	1440.70	17432.47
21	Paver Blocks	27.6	Sqm	498.036	13745.79
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	415	Sqm	58.00	24070.00
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	415	Sqm	41.80	17347.00
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	247.403	Sqm	59.10	14621.52
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	419.64	Sqm	53.60	22492.70
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	20.3	sqm	94.40	1916.32
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	120.3	2527.74

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BHAKTATOLI**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	655.06	19651.80
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT JHUNMUR-BHAKTATOLI**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				65608.00
	<b>TOTAL</b>				<b>1164285.51</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1164286.00</b>
<b>(Rupees Eleven Lakhs Sixty four thousand two hundred and eighty six ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-PASCHIMPADA**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	307.4	8037.59
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3288.6	50785.85
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	3949.4	99181.28
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	22.708	Qntl	6221.90	141286.91
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	224.3	15763.80
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3670.1	107218.30
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3703.40	193387.84
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.89	26515.16
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	54.289	Sqm	86.26	4682.97
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	538.39	23629.94
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-PASCHIMPADA**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	72.243	Sqm	109.6	7917.83
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	142	27534.23
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.937	Sqm	99.5	35913.23
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	873.00	40908.78
15	Pre fabricated M.S door, window, grill & Ventilator	839.388	Kg	56.60	47509.36
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	889.50	5738.16
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	630.70	11526.04
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	607.80	5509.71
20	Granite fixing on top	12.1079	Sqm	1429.10	17303.40
21	Paver Blocks	11.742	Sqm	498.036	5847.94
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	58.10	23948.30
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	114.5	2405.87

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-PASCHIMPADA**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-PASCHIMPADA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				29908.55
	<b>TOTAL</b>				<b>1179924.96</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1179914.00</b>
<b>(Rupees Eleven Lakhs Seventy nine thousand Nine hundred and fourteen ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**



## TENDER SCHEDULE

TENDER INVITING AUTHORITY-BLOCK DEVELOPMENT OFFICER ,KUARMUNDA

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-DHENGURBEDA**

Bidder Name Less(-) %

### SCHEDULE OF WORKS

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
1	2	3	4	5	6
1	Earthwork in excavation in foundation in hardsoil within initial lead and lift including rough dressing and breaking clods to max 5cm to 7cm and laying in layers not exceeding 0.30m in depth etc complete	71.836	Cum	134.40	9654.76
2	Filling foundation and plinth with sand well watered and rammed etc complete	26.147	Cum	307.4	8037.59
3	Cement Concrete (1:4:8) using 40mm size HBG metal including Cost,Coveyance, royalty etc complete	15.443	Cum	3288.6	50785.85
4	C.C (1:2:4) with 12mm and down grade C.B Chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator	0	Cum	0	0.00
5	RCC work for M-20 using 20mm and down graded h.g chips with cost,conveyance and royalty etc.complete	25.113	Cum	3949.4	99181.28
6	Labour charges forreinforcement for Rcc works includingcutting,bending,binding &tying the grills placing in position including cost of binding wire 18 to20mm gauge & cost of MS rod.	22.708	Qntl	6221.90	141286.91
7	2.5 cm thick grading concrete with C.C (1:2:2)with 6mm hg chips	70.28	Sqm	224.3	15763.80
8	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. A- foundation	29.214	Cum	3670.1	107218.30
9	Fly Ash brick masonry in CM(1:6) in using 23cmx11cmx8cm size brick including cost,conveyance,taxes,royalty labour & T&P etc complete. B- Super structure	52.219	Cum	3703.40	193387.84
10.A	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-slab/chajja/Balcony	78.94	Sqm	335.89	26515.16
10.B	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Foundation and plinth	54.289	Sqm	86.26	4682.97
10 C	Rigid smooth centering &shuttering for R.C.C Work including false work &dismantaling then after casting including cost of material complete-Beam and Column	43.89	Sqm	538.39	23629.94
10 D	Rigid & smooth centering & shuttering for Rcc work including False work & dismantling then after casting including cost of material complete. B-lintel	14.35	Sqm	211.18	3030.43

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-DHENGURBEDA**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost convenience	72.243	Sqm	109.6	7917.83
12	20mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	193.903	Sqm	142	27534.23
13	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering, curing, cost, conveyance, taxes & royalty complete etc. Ground floor	360.937	Sqm	99.5	35913.23
14	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	46.86	Sqm	873.00	40908.78
15	Pre fabricated M.S door, window, grill & Ventilator	839.388	Kg	56.60	47509.36
16	SS Railing	20	Kg	325.10	6502.00
17	Fixing of vitrified printed Tiles 600x 600 in floors, tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing, polishing	6.451	Sqm	889.50	5738.16
18	Fixing Colour Galzed tiles in walls on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	18.275	Sqm	630.70	11526.04
19	Fixing Colour Galzed tiles in Floors on 12mm thick Cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades	9.065	Sqm	607.80	5509.71
20	Granite fixing on top	12.1079	Sqm	1429.10	17303.40
21	Paver Blocks	11.742	Sqm	498.036	5847.94
22	Labour for fitting, fixing pre fabricated M.S Door, window, Grill etc complete	18.5	Sqm	68.10	1259.85
23	Finishing wall surface with Acrylic wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding	412.191	Sqm	58.10	23948.30
24	priming one coat with all primer water bond cement primer including all labour, material, T&P etc. complete	627.082	Sqm	41.80	26212.03
25	Wall painting with two coats plastic emulsion paint of Approved shade on new work	218.289	Sqm	59.10	12900.88
26	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	408.794	Sqm	53.60	21911.36
27	Painting Two coats with approved paint over one coat priming over M.S Door, window and grill, ventilator	34.76	sqm	94.40	3281.34
28	PVC door for toilet	3.36	sqm	1847.40	6207.26
29	Cost of RCC sign board with writing charges with DMF Drawing and Colour				4000.00
30	12mm thick cement plaster in cement mortar (1:4) over brick masonry with neat cement punning	21.012	Sqm	114.5	2405.87

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-DHENGURBEDA**

Bidder Name Less(-) %

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
<b>Boring</b>					
1	Labour for drilling & perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and unconsolidated Rock with down the hole Hammer drilling rigs or combination drilling rigs as required to suit the site conditions as per the direction of Engineer-in-charge including use of own Rigs with its accessories T&P and consumable etc. for lowering of 125 mm dia PVC pipes/ G.I. pipes for hoisting fitted with socket and with or without well screens as per the necessity for the soft, medium and hard formation ( PVC/GI pipes casing pipes if required to prevent collaps or the over burden is to be provided by the contractor including lowering and with drawing after completion of the tube well.				
	125mm dia 00 mtr. To 100 mtr	100	Mtr	480.00	48000.00
2	Lowering the following size G.I/PVC pipes with or without slotted pipes as per the necessity from G.I. up to 30 mtr. Depth and fitted and fixed up imperfectly vertical position, including cutting and threading pipes and slotted pipe and supplying and fixing all ljoining materials, T&P etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign matters from above.				
	125mm dia PVC Casing pipe	30	Mtr	72.00	2160.00
3	Cleaning and developing the tube well with their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipmennts and labours as per the direction of Engineer-in-charge.				
	(a) For one tube well	1	Each	2000.00	2000.00
<b>Cost of Materials</b>					
4	125 mm dia PVC Casing pipe ( Sch 80 )	30	Mtr	568.00	17040.00
5	Supply fitting fixing and installation of 1 Hp Summersible Pump with all respective like (PVC pipe, Cabale, Electric Panel, Row Boring, Cap etc)	1	Nos	16000	16000.00

**NAME OF WORK :- "CONSTRUCTION OF AWC BUILDING AT ANDHARI-DHENGURBEDA**

Bidder  
Name

Less(-)

%

**SCHEDULE OF WORKS**

SL.No	Description of item	Quantity	Unit	Rate ( Rs)	Amount (Rs)
	<b>Electrical</b>				30000.00
	<b>SANITARY FITTINGS AND PLUMBING ESTIMATE</b>				37304.00
	<b>Add for Unforeseen items if any</b>				29908.55
	<b>TOTAL</b>				<b>1179924.96</b>
	<b>GST 12 %</b>				
	<b>Total</b>				<b>1179914.00</b>
<b>(Rupees Eleven Lakhs Seventy nine thousand Nine hundred and fourteen ) Only</b>					

**Junior Engineer  
Kuarmunda Block**

**Asst.Executive Engineer  
Kuarmunda Block**

**Block Development Officer  
Kuarmunda Block**

