

Name of the Work "Construction of AWC Building at Telendihi ,Dumabahal G.P.

TENDER SCHEDULE

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work excavation in foundation in hard soil within initial lead 50m. & lift 1.5 m. including rough dressing, breaking clods, laying in layers. Etc. Complete	cum	96.27	184.60	17771.00
2	Filling F & P with sand, well watered and rammed with cost, carriage and royalty etc. complete	cum	64.67	319.40	20656.00
3	Cement Concrete in (1:3:6) using 40mm. Size H.G. metal including laying compacting, Curing with cost, carriage and royalty etc. complete	cum	20.490	5027.50	103013.00
4	R.C.C. M-20 Grade With 20mm and down Grade C.B. Chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator watering, curing and cost of all materials and labour, T & P etc Complete but excluding cost of reinforcement complete.	cum	30.310	5176.10	156888.00
5	Labour for straightening , Cutting, bending & binding the M.S. Road including cost of binding wire and cost of MS Road	Qtnl	28.000	8021.10	224591.00
6	Rigid and smooth centering and shuttering for R.C.C. work and dismantling then after casting including cost of all materials complete				
	(A) Mass Concrete	Sqm	102.650	99.90	10255.00
	(B) Column & Beam	Sqm	69.638	718.50	50035.00
	(C) Lintel	Sqm	15.803	258.70	4088.00
	(D) Roof slab & Chajja	Sqm	87.914	419.70	36898.00
7	Brick work with Fly Ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75kg/cm ² with dimensional tolerance ± 8 Percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	cum	22.13	4178.70	92475.00
8	Fly ash Brick Masonry in C.M. (1:6) with all Finishing, Curing in superstructure etc. complete	cum	58.98	4212.00	248424.00

9	16mm thick C.P. in C.M. (1:6) over brick masonry to the rough surface including watering, curing cost, Carriage, royalty and taxes of all materials, cost of all labour, T&P	Sqm	108.601	194.70	21145.00
10	12mm thick C.P. in C.M (1:6) Over brick Masonary to the smooth surface including watering, Curing, cost, carriage, royalty and taxes of all materials, cost of all labour T&P	Sqm	410.76	136.70	56151.00
11	6mm thick cement plaster (1:4) to RCC surfaces finisher smooth including closed deep chipping and slurry treatment, watering, curing cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	Sqm	82.32	151.30	12455.00
12	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conformaing to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials labour T&P etc required	Sqm	77.92	946.00	73712.00
13	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqm	18.08	1044.40	18883.00
14	C.C (1:2:4) with 12 mm and down cbhg chips including cost,carriage and royalty etc complete.	cum	1.758	6272.10	11026.00
15	Fixing glazed tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	Sqm	17.194	738.00	12689.00
16	Granite fixing above 0.10 to 0.40 sqm on Cement Plaster (1:4)	Sqm	11.713	1516.50	17763.00

17	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	RM	6.00	3495.10	20971.00
18	Paver Blocks	Sqm	9.85	579.20	5705.00
19	2.5cm thic grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken Granite chips on new work including watering curing cost of all materials water- proofing compounds, T&P required for the works etc complete	Sqm	31.68	303.40	9612.00
20	Roofing with an Flat tiles and cement mortar (1:6) boarders 23 cmx5 cm at 1.80 mt intervals,complete per 1 sqm.	Sqm	36.94	500.70	18495.00
21	Priming 1 coat with wall primer water bond cement primer including all labour, Materials, T&P etc Complete	Sqm	240.73	57.80	13914.00
22	Finishing to the exposed surfaces of wall with weather coat of any approved shade	Sqm	240.73	70.70	17020.00
23	MS-Gate	Kg	110.534	56.60	6256.00
24	Enamel paint for Door	Sqm	4.8	133.00	638.00
25	Plastering with cement punning	Sqm	21.012	154.40	3244.00
26	Display Board	No.	1	4812.00	4812.00
Total					1289585.00

Bore well

27	Labour for drilling of perfectly vertical bore hole of specified dia for a specified depth below ground level through consolidated and un-consolidated rock with down the hole hammer drilling rigs of combination drilling rigs required to suit the site conditions as per the direction of Engineer-in-charge including supply of rigs with its accessories, T&P & consumable etc. for lowering 125mm dia PVC pipes or GI pipes for housing fitted with socket and with or without well screens as per the necessity for the soft medium and hard formation (PVC/GI) pipe casing pipes if required to prevent collapse of the over burden is to be provided by the contractor including lowering and with drawing after completion of the Tube Well.				
----	---	--	--	--	--

	125mm dia oomtr 100th mtr	100.00	mtr	480.00	48000.00
28	Lowering the following size PVC/GI pipe with or without slotted pipes as per the necessity from 0 mtr. up to 30 mtr. depth, fitted & fixed up in perfectly vertical position, including cutting & threading pipe & slotted pipe & supplying & fixing all jointing materials T&P etc. complete & keeping the top of the casing pipe threaded including plugging Tube Wells to prevent entry of foreign matters from above.				
	125 mm dia PVC casing pipe	30.00	mtr	72.00	2160.00
29	Clearing and developing the Tube Wells with their own compressor continuously worked till clear and adequate discharge is obtained from the Tube Well including supply of and us of all necessary equipments and labour as per the direction of Engineer-in-charge.	1	each	2000.00	2000.00
30	125mm PVC-sch 80-ASTM Casing pipe	30	mtr	568.00	17040.00
31	Supply Fitting, Fixing & Installation 1 HP Submersible pump with all accessories	1	no	25000.00	25000.00

94200.00
1383785.00
 1383785.00
1383785.00

Limited to
 (Extra CGST&SGST Will paid as applicable)

The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender document will be rejected.

My/Our quoted rate is _____%(Figure) _____ (In words)

***Less than/Excess over/ Equal to the amount put to tender.**

Total number of Items:.....	
Number of Corrections:.....	
Number of interpolation:.....	
Number of over writings:.....	
E.M.D Funnished/EMD Exempted	
(A)Demand Draft No.....	
(B)Ammount Rs.....	
Copy of PAN card:furnished/not furnished	
Copy of GST Registration:furnished/not furnished	
Copy of Contractor's Licecence:furnished/not furnished	
Copy of Experience certificate:furnished/not furnished	
Total No of sheets in the Tender Papers:.....	

Full Signature of Contractor

Signature of the Bidder/Tenderer

**Signature of the B.D.O
Lephripara**