

BOQ**Establishment of SC HWC building (FF) at Jamtalia of Sadar block under PIP of Sundargarh district for the year 2020-21**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Dismantling and removing R.C.C. columns beams slab staircase landing lintels including stacking the useful materials for reuse and removing the debris within 50m lead as per the direction of Engineer-in-charge.	0.41	Cum	1126.90	462.03
2	R.C.C. M-25 grade with 20mm and down grade C.B. chips including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P centering shuttering etc complete but cost of reinforcement complete as per the direction of Engineer-in-charge.				
	(A) Lintel	1.09	Cum	9636.00	10503.24
	(B) Chajja	4.65	Sqm	895.20	4162.68
	(C) Column in Superstructure, Beam	4.11	Cum	12151.80	49943.90
	(D) Roof Slab	8.58	Cum	10316.40	88514.72
3	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steelas per the direction of Engineer-in-charge.	15.99	Qntl	6109.80	97695.71
4	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 2 percent in cement mortar (1:6) in Superstructure including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of Engineer-in-charge.	14.16	Cum	4352.50	61631.40
5	Supplying M.S Door made out with ms flat , angle of approved design & specification including cost of all materials cost of manufacture, cost of one coat of primer, all taxes T&P etc complete as per the direction of Engineer-in-charge.	95.20	Kgs	72.00	6854.40
6	Supplying M.S Window made out with ms flat , angle of approved design & specification including cost of all materials cost of manufacture, cost of one coat of primer, all taxes T&P etc complete as per the direction of Engineer-in-charge.	324.00	Kgs	76.00	24624.00
7	Labour charge for fitting ,fixing of M.S door,window, grill , Gate including all cost etc complete as per the direction of Engineer-in-charge.	9.29	Sqm	68.10	632.65

8	12mm thick C.P. in C.M.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of Engineer-in-charge.	97.97	Sqm	134.10	13137.78
9	16mm thick C.P. in C.M.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of Engineer-in-charge.	125.74	Sqm	192.10	24154.66
10	Supplying, fitting and fixing Vetrified tile in floors treads or steps and landing of size 600mm x 600mm Coloured /Printed series (Homogeneous) laid on 25mm thick cement mortar (1:1) 1cement:1 course sand and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of Engineer-in-charge.	40.61	Sqm	1303.40	52931.08
11	Supplying, fitting and fixing Glazed tile in floors treads or steps and landing of size 30cmx30cm / 40cm x 40cm (special plain/printed series ceramic tiles) laid on 25mm thick cement mortar (1:1) 1cement:1 course sand and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of Engineer-in-charge.	5.84	Sqm	1038.20	6063.09
12	Supplying, fitting and fixing Vetrified tile of size 600mm x 600mm Coloured /Printed series (Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including all costs complete as per the direction of Engineer-in-charge.	4.69	Sqm	1047.10	4910.90
13	Fixing Glazed tiles (20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including all costs complete as per the direction of Engineer-in-charge.	18.74	Sqm	740.80	13882.60
14	Providing fitting, fixing of Aluminium door with anodized Al. door section of 9202 as vertical member, 9201 as top, 9200 as bottom and middle member with frame section as 9221with tapered clip No. 4660 and the frame to be completed by means of jointing angle No. 1855 including all cost of labour, T&P, hire charges of drilling machine, labour charges etc. complete excluding cost of laminated board.	42.00	Kg	459.40	19294.80

15	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T.& P. required for the works etc complete as per the direction of Engineer-in-charge.	58.81	Sqm	322.00	18936.82
16	Painting 2 coats with any approved paint in new iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of Engg-in charge.	24.26	Sqm	137.30	3330.90
17	Priming 1 coat with wall primer (water bond) of any approved shade including all costs complete as per the direction of Engineer-in-charge.	153.01	Sqm	58.70	8981.69
18	Distempering 2 coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper and labour, T & P. etc complete. as per direction of Engineer-in-charge.	153.01	Sqm	63.80	9762.04
19	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc complete as per the direction of Engineer-in-charge.	97.97	Sqm	132.30	12961.44
20	Fixing water closet Porcelain pan (Indian type W.C pan) confirming to IS 2556:Part 3-2004 duly embeded in cement concrete 1:4:8 (using hbg metal 4 cm size) all complete as per P.H specification.				
(i)	580 x440mm size Orissa Pan (White)	1.00	Nos	2772.60	2772.60
21	Fixing of Brass Screw -Down Bib Cocks (Tap) Polished bright confirming to IS:781-1995 of the following nominal sizes as per specification complete.				
(i)	15 mm dia C.P. Brass Short Body Bib Cock	2.00	Nos	672.10	1344.20
(ii)	15 mm diameter Pillar cock	1.00	Nos	696.90	696.90
22	Fixing of Brass or C.P screw down stop cocks/ concealed stop cock/ angle stop cocks confirming to IS: 781-1995 of the following nominal sizes as per P.H specification complete.				
(i)	15 mm dia Brass Screw- down Stop Cock	1.00	Nos	656.00	656.00
(ii)	125mm CP grating	3.00	Nos	72.90	218.70
23	Fixing Wash Basins with hole for Pillar Taps confirming to IS 2556:Part 4-2004 with Cast Iron or M.S brackets painted white including cutting holes in walls and making good the damages etc all complete as per P.H specification.				
(i)	Vitreous China flat back Wash Hand Basin of size 550 mm x 400 mm	1.00	Nos	2863.80	2863.80

24	Providing and fixing to wall or ceiling and floor Chlorinated Polyvinyl Chloride (CPVC) Pipes conforming to IS: 15778 of the following nominal bore with clamp including making good the damages to wall ,ceiling & floor etc complete as per specification as per direction of Engineer in Charge.				
(i)	15 mm nominal outer dia pipe	15.00	Mtrs	166.80	2502.00
(ii)	25 mm nominal outer dia pipe	15.00	Mtrs	297.00	4455.00
25	Providing and laying in trenches PVC pipe (4Kg/cm2) as sewer line and alining to requisite gradients inside the trench, jointing with solvent cement with 0.08m sand filling in bed , 0.10m C.C (1:4:8) using 40 mm size hbg metal in bed & for intermediate pillar including lowering the pipes to the bed of trench, Earthwork in excavation in all kind of soil ,Filling the trenches with excavated earth with watering and ramming and removal of surplus earth, testing of sewer line etc. complete as per the direction of Engineer.in charge..				
(i)	75 mm PVC Pipe	8.00	Mtrs	819.80	6558.40
(ii)	110 mm PVC Pipe	8.00	Mtrs	861.00	6888.00
26	Supplying all materials, labour, T&P and fitting and fixing U-PVC, SWR soil waste ventilating pipes and fitting of the following outside diameter conforming to 13592/1992 to walls with nails bobbins and wooden plugs or laying in trenches including with supply of approved rubber lubricant by non-heat application method as per manufactures specification testing earth work in excavation in all kinds of soil and refilling of trenches all complete as per specification and direction of Engineer.in charge.				
(i)	110 mm U-PVC Pipe	3.00	Mtrs	284.20	852.60
(ii)	110 mm U-PVC 'P' trap	2.00	Each	294.20	588.40
(iii)	110 mm U-PVC door bend	4.00	Each	302.10	1208.40
(iv)	110 mm U-PVC Plain bend	7.00	Each	287.10	2009.70
(v)	110 mm U-PVC Cowl	3.00	Each	38.40	115.20
(vi)	110 mm U-PVC Coupler	8.00	Each	130.30	1042.40
(vii)	75 mm U-PVC Plain bend	8.00	Each	163.80	1310.40
(viii)	75 mm U-PVC Coupler	8.00	Each	97.60	780.80
27	Fixing 15 mm dia PVC inlet connection pipe and making connection with pillar cocks and supply main for wash basin complete as per specification. & direction of Engineer-in-charge.				
(i)	15mm dia	1.00	Nos	195.40	195.40
28	Fixing PVC Waste Pipe of the following diameter for sink or wash basin including brass check nut complete as per specification & direction of Engineer-in-charge.				
(i)	32mm dia	1.00	Nos	174.50	174.50

29	Fixing chromium plated Brass waste of the following nominal diameter for wash basin and sink as per specification & direction of Engineer-in-charge.				
(i)	32mm dia	1.00	Nos	409.70	409.70
30	Cutting holes through existing brick work including making good the same in cement mortar (1: 4) for taking G.I / P.V.C pipes and fittings all complete as per specification & direction of Engineer-in-charge.				
(i)	250 mm thick wall	6.00	Nos	47.40	284.40
(ii)	375 mm thick wall	4.00	Nos	71.10	284.40
31	Recessed wiring to light point / fan point / exhaust fan point / call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite mm dia non-metalic PVC conduit with 5 cover of suitable size, MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accesories and connection as per direction of Engineer in Charge.				
	Group (A)	9.00	Nos	584.20	5257.80
	Group (B)	4.00	Nos	690.00	2760.00
	Group (C)	8.00	Nos	829.00	6632.00
32	Supplying and fixing of following piano type switch / socket on the existing switch box / cover including connections etc as required (5/6A) as per direction of Engineer in Charge.	6.00	Nos	212.00	1272.00
33	Supplying and fixing batten holder / BK angle holder ISI marked including connection etc as required as per direction of Engineer in Charge.	8.00	Nos	43.00	344.00
34	Supply and drawing of following sizes FR PVC insulated single core multistrand copper conductor in existing surface / recessed STEEL/PVC conduit as required (2 x 2.5 sqmm) as per direction of Engineer in Charge.	25.00	Mtrs	115.00	2875.00
35	Supply and drawing of following sizes FR PVC insulated single core multistrand copper conductor in existing surface / recessed STEEL/PVC conduit as required (2 x 4.0 sqmm) as per direction of Engineer in Charge.	25.00	Mtrs	132.00	3300.00
36	Providing Colour & Branding of Health Wellness Centre in weather coat colour with all labour, material, T&P, taxes etc complete as per the direction of Engineer in Charge.	110.00	Sft	53.45	5879.50

37	Providing Colour & Branding of Health Wellness Centre door, window border in weather coat colour with all labour, material, T&P, taxes etc complete as per the direction of Engineer in Charge.	160.00	Rft	52.30	8368.00
38	GST aplicable				
Total 38 items				608273.00	
				(Rupees Six lakhs eight thousand two hundred seventy three) only	

My / Our Quoted rate is % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

- 1 The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.
- 2 Strick out which are not applecable.

Total :- 38 (Thirty eight) Items only

No. of correction :-

No.of overwriting :-

No. of Interpolation :-

Approved for 38 (Thirty eight) Items only

Full signature of the Contractor with date.

Chief District Medical & Public Health Officer
cum District Mission Director
Sundargarh