

## Name of the Work "Construction and Renovation of Govt Chatabar U.G.High School Hemgir

### TENDER SCHEDULE

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Earth Work in exavation of foundation in oridinary soil within initial leads of 50m & lifts of 1.5m including dressing and levelling of bed etc. and adding contractor's profit and over head charges, etc. complete in all respect	cum	408.238	116.74	47658.00
1.1	Earth work in hard soil or gravelly soil within 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the E-I-C.	cum	144.410	186.40	26918.00
2	Supplying & filling foundation and plinth with course sand well watered and rammed including cost, cost of all labour, carriage, royalty, etc complete.	cum	190.153	319.85	60820.00
3	Dismantling and removing Cement Concrete and R.C.C. in all locations including stacking the useful materials for reuse and removing the debris within 50m lead as suggested by School Management Committee.	cum	21.400	1153.37	24682.00
4	Dismantling brick masonry in cement mortar 3m. Height including stacking the useful materials for reuse and removing the debris within 50m. Lead as suggested by School Management Committee.	cum	13.000	1084.95	14104.00
5	Removing old lime or cement plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead etc. all complete	Sqm	629.320	38.84	24443.00
5.1	A.S. Flooring Dismantling	Sqm	0.000	0.00	0.00
6	Cement Concrete (1:3:6) using 4cm size hard granite C.B. metal approved quality from approved quarry including cost, carriage, royalty, cost of all labour. etc complete.	Cum	45.926	5851.36	268730.00
7	R.C.C. work of M-20 grade with 20mm and down grade black hard granite (crusherbroken) stone chips including hoisting and laying		0.000		
7.1	Foundation	Cum	134.887	5633.10	759832.00
7.2	Columns Base & Footings	Cum	23.267	5633.10	131065.00
7.3	R.C.C. Column / Beam		0.000		
	Ground Floor	Cum	60.028	11293.90	677950.00
7.31	First Floor	Cum	8.170	12538.50	102440.00
7.4	R.C.C Roof Slab		0.000		
	Ground Floor	Cum	34.182	9739.30	332909.00
7.41	First Floor	Cum	17.000	10674.50	181467.00
7.5	R.C.C. Stair case		0.000		
7.51	Ground Floor	Cum	5.893	10820.60	63766.00
7.52	First Floor	Cum	5.893	10820.60	63766.00
7.6	R.C.C Chajja		0.000		
	Ground Floor	Cum	1.485	824.70	1225.00
	Ground Floor	Cum	1.450	9157.60	13279.00
7.61	First Floor	Cum	1.485	923.80	1372.00
7.7	TIE BEAM		0.000		
	Ground Floor	Cum	13.819	5987.79	82745.00
8.0	LINTEL		0.000		
	Ground Floor	Cum	6.356	9066.91	57629.00
8.1	First Floor	Cum	6.356	9066.91	57629.00

9	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.		0.000		
	Ground Floor	Qtl	331.470	7892.60	2616160.00
9.1	First Floor	Qtl	152.770	7916.00	1209327.00
10	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ±2 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.		0.000		
	F&P	Cum	83.091	4035.60	335322.00
	Ground Floor Qty.	Cum	391.112	4068.90	1591396.00
	First Floor	Cum	69.469	4330.70	300849.00
	Septictank	Cum	4.080	3829.30	15624.00
11.0	A.S Flooring Dismantalling	Sqm	614.770	77.68	47755.00
11	12mm thick C.P.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.		0.000		
	Ground Floor Qty.	Sqm	1510.279	140.90	212798.00
	First Floor	Sqm	235.800	144.20	34002.00
	16mm thick C.P. (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.		0.000		
12	Ground Floor Qty.	Sqm	4899.955	215.70	1056920.00
12.1	First Floor	Sqm	850.200	224.20	190615.00
12.2	Terace	Sqm	90.000	224.20	20178.00
	6 mm thick C.P. (1:4) to RCC surfaces finished smooth including closed deep chipping and slury treatment , watering, curing cost, carriage & royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.		0.000		
13	Ground Floor Qty.	Sqm	2051.220	154.90	317734.00
	Supplying, fitting and fixing tile in floors of approved make conformaimg to IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.		0.000		
14	Verified Tiles(600x600)mm		0.000		
	First Floor	Sqm	1644.400	1244.49	2046439.00
	Verified Tiles		0.000		
	Ground Floor Qty.	Sqm	232.000	1012.89	234990.00
	Anti-Skid / Matte Finish Tile (300x300) mm		0.000		
	Ground Floor Qty.		0.000		
			0.000		
14			0.000		
			0.000		
	Fixing tiles in dados on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.		0.000		
15	Ceramic Tiles		0.000		
	Ground Floor Qty.	Sqm	146.270	714.80	104554.00

	Finishing wall surface with one coat of Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour etc. complete.		0.000		
16	Ground Floor Qty.	Sqm	4394.019	48.40	212671.00
	Finishing wall surface with two coat of Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour etc. complete.	Sqm	4432.109	77.50	343488.00
17	Priming 1 coat with wall primer water bond cement primer including all labour, materials etc. complete.		0.000		
18	Ground Floor Qty.	Sqm	4394.019	47.73	209732.00
	Priming 1 coat with wall primer water bond cement primer including all labour, materials etc. complete.		0.000		
	Ground Floor Qty.	Sqm	52.490	56.20	2950.00
	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade excluding cost of paint		0.000		
19	Ground Floor Qty.	Sqm	1492.599	74.40	111049.00
	First Floor	Sqm	0.000	0.00	0.00
	Wall painting 1 coat with plastic emulsion paint of approved shade on old work to give an even shade excluding cost of paint.		0.000		
20	Ground Floor Qty.	Sqm	4394.019	84.30	370416.00
	Wall painting two coat with any approved weather coat paint including cost of all materials, labour and T&P require for the work etc. complete as directed by the E.I.C.		0.000		
21	Ground Floor Qty.	Sqm	2706.649	74.40	201375.00
	Wall painting 1 coat with plastic emulsion paint of approved shade on old work to give an even shade excluding cost of paint.		0.000		0.00
22	Ground Floor Qty.	Sqm	0.000	84.30	0.00
	Wall painting two coat with any approved plastic emulsion paint including cost of all materials, labour and T&P require for the work etc. complete as directed by the E.I.C.		0.000		0.00
23	Ground Floor Qty.	Sqm	0.000	74.40	0.00
	First Floor	Sqm	0.000	0.00	0.00
22	Painting two coats with approved enamel paints of approved colour, shade over a coat of primer including sand papering, polishing the surface, cost, conveyances of all materials and cost of all labour etc, complete as per specification & direction of En	Sqm	14.400	133.88	1928.00
22	5 cm thick grading concrete (1:2:4) on roof slab with 12mm & down grade size black hard granite chips for old & New work.	Sqm	0.000		
			0.000		
	Ground Floor Qty.	Sqm	520.000	691.75	359712.00
	Extra for pre finished nosing in treads of steps of Kota stone slab.	Rmt	0.000	0.00	0.00
25		Sqm	0.000	0.00	0.00

25	Providing and fixing TATA Pravesh Plain wooden finish Doors (Termite-Resistant, Weather proof, Environment friendly, Longevity, Strength) with shutter of approved size constructed from 0.8mm (22SWG) thick skin pass Galvanised Iron Sheet (Conform to IS 277), thickness of flush doors shall be 30mm and In-Fill Honeycomb Kraft Paper. Door frames conform to IS 4351: 2003 constructed from 1.2mm (18SWG) thick skin pass galvanised iron sheet (conform to IS 277) formed to single rebate profile of size 100mmx58mm. The door frames and door shutters are coated with Zinc Phosphate primer to receive any paint on site or finished with thermosetting polyurethane paint of Aliphatic Grade including fixing of accessories of SS Ball bearing butt hinges of 102mm x 76mm x3mm-4No., Lever handle with lock HLIP 06SS-1 No., SS Tower Bolt 200mm long-1No. including T&P, material, hire charges and fixing at location etc. all complete		0.000		
27	Wood Finish Door size 1200 * 2130	nos	35.000	23259.16	814071.00
	Providing and fixing of TATA Pravesh (Oyster window) base variant double shutter window with grill & glass (Termite-Resistant, Weather proof, Environment friendly, Longevity, Strength), window frames and leaves of skin Pass Galvanised Iron sheet (as per IS513 "D" Quality, Galvanised as per IS 277 with Hot Zinc Coating of 120grams /Sq. Mtr & thickness of 0.6mm), Window shutter of 0.6mm (24SWG) thick skin pass Galvanised Iron sheet, Window Frames 8mm (22SWG) thick skin pass Galvanised Iron Sheet of Size 80mmx45mm, Mullion should be 8mm (22SWG) thick skin pass Galvanised Iron Sheet of size 80mmx60mm, Vision Glass 4mm clear float glass in rectangular shape. Height & width at least 8.8mm less than that of the shutter height & width, Finished of window with coated zinc phosphate primer or Thermosetting Polyurethane paint of Aliphatic Grade providing high levels of scratch resistance and durability. Window grill shall be made by 10mm Square MS bright bars. Windows accessories : SS Pin type Hinges -6No., Polypropylene handle -2No., Friction stay Powder coated-1No., MS Powder coated Tower Bolt -2 No. 150mm long, EPDM should be used all		0.000		
28	Ventilator	nos	30.000	29368.88	881066.00
	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 32mm x 32mm x 2mm @ 0.90mtr C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T & P etc required for the work complete in all respect. (Data for 3.26 sqm.)	Rmt	25.000	3515.30	87883.00
29	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge. 60 mm thick, M-35 grade	Sqm	500.000	884.75	442375.00

30	providing and laying at or near level factory made kerb stone of m25 garde cc in position line level of curvature jointed with cement mortar 1:3.(precast C.C kerb shall be measured for paymet.	cum	160.000	6844.89	1095182.00
31	Iron works wrought & put in grated door, windows & cage latrines(per 1 qntl)	Qtl	2.000	13803.77	27608.00
32			0.000	0.00	0.00
33			0.000		
34		Sqm	0.000	0.00	0.00
32	welded in built upsections trusses and framed work including cutting hoisting fixing in position and applying a priming	Kg	12800.000	10.75	137600.00
35	Cement Concrete (1:2:4) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. using 12mm size hard granite C.B. chips approved quality from approved quarry including cost, carriage, royalty, cost of all labour. etc complete and as directed by E.I.C.	cum	1.600	6578.43	10525.00
36	Painting two coats with approved enamel paints of approved colour, shade over a coat of primer including sand papering, polishing the surface, cost, conveyances of all materials and cost of all labour etc, complete as per specification & direction of En	Sqm	0.000	133.88	0.00
37	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with sand, with common burnt clay non modular bricks.	Sqm	0.690	516.00	356.00
38	560 mm diameter C.I. cover (heavy duty) the weight of the cover to be not less than 108 kg	Each	1.000	5891.20	5891.00
39	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :		0.000		
40	250 mm dia. R.C.C. pipe	mt	6.000	482.05	2892.00
	40mm thick Brick Ballast Aggregate	Cum	1.890	4651.00	8790.00
41	50 to 80mm Brick Ballast Aggregate	cum	0.180	4651.00	837.00
42	Honey-comb brick work 10 / 11.4 cm thick with common burnt clay bricks of class designation 7.5 in substructure upto plinth level with cement mortar 1:4 (1 cement : 4 coarse sand).	Sqm	4.450	331.30	1474.00
43	Supply and filling of brick bats for soak pit of approved size as shown in the drawing etc. all complete under instruction of Engineer in charge.	cum	0.670	2009.00	1346.00
44	Supplying of M.S. Door, Window with grills. Grills made out of M.S. Flat Sheet etc of approved section & design, electrically welded properly with all necessary locking aaengement and 1 coat red oxide primer incl. cost of all materials, labour charges , carriage of materials to site etc. complete.	kg	203.380	135.38	27534.00
				(A)	18687843.00
	<b>Total</b>				

## Electric Works

	<b>Electric Works</b>				
	Recessed wiring to Light Point / Fan Point / Exhaust Fan Point / Call Bell Point with 1.50 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 5 Amp, 250 Volt piano type swich ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite cover of suitable size, MS box with 1.0 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor of ISI marked as earth wire including all accesories and connection as per direction of engineer in charge. (Make of wire Finolex / L&T / Anchor / Hevels / V Guard)				
1	a) Light point				
	Long	Nos	5	861.00	4305.00
	Midium	Nos	15	607.00	9105.00
	Short	Nos	20	386.00	7720.00
	b) Celling fan point				
	Short	Nos	4	602.77	2411.00
	c) 5 A plug point	Nos	6	393.94	2364.00
	Recessed wiring for 15 / 16 Amp socket outlet with 2 X 4.00 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 5 Amp, 250 Volt piano type swich ISI marked, Phenolic laminated sheet of suitable size ISI marked MS box and earthing point with 1 X 2.50 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor for loop earthing etc. as required, as per direction of engineer in charge. (Make of wire Finolex / L&T / Anchor	Nos	5	543.18	2716.00
2	Recessed wiring to Sub-Main in 2 X 2.50 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor of ISI marked with 20 mm dia non-metallic PVC heavy duty flexible conduit with 1.60 mm thick, along with 1 X 1.50 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor as earth wire as required as per direction of Engineer-in-Charge. (Make of wire Finolex / L&T / Anchor / Hevels / V Guard)	mtr	20.00	154.29	3086.00
3	Recessed wiring to Sub-Main in 2 X 4.00 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor of ISI marked with 25 mm dia non-metallic PVC heavy duty flexible conduit with 1.60 mm thick, along with 1 X 2.50 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor as earth wire as required as per direction of Engineer-in-Charge. (Make of wire Finolex / L&T / Anchor / Hevels / V Guard)	mtr	20.00	154.00	3080.00
4	Recessed wiring to Sub-Main in 2 X 10 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor of ISI marked with 25 mm dia non-metallic PVC heavy duty flexible conduit with 1.60 mm thick, along with 1 X 4 sq. mm FR PVC insulated Single Core Multi standard Copper Conductor as earth wire as required as per direction of Engineer-in-Charge. (Make of wire Finolex / L&T / Anchor / Hevels / V Guard)	mtr	20.00	241.98	4840.00
5	Earthing with G.I earth pipe 3 mtr long 40 mm dia ISI mark including accessories and providing machinary enclosure with cover plate having locking arrangement and watering pipe etc. with charcol and salt etc.	Nos	3	2761.46	8284.00
6	Providing and fixing Copper tape 32 mm X 6 mm from earth electrode directly in ground as required.	mtr	5.00	607.47	3037.00
7	Supply , fixing and fitting of 11 watt LED light ( make Philips / Bajaj/ Crompton or Equivalent)	Nos	6.00	200.00	1200.00

8	Supply & fixing of single spot light of 18 watts complete with 1 no. 18 watt of approved make complete with all necessary fixing materials including termination & labour ( make:- Philips/ Bajaj/ Crompton of Equivalent)	Nos	10.00	600.00	6000.00
9	Supply & fixing of 28W LED Tube Light of approved make complete with all necessary fixing materials including termination & labour ( make:- Philips/ Bajaj/ Crompton of Equivalent)	Nos	20	750.00	15000.00
10	SITC of Exhasut Fan	Nos	2	500.00	1000.00
11	SITC of Street Light with 6mtr heigh pole & 50W LED lamp with all the accessories.	Nos	2	15000.00	30000.00
12	Supply, installation, Testting and commissioni of ceiling fan 1200 mm sweep 230/250 volts , 50 Hz, complete with suitable, clamp, downrod, blades, connections with 1.5 sq. mm PVC insulated copper conductor cable et as required and fan hook made of 16mm M.S. rod in R.C.C roof complete with all accessories	Nos	3	1800.00	5400.00
13	Providing and fixing Single Pole MCB with sheet steel enclosure, distribution board on surface / recess complete with tinned copper bus bar , neutral bus bar, earth bar, din bar, detachable gland plate inter connection phospate and powder painted including earthing etc. as per direction of Engineer-in-charge.	Nos	3	1705.00	5115.00
14	Supply, installation, testing and commisisoning of 63amp TPN main switch of following capacity (IS 13940 part-3/19930 on existing surface / wall mounting and complete with HRC fuse links inter connections, earthing etc as per direction of Engineer-in-charge. (SEIMENS/HPL/ANCHOR/L&T/HAVELS/C&S/RK)	Nos	5	2273.00	11365.00
15					126510.00
	Add Over head charges & Contractor Profit 15%				18977.00
					145487.00
	Labour Cess 1%				1455.00
				(B)	146942.00
<b>Plumbing Works</b>					
	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required				
1	W.C. pan with ISI marked white solid plastic seat and lid	Each	8	5263.39	42107.00
	Supplying , fitting , fixing of water closet of CERA make 2073 Orissa Pan (Cello) of size 510 x 400 mm or equivalent of parryware/ Hindware, duly embedded in cement concrete (1:3:6) using 25 mm size b.h.g. metal all complete with materials, labour and T & P etc.	Each	2	2919.39	5839.00
2	Supplying , fitting , fixing of porcelein wash hand basin of size 450mm x 350 mm of CERA make, catalogue no Canon 1012 Wash Basin of Equivalent of Parryware/ Hindware with rog bolts, CI brackets, hole for pillar cock with cast iron/ M.S. brackets painted while including cutting holes in wall and making good to the damages etc. all complete with materials , labour and T& P etc	Each	2	2714.56	5429.00

3	Supply , fitting , fixing of ( 500 x 450 mm) bevelled edge mirror of superior glass mounted on 6 mm thk A.C. sheet or ply-wood sheet and fixed to wooden plugs with cromium plated brass screws and washers etc. all complete with materials .labour and T & P etc.	Each	4	560.71	2243.00
4	Supply, fitting , fixing of Stain Less Steel Kitchen sink with cast iron/ M.S brackets painted while including cutting holes in walls and making good to the damages etc. all complete wit materials labour and T& P etc.	Each	1	3097.64	3098.00
5	Providing and fixing PVC soil waste and vent pipes (Rain Water)				
6	(i) 110 mm dia .	mtr	20.00	167.00	3340.00
	Supplying fitting , fixing of PVC floor traps of the following normal diameter of outlet of self cleaning design with sand cast iron screwed down or hinged grating with or without vent arm including cutting holes in walls and making good to the damages etc. all complete with materials, labour and T& P etc.	Each	6	536.83	3221.00
7	Providing and fixing PVC plain bend of required degree				
8	(i) 100 mm	Each	15	140.00	2100.00
	Providing and fixing PVC single equal plain junction of required degee with access door, insertion rubber washer 3mm thick, bolts and nuts complete .				
9	(i) 1000x100x100mm	Each	15	135.00	2025.00
	Providing and fixing door piece, insertion rubber washer 3mm thick , bolts & nuts complete .				
10	(i) 110mm	Each	20	10.00	200.00
	Providing & fixing PVC terminal guard (i) 110 mm	Each	20	60.00	1200.00
11	Supplying, fitting, fixing to walls, ceiling and floor upplasticized PVC pipes conforming to I.S. 4985 of class IV ( 10 kg/ cm 2) th efollowing nominal diameter with fittings and clamps includings testing all complete with materials labour and T & P etc.				
12	a) 15mm dia nominal bore	mtr	30	103.59	3108.00
	b) 20mm dia nominal bore	mtr	20	123.27	2465.00
	c) 25 mm dia nominal bore	mtr	10	152.01	1520.00
	d) 32 mm dia nominal bore	mtr	10	201.95	2020.00
	e) 40 mm dia nominal bore.	mtr	20	296.15	5923.00
	Providing and fiowing brass bib cock of approved quality .				
13	(i) 15 mm nominal bore short body	Each	3	605.59	1817.00
	(ii) 15mm nominal bore long body	Each	2	654.49	1309.00
	Providing and fixing brass stop cock with wall flush of approved quality .				
14	(i) 15 mm nominal bore.	Each	2	746.41	1493.00
	Providing and fixing gun metal gate valve with C.I. wheel of approved qualioty ( screwed end)				
15	(i) 25 mm dia Nominal bore	Each	2	482.02	964.00
	(ii) 32 mm dia Nominal bore	Each	2	975.72	1951.00
	Supplying fitting , fixing of S.W. Gully trap Grade-A complete with cast iron grating, brick masonry chamber( 250 mm x 250 mm) with R.C.C cover slab as per P.H. specifiaiton and design all complete with materials labour and T & P etc. (Excluding cost of gully trap and grating)	Each	4	1542.14	6169.00
16	Supply all labour , materials and T & P and laying to level and slope and jointing with cement mortar(1:1) for PVC pipes . (Grade-A) of the following diametersas per specification al complete (excluding earth work in trenches)(data for 30 mtr.) (per mtr) S.W. Pipe 150mm dia.	mtr	20	779.41	15588.00
17	Supplying all materials, labour and T & P for construction of inspection chamber as per P.H. specification and design all ocomplete ( per each)	Each	3	10585.46	31756.00

18	Providing and placing on terrance (at all floor levels) per liter polyethylene water storage tank ISI:12701 marked capacite indicating the BIS License No. with cover and suitable locking arrangement and making necessary holes for intel, outlet and overflow pipes but without fittings and the base support for tank ( sintex, Electroplast, star Lots of equivalent having valid ISI licence)	Per Ltr	5000.00	7.50	37500.00
19	Providing & fixing heavy forged brass ( chrome plated ) tested ISI marked Ball valves as per ( IS:554 /BS:21/ISO : 7 full bore design ) of approved quality for 15 mm to 40 mm and Wafer type butterfly valve of pressure rating PN10 confirming to BS 5155 for 50 mm and above.				
20	40 mm	Each	2.00	1950.00	3900.00
	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes				
21	75 mm diameter	mtr	8.00	201.10	1609.00
	Providing and fixing of SWR PVC vent / waste water / waste water & soil pipes, Type 'B' conforming to I.S. - 13592, and fittings conforming to I.S. 14735/99 cut to required lengths including all necessary fittings and specials such as as 45 or 90 deg. bends, Tee's, Y's, access pipe with <b>solvent cement jointing</b> . Setting the pipes in cement concrete M-15 as per specifications after testing of pipes				
22	50 mm	mtr	6.00	360.00	2160.00
	Providing and fixing, jointing of uPVC waste pipe (IS: 4985 6Kgf/cm <sup>2</sup> )including all fittings (Plain or door) e.g. bends, junction, cowls, offsets, access pieces,jointing with rubber ring/solvent cement joints including cutting chase or holes in walls and floors and making good where required				
23	40 mm NB	mtr	6.00	165.00	990.00
	Installation testing and commissioning of <b>Health faucet</b> of approved make & model.	Nos	3	1950.00	5850.00
24	Providing, fixing, jointing & testing in position 75 mm UPVC <b>multi trap</b> (IS 14735-99) for the embedded areas. Making proper connection, cutting chase / hole in floors /slabs and bringing the same in proper condition and shape after placing the trap in right position complete as required with encasing in CC M-15	Nos	4	750.00	3000.00
25	Providing & fixing in position 80mm NB "P" type trap of self cleaning type ( <b>inlet to "P" trap to be 100mm dia</b> ) including brass 125mm dia CP grating, <b>lead jointing embedding in concrete etc. all complete.</b>	Nos	1	800.00	800.00
26	Supply and Installation of PVC clean out plugs with suitable insert keys for PVC pipes with heavy duty adaptor with a threaded socket as necessary.				
27	75 mm dia	Nos	1	475.00	475.00
	110 mm dia	Nos	3	630.00	1890.00
	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required.				
28	One urinal basin with 5 litre white P.V.C. automatic flushing cistern	Each	3	4982.25	14947.00
	Providing & Fixing <b>150x250 mm Parapet with CI/MS Grating</b> at the Collection Point of Rainwater Pipe On Terrace of approved design.	Nos	3	1375.00	4125.00

29	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. <b>(External work)</b>				
30	32 mm nominal outer dia .Pipes.	mtr	30.00	250.00	7500.00
	40 mm nominal outer dia .Pipes.	mtr	20.00	278.00	5560.00
	50 mm nominal outer dia .Pipes.	mtr	20.00	411.00	8220.00
	Fixing, testing and commissioning of <b>Portable RO Water Purifier</b> of suitable capacity as per requirement complete as required.	Nos	1.00	50000.00	50000.00
31	Fixing, testing and commissioning of borewell of suitable capacity as per requirement complete as required.	Nos	1.00	380000.00	380000.00
32					706024.00
	Add O.C & Contractor Profit 15%				105904.00
					811928.00
	Add 1% Labour cess 1%				8119.00
				( C )	<b>820047.00</b>
		<b>Total</b>	<b>(A+B+C)</b>		<b>19654832.00</b>

The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender My/Our quoted rate is \_\_\_\_\_%(Figure) \_\_\_\_\_ (In words)  
\*Less than/Excess over/ Equal to the amount put to tender.

Total number of Items:..... Number of Corrections:..... Number of interpolation:..... Number of over writings:..... E.M.D Funnished/EMD Exempted (A)Demand Draft No..... (B)Ammount Rs..... Copy of PAN card:furnished/not furnished Copy of GST Registration:furnished/not furnished Copy of Contractor's Liccence:furnished/not furnished Copy of Experience certificate:furnished/not furnished Total No of sheets in the Tender Papers:.....	
---	--

Full Signature of Contractor

Signature of the Bidder/Tenderer

Signature of the B.D.O  
Hemgir