

TENDER SCHEDULE

| Construction of Labour Room Building at Khuntgaon PHC-N of Lahunipara Block for the year 2021-22 | | | | | |
|---|---|----------|------|----------|-----------|
| Sl. No. | Item | Quantity | Unit | Rate | Amount |
| 1 | Earth Work in Excavation of foundation in hard soil or gravelly soil including dressing and levelling the bed, initial leads and lifts as per direction of EIC. | 143.41 | Cum | 188.77 | 27071.50 |
| 2 | Supplying and Filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc. complete. | 92.44 | Cum | 373.75 | 34549.45 |
| 3 | Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C. | 26.83 | Cum | 4661.15 | 125058.65 |
| 4 | R.C.C. M-25 grade with 20mm and down grade C.B. chips including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P centering shuttering etc complete but cost of reinforcement complete. | | | | |
| | (A) Column base and Column footing | 15.84 | Cum | 5357.70 | 84865.96 |
| | (B) Plinth band (Grade beam) | 9.98 | Cum | 5709.83 | 56984.10 |
| | (C) Lintel | 3.30 | Cum | 8859.90 | 29237.67 |
| | (D) Chhaja | 10.21 | Sqm | 805.00 | 8219.05 |
| | (E) Column in Superstructure, Beam (Ground Floor) | 13.14 | Cum | 12494.35 | 164175.75 |
| | (F) Roof Slab (Ground Floor) | 17.53 | Cum | 9448.29 | 165628.52 |
| | (G) Staircase | 1.67 | Cum | 10569.72 | 17651.43 |
| | (H) Column in Superstructure, Beam (First Floor) | 1.98 | Cum | 14035.53 | 27790.34 |
| 5 | C.C. (1:2:4) with 12mm and down grade C.B. chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C. | 5.03 | Cum | 5979.58 | 30077.28 |
| 6 | Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. | | | | |
| i | Ground Floor | 76.42 | Qntl | 8574.35 | 655251.82 |
| ii | First Floor | 2.77 | Qntl | 8598.00 | 23816.46 |
| 7 | 2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T.& P. required for the works etc complete. (Ground Floor) | 136.56 | Sqm | 302.51 | 41310.76 |

| | | | | | |
|----|--|--------|-----|---------|-----------|
| 8 | Brick work with Flyash Ash. bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent in cement mortar (1:6) in Foundation & Plinth including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C. | 19.59 | Cum | 4069.87 | 79728.75 |
| 9 | Brick work with Flyash Ash. bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 8 percent in cement mortar (1:6) in Superstructure including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C. | | | | |
| i | Ground Floor | 47.62 | Cum | 4103.20 | 195394.38 |
| ii | First Floor | 15.13 | Cum | 4368.08 | 66089.05 |
| 10 | Supplying M.S Door & Window made out with ms flat , angle of approved design & specification including cost of all materials cost of manufacture, cost of one coat of primer,all taxes T&P etc complete. | 750.94 | Kg | 75.00 | 56320.50 |
| 11 | Labour charge for fitting ,fixing of M.S door,window, grill , Gate including all costetc complete. | 25.56 | Sqm | 67.40 | 1722.74 |
| 12 | Painting 2 coats with any approved paint in new iron works including sand papering, polising surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of Engg-in charge.(Ground Floor) | 63.78 | Sqm | 135.04 | 8612.85 |
| i | First Floor | 4.25 | Sqm | 138.51 | 588.66 |
| 13 | 16mm thick C.P. in C.M.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.(Ground Floor) | 122.71 | Sqm | 195.69 | 24013.11 |
| i | First Floor | 34.74 | Sqm | 200.57 | 6967.8 |
| 14 | 12mm thick C.P. in C.M.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C. | | | | |
| i | Ground Floor | 248.51 | Sqm | 136.92 | 34025.98 |
| ii | First Floor | 83.24 | Sqm | 142.39 | 11852.54 |
| 15 | Supplying all materials,labour,T&P for 12mm thick cement plaster (1:4) over brick work including cement punning including cost all taxes,royalty of all materials,curing and conveyance of materials to the work site etc.all complete as per the direction of Engineer-in-charge. | 28.20 | Sqm | 155.61 | 4388.20 |
| 16 | Fixing glazed tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles. | 180.98 | Sqm | 751.10 | 135934.07 |

| | | | | | |
|----|---|--------|------|---------|-----------|
| 17 | Supplying, fitting and fixing Vetrified tile in floors of size 600mm x 600mm of approved make conforming to IS 13755 laid on 20mm thick cement mortar (1:4) 1cement:4 course sand and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of Engineer-in-charge. | 115.05 | Sqm | 907.31 | 104386.01 |
| 18 | Fixing Glazed tile (30cmx30cm / 40cm x 40cm (special plain/printed series ceramic tiles)of premium grade having thikness 7mm to 8 mm confirming to IS 13755) in floors,treads or steps and landing on 20mm thick bed of cement mortar 1:4(1cement:4 sand jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost of tile. | 7.36 | Sqm | 689.64 | 5075.75 |
| 19 | Fixing Chequred tiles in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete. | 13.92 | Sqm | 486.77 | 6775.83 |
| 20 | Priming 1 coat with wall primer (water bond) of any approved shade including all costs complete. | | | | |
| i | Ground Floor | 490.93 | Sqm | 58.70 | 28817.59 |
| ii | First Floor | 117.98 | Sqm | 61.10 | 7208.57 |
| 21 | Finishing plastered surface of wall surface with Cement based putty & making smooth to recive painting including cost of scaffolding etc. with cost of all materials, labour T&P etc. complete. | | | | |
| i | Ground Floor | 490.93 | Sqm | 72.24 | 35464.78 |
| ii | First Floor | 117.98 | Sqm | 73.56 | 8678.60 |
| 22 | Distempering 2 coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper and labour, T & P. etc complete. | | | | |
| i | Ground Floor | 309.15 | Sqm | 63.88 | 19748.50 |
| 23 | Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete . | | | | |
| ii | Ground floor | 181.78 | Sqm | 71.70 | 13033.62 |
| ii | First Floor | 117.98 | Sqm | 74.26 | 8761.19 |
| 24 | Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless aquare pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor) | 10.00 | Rmtr | 3499.50 | 34995.00 |

| | | | | | |
|-------|---|--------|-----|----------|-----------|
| 25 | Supplying, fitting & fixing of PPGL sheet in roof including fixing of ridges wind ties etc. complete but excluding cost of fitting including drilling holes in wind ties as per the direction of Engineer in Charge. | 15.11 | Sqm | 772.60 | 11673.98 |
| 26 | Providing fitting, fixing of Aluminium door with anodized Al. door section of 9202 as vertical member, 9201 as top member and 9200 as bottom and middle member with frame section as 9221 by means of tapered clip No. 4660 and the frame to be completed by means of jointing angle No. 1855 including all cost of labour, T&P, hire charges of drilling machine, labour charges etc. complete. excluding cost of laminated board. | 289.29 | KG | 414.89 | 120023.52 |
| 27 | Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778 as windows frame, section No. 4095, 4096 and 9777, 3994 as shutter frame with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour, T&P etc. complete as per direction of Engineer-in-charge. excluding cost of glass. | 61.24 | KG | 606.59 | 37147.57 |
| 28 | Providing and fitting of (12 mm thick) Pre-laminated Board Standard Type (ISI) in Aluminium frame of doors, windows & ventilators etc. including cost of all materials, labour T&P etc. complete. (Measurement to be taken as per actual) | 11.02 | Sqm | 647.68 | 7137.43 |
| 29 | Providing and fitting of glass pane (5 mm thick black Glass) for windows, door and ventilators including cost of all materials, labour T&P etc. complete. (Measurement to be taken as per actual) | 23.57 | Sqm | 599.45 | 14129.03 |
| 30 | Construction of 1.20 m dia and 2.00 m deep soak pit as per the direction of Engineer-in-charge. | 2.00 | Nos | 20214.80 | 40429.60 |
| 31 | Construction of Inspection Chamber of Inside size 0.60 m x 0.60 m x 0.60 m deep with RCC Cover slab as per the direction of Engineer-in-charge. | 2.00 | Nos | 6938.20 | 13876.40 |
| 32 | Fixing Wash down water closet (European type W.C) with integral ' S ' or ' P ' trap conforming to IS 2556:Part 8-2004 to the floor with wooden plug and chromium plated screws including jointing the trap with soil pipe in cement mortar (1: 1) etc all complete as per specification | | | | |
| i | White vitreous china Wash down water closet (EWC) | 2.00 | Nos | 5234.10 | 10468.20 |
| 33 | Providing and Fixing PVC Low level flushing cistern with manually controlled device (hand lever) conforming to IS: 7231, with all fittings and fixtures etc, all complete as per specification. | | | | |
| i | 10.00 ltrs capacity Low level flushing cistern-White | 2.00 | Nos | 1697.80 | 3395.60 |
| 34 | Fixing of Brass Screw -Down Bib Cocks (Tap) Polished bright conforming to IS:781-1995 of the following nominal sizes as per specification complete. | | | | |
| (i) | 15 mm dia C.P. Brass Short Body Bib Cock | 5.00 | Nos | 672.10 | 3360.50 |
| (ii) | 15 mm dia two way Bib Cock | 2.00 | Nos | 1853.60 | 3707.20 |
| (iii) | 15 mm diameter long handle elbow operated bib cock | 2.00 | Nos | 1482.50 | 2965.00 |

| | | | | | |
|------|--|-------|------|----------|----------|
| (iv) | 15 mm diameter Pillar cock | 2.00 | Nos | 696.90 | 1393.80 |
| 35 | Fixing standard size chromium plated brass towel rail complete with chromium plated brass brackets fixed to wooden plugs with C.P.Brass screws complete as per specification. | | | | |
| (i) | 20mm x 600 mm long CP towel rail | 2.00 | Nos | 829.90 | 1659.80 |
| 36 | Fixing standard sized chromium plated brass towel ring fixed to wooden plugs with C.P.Brass screws complete as per specification. | 2.00 | Nos | 574.50 | 1149.00 |
| 37 | Fixing of Brass or C.P screw down stop cocks/ concealed stop cock/ angle stop cocks confirming to IS: 781-1995 of the following nominal sizes as per specification complete. | | | | |
| (i) | 15 mm dia Brass Screw- down Stop Cock | 4.00 | Nos | 656.00 | 2624.00 |
| (ii) | 125mm CP grating | 6.00 | Nos | 72.90 | 437.40 |
| 38 | Fixing bevelled edge mirror of superior glass mounted on 6mm thick AC sheet or plywood sheet and fixed to wooden plugs with chromium plated brass screw & washers complete as per specification. | | | | |
| (i) | 600mm Bath room mirror | 2.00 | Nos | 1675.20 | 3350.40 |
| 39 | Fixing Wash Basins with hole for Pillar Taps confirming to IS 2556:Part 4-2004 with Cast Iron or M.S brackets painted white including cutting holes in walls and making good the damages etc all complete as per specification. | | | | |
| (i) | Vitreous China flat back Wash Hand Basin of size 550 mm x 400 mm | 2.00 | Nos | 2897.30 | 5794.60 |
| 40 | Supplying all materials, labour, T&P and fixing kitchen sink with hole for pillar taps with C.I/M.S brackets painted white including holes in walls and making good the damages etc all complete as per PH specification as per the direction of Engineer-in-charge. | | | | |
| (i) | Porcelain sink 510mm x 600mm x 225mm | 1.00 | Nos | 5435.50 | 5435.50 |
| 41 | Fixing Rational moulded Polythylene cylindrical vertical water storage tanks confirming to IS:12701--1996 including cutting holes through the tank and fixing mild steel tubes and fittings and providing extra socket ,jam nut, fixing ball valves etc including hoisting upto a height of 5 mtr above ground level and placing the tank to the required position etc all complete as per specification and direction of Engineer-in- Charge. | | | | |
| (i) | 1000 litres capacity PVC water storage tank | 1.00 | Nos | 19119.50 | 19119.50 |
| 42 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) Pipes confirming to IS: 15778 having thermal stability for hot & cold water supply, including all CPVC plain & brass threader fittings, fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints etc as per direction of Engineer in Charge. | | | | |
| (i) | 25 mm nominal outer dia pipe | 20.00 | Mtrs | 265.50 | 5310.00 |

| | | | | | |
|---------------|--|-------|------|--------|---------|
| 43 | Providing and fixing to wall or ceiling and floor Chlorinated Polyvinyl Chloride (CPVC) Pipes conforming to IS: 15778 of the following nominal bore with clamp including making good the damages to wall ,ceiling & floor etc complete as per specification as per direction of Engineer in Charge. | | | | |
| (i) | 15 mm nominal outer dia pipe | 24.00 | Mtrs | 171.40 | 4113.60 |
| (ii) | 25 mm nominal outer dia pipe | 30.00 | Mtrs | 302.00 | 9060.00 |
| 44 | Fixing of UPVC Ball Valve (Horizontal plunger type) conforming to IS: 1703-1977 as per specification & direction of Engineer-in-charge | | | | |
| (i) | 25 mm dia | 4.00 | Nos | 624.50 | 2498.00 |
| 45 | Providing and laying in trenches PVC pipe (4Kg/cm2) as sewer line and alinging to requisite gradients inside the trench, jointing with solvent cement with 0.08m sand filling in bed , 0.10m C.C (1:4:8) using 40 mm size hbg metal in bed & for intermidiate pillar including lowering the pipes to the bed of trench, Earthwork in excavation in all kind of soil ,Filling the trenches with excavated earth with watering and ramming and removal of surplus earth, testing of sewer line etc. complete as per the direction of Engineer.in charge. | | | | |
| (i) | 75 mm PVC Pipe | 10.00 | Mtrs | 843.90 | 8439.00 |
| (ii) | 110 mm PVC Pipe | 10.00 | Mtrs | 885.10 | 8851.00 |
| 46 | Supplying all materials, labour, T&P and fitting and fixing U-PVC, SWR soil waste ventilating pipes and fitting of the following outside diameter conforming to 13592/1992 to walls with nails bobbins and wooden plugs or laying in trenches including with supply of approved rubber lubricant by non-heat application method as per manufactures specification testing earth work in excavation in all kinds of soil and refilling of trenches all complete as per specification and direction of Engineer.in charge. | | | | |
| (i) | 110 mm U-PVC Pipe | 8.00 | Mtrs | 284.20 | 2273.60 |
| (ii) | 110 mm U-PVC 'P' trap | 2.00 | Each | 294.20 | 588.40 |
| (iii) | 110 mm U-PVC door bend | 2.00 | Each | 302.10 | 604.20 |
| (iv) | 110 mm U-PVC Plain bend | 10.00 | Each | 287.10 | 2871.00 |
| (v) | 110 mm U-PVC Cowl | 2.00 | Each | 77.30 | 154.60 |
| (vi) | 110 mm U-PVC Coupler | 8.00 | Each | 130.30 | 1042.40 |
| (vii) | 75 mm U-PVC door bend | 4.00 | Each | 207.90 | 831.60 |
| (viii) | 75 mm U-PVC Plain bend | 8.00 | Each | 163.80 | 1310.40 |
| (ix) | 75 mm U-PVC Coupler | 8.00 | Each | 97.60 | 780.80 |
| 47 | Fixing 15 mm dia PVC inlet connection pipe and making connection with pillar cocks and supply main for wash basin complete as per specification. & direction of Engineer-in-charge. | | | | |
| (i) | 15mm dia | 6.00 | Nos | 195.40 | 1172.40 |
| 48 | Fixing PVC Waste Pipe of the following diameter for sink or wash basin including brass check nut complete as per specification & direction of Engineer-in-charge. | | | | |

| | | | | | |
|------|---|-------|------|---------|----------|
| (i) | 32mm dia | 6.00 | Nos | 174.50 | 1047.00 |
| 49 | Fixing chromium plated Brass waste of the following nominal diameter for wash basin and sink as per specification & direction of Engineer-in-charge. | | | | |
| (i) | 32mm dia | 3.00 | Nos | 409.70 | 1229.10 |
| 50 | Cutting holes through existing brick work including making good the same in cement mortar (1: 4) for taking G.I / P.V.C pipes and fittings all complete as per specification & direction of Engineer-in-charge. | | | | |
| (i) | 250 mm thick wall | 18.00 | Nos | 49.60 | 892.80 |
| (ii) | 375 mm thick wall | 10.00 | Nos | 74.30 | 743.00 |
| 51 | Cutting groves in pucca floor and walls for taking G.I/PVC pipes and making good the damages as per specification etc all complete as per the direction of Engineer-in-charge. | 30.00 | Mtrs | 182.90 | 5487.00 |
| 52 | Labour for drilling and perfectly vertical bore hole of specified dia. For a specified depth below ground level through consolidated and unconsolidated rock with down the hole hammer drilling rigs or combination drilling rigs as required suit the site condition as per the direction of E.I.C. including use of own rigs with its accessories , tools & plants and consumable etc. for lowering of 125mm dia. P.V.C./G.I. pipes for housing fitted with sockets with or the necessity for soft , medium , hard and boulderwith out well screen as per formation (G.I/P.V.C.)casing pipes if required to prevent collapse over burden is to be provided by the contractor including lowrering and withdrawing after completion of the tubes as per direction of E.I.C. | | | | |
| i | (a)Drilling of 125mm. dia. Bore "o"mtr to 30mt | 30.00 | Mtr | 480.20 | 14406.00 |
| ii | (B)Drilling of 125mm. dia. Bore "30"mtr to 60mt.& above | 5.60 | Mtr | 480.20 | 2689.12 |
| iii | (b)Drilling 100mm dia. Bore 35mtr to60 mtr& above | 55.40 | Mtr | 480.20 | 26603.08 |
| 52 | Lowering the folloing size G.I./ P.V.C. pipes with without slotted pipes as per the necessary from ground level up to 30mtrs. Depth and fitted and fixed up in perfectly vertical position including cutting, and threading pipe and slotted pipe and supply and fixing all jointing materials tools and plants etc. complete and keeping the top plugging tube wells to prevent entry of foreign materials from above | | | | |
| i | (a) Lowering 125mm dia pipes "0" mtr to 30 mtr & above. | 35.60 | Mtr | 71.60 | 2548.96 |
| ii | (b)Cost of 125mm dia pipes P.V.C. pipes | 35.60 | Mtr | 651.80 | 23204.08 |
| 53 | .Cleaning and developing the tube well using their own compressor continuously worked till clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipment and labour as per the direction of E.I.C | | | | |
| i | (a) Developing the tube well | 1.00 | Each | 2147.00 | 2147.00 |
| 54 | Supplying all materials labour T & P and withdrawing casing pipes from unsuccess bore etc. all complete as per the direction of E.I.C. | 12.00 | Mtr | 173.70 | 2084.40 |

| | | | | | |
|----|---|-------|------|----------|----------|
| 55 | Supplying all materials, labour, T & P and fitting and fixing of I.S.I. mark 1H.P. single phase vertical water cool submersible pump set with discharge 1800/2200 Lit/Hour & a head-55/70mtr. of reputed make (C.R.I./K.S.B./Texmoor Equivalent) Including cost conveyance and taxes etc. all completes as per P.H. Specification and direction of E.I.C. | 1.00 | Each | 13749.15 | 13749.15 |
| 56 | Supplying all materials, labour, T & P and fitting & fixing of I.S.I. mark D.O.L. starter of reputed make like B.C.H. or equivalent for 1HP single phase vertical submersible pump set including all cost conveyance & taxes etc. all completes as per P.H. Specification and direction of E.I.C. | 1.00 | Each | 2809.30 | 2809.30 |
| 57 | Supplying all materials labour "T & P" and fitting & fixing of 1.5mm ² 3core copper flat suitable cable having I.S.I. mark of reputed company like B.C.H./ Finolex or equivalent & connecting the pump starter including cost conveyance & taxes etc. all completes as per P.H. Specification and direction of E.I.C. | 75.00 | mtr | 71.70 | 5377.50 |
| 58 | Supplying all materials labour "T & P" and fitting & fixing plastic rope with MS well cover, M.S. Clamp, stainless steel short piece, Bend & socket, union including all cost conveyance & taxes etc. all completes as per P.H. Specification direction of E.I.C. | 1.00 | Set | 1660.00 | 1660.00 |
| 59 | Supplying all materials labour "T & P" and fitting & fixing of H.D.P.E. pipes and pipe fittings with making connection to pump set including all cost conveyance & taxes etc. all completes as per P.H. Specification direction of E.I.C. | | | | |
| i | (a) 32mm dia H.D.P.E. pipe | 75.00 | Mtr | 41.10 | 3082.50 |
| 60 | Recessed wiring to light point / fan point / exhaust fan point / call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite mm dia non-metallic PVC conduit with 5 cover of suitable size, MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accessories and connection as per direction of Engineer in Charge. | | | | |
| i | Group (A) | 30.00 | Nos | 584.20 | 17526.00 |
| i | Group (B) | 20.00 | Nos | 690.00 | 13800.00 |
| i | Group (C) | 25.00 | Nos | 829.00 | 20725.00 |
| 61 | Supplying and fixing of following piano type switch / socket on the existing switch box / cover including connections etc as required (5/6A) as per direction of Engineer in Charge. | | | | |
| i | On existing board | 10.00 | Nos | 212.00 | 2120.00 |
| 62 | Supplying and fixing of following piano type switch / socket on the existing switch box / cover including connections etc as required (15/16A) as per direction of Engineer in Charge. | 6.00 | Nos | 642.00 | 3852.00 |
| 63 | Supplying and fixing batten holder / BK angle holder ISI marked including connection etc as required as per direction of Engineer in Charge. | 25.00 | Nos | 43.00 | 1075.00 |

| | | | | | |
|-----|---|--------|------|---------|----------|
| 64 | Supply, Installation, Testing, and Commissioning of 32 Amp TPN Main switches of following capacity (IS 13940 Part 3/1993) on existing surface / wall mountnting and complete with HRC Fuse links,interconnections, earthing, etc. as required as per direction of Engineer in Charge. | 1.00 | Nos | 2450.00 | 2450.00 |
| 65 | Installation, Testing and Commissioning of resistance type ceiling fan regulator, in existing switch box including connection with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor,earthing the regulator as required as required as per direction of Engineer in Charge. | 7.00 | Nos | 71.60 | 501.20 |
| 66 | Installation, Testing and Commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq.mm FR PVC insulated single core multiatrand copper conductor etc as required as per direction of Engineer in Charge. | 7.00 | Nos | 80.00 | 560.00 |
| 67 | Installation, testing and commissioning of exhaust fan up to 450 mm sweep in the existing opening, including making the hole to suit the size of the above fan, making good the damage complete, connection, etc as required as required as per direction of Engineer in Charge. | 2.00 | Nos | 419.00 | 838.00 |
| 68 | Supply and fixing of single pole MCB with sheet steel enclosure, distribution board, on surface /recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnection, phosphate and powder painted including earthing etc as required as per direction of Engineer in Charge. | 2.00 | Nos | 1493.90 | 2987.80 |
| 69 | Earthing with G.I earth pipe 3 meter long 40 mm dia ISI marked including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc with charcoal and salt as required as per direction of Engineer in Charge. | 1.00 | Nos | 2755.70 | 2755.70 |
| 70 | Recessed wiring to submain in 2 x 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked as per direction conforming to IS-694/1990 in 20mm dia non metallic heavy duty flexible conduit 1.6mm thick along with 1 x 1.5sq.mm FR PVC insulated single core multistrand copper conductor as earthwire as required of Engineer in Charge. | 90.00 | Mtrs | 101.00 | 9090.00 |
| 71 | Supply and drawing of following sizes FR PVC insulated single core multistrand copper conductor in existing surface / recessed STEEL/PVC conduit as required (2 x 2.5 sqmm) as per direction of Engineer in Charge. | 125.00 | Mtrs | 115.00 | 14375.00 |
| 72 | Supply and drawing of following sizes FR PVC insulated single core multistrand copper conductor in existing surface / recessed STEEL/PVC conduit as required (2 x 4.0 sqmm) as per direction of Engineer in Charge. | 80.00 | Mtrs | 132.00 | 10560.00 |
| i | Supply and Fixing of LED Bulb 12W | 25.00 | Nos | 190.00 | 4750.00 |
| ii | Supply and Fixing of Ceiling Fan 1200mm blade | 12.00 | Nos | 2080.00 | 24960.00 |
| iii | Supply and Fixing of Exhaust Fan 300mm | 2.00 | Nos | 1908.00 | 3816.00 |

| | | | | | |
|-----------------------|--|------|------|---|-------------------|
| 73 | S/F of 1.5 Ton 5 star Inverter type split A.C. M/C with 4 KVA Voltage Stabilizer (Make - Microtek, V-Guard) with all accessories and connections (Make - HITACHI-RMOG524HCEA/ Bluestar- IC518 QATU/ Carrier - Durafresh-Neo-X) | 2.00 | Each | 61656.00 | 123312.00 |
| Total 73 Items | | | | Total Rs.= | 3119266.00 |
| | | | | Rupees (Thirty one lakhs Ninteen thousand two hundred Sixty six) only | |

My / Our Quoted rate is % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

- 1 The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.
- 2 Strick out which are not applicable.

Total :- 73 (Seventy three) Items only

No. of correction :-

No.of overwriting :-

No. of Interpolation :-

Approved for 73 (Seventy three) Items only

Full signature of the Contractor with date.

**Chief District Medical & Public Health Officer
cum District Mission Director
Sundargarh**