

Name of the Work: CONST. OF SMALL BRIDGE AT TANGARJORE GAMMIDHIPA, DEOBHUBANPUR GP

Tender Call Notice No: 1191 / Date. 26/07/2021

Sl. No.	Description of Items of work	No.or Qty.	Unit	Rate in Figures (in Rs.)	Amount (in Rs.)
1	2	3	4	5	6
1	Earth work excavation in foundation in hard soil or gravelly soil Within 50m initial lead and 1.5m lift including rough dressing and breaking clods to maximum 5 to 7cm. Size including leveling and dressing all complete as per direction of Engineer- in -charge.	437.80	Cum.	186.40	81606.00
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete.	35.60	Cum.	408.70	14550.00
3	P.C.C. (1:3:6) with 40 mm size and down graded hard granite crusher broken metal including cost conveyance royalty of all materials etc.complete as per the direction of Engineer-in-charge.	183.03	Cum.	5076.70	929188.00
4	P.C.C. (1:2:4) with 12 mm size and down graded hard granite crusher broken chips including cost conveyance royalty of all materials etc.complete as per the direction of Engineer-in-charge.	0.81	Cum.	6365.90	5156.00
5	RCC work of M-15 grade with 20 mm and down graded black hard granite crusher broken stone chips including hoisting and laying and including cost of rigid smooth centering and shuttering etc. complete as per the direction of Engineer-in-charge.	70.40	Cum.	5049.60	355492.00
6	RCC work of M-20 grade with 20 mm and down graded black hard granite crusher broken stone chips including hoisting and laying and including cost of rigid smooth centering and shuttering etc complete as per the direction of Engineer-in-charge.				
(A)	Mass Concrete (Bottom slab , Cut off , Wing wall base)	84.40	Cum.	5416.80	457178.00
(B)	Walls (Verical walls , Abutment walls, piers, hunch, keys, wing walls	93.40	Cum.	6507.80	607829.00
(C)	Deck Slab , Kerb	42.50	Cum.	6531.70	277597.00
(D)	Wearing coat , M-30	9.40	Cum.	5678.10	53374.00
(E)	Railing ,M-30	36.30	Rmt.	2028.70	73642.00
7	Rigid smooth Centering and shuttering for CC work including false works and dismanteling them after casting including cost of material etc all comp.as per the direction of Engineer-in-charge. (Mass Concrete)	363.00	sqm	100.30	36409.00
8	Supplying, cutting, bending, binding and tying the grills and placing uncoated HYSD bar reinforcement including cost of all rod and binding wire and labour and transportation etc complete as per the direction of Engineer-in-charge.	155.20	Qtl.	8002.10	1241926.00
9	Providing weep holes in Brick masonry/ Plain/ Reinforced concrete abutment, wing wall/ return wal with 100 mm dia AC pipe, extended through the full width of the structure with slope of 1V:20H towards drawing face. Complete as per drawing and Technical specification.as per the direction of Engineer-in-charge.	64.60	Rmt.	115.00	7429.00
10	Providing fitting and fixing of 16 mm thick bituminous expansion joint board for expansion joint including all cost etc. complete as per the direction of Engineer-in-charge.	6.30	Rmt.	823.30	5187.00

Name of the Work: CONST. OF SMALL BRIDGE AT TANGARJORE GAMMIDHIPA, DEOBHUBANPUR GP**Tender Call Notice No: 1191 / Date. 26/07/2021**

Sl. No.	Description of Items of work	No.or Qty.	Unit	Rate in Figures (in Rs.)	Amount (in Rs.)
1	2	3	4	5	6
11	Metal spull backing in the rear steining or weep holes of abutment and for deep drains complete as per the direction of Engineer-in-charge.	65.00	Cum.	2321.20	150878.00
12	Earth work excavation in hard soil or gravelly soil Within 50m initial lead and 1.5m lift including rough dressing and breaking clods to maximum 5 to 7cm. Size including leveling and dressing all complete as per direction of Engineer- in -charge.	482.10	Cum.	155.30	74870.00
13	Rough stone dry packing in aprons and revetments with stones of 15 cm to 30cm and above size other than grinites of approved quality including all cost of materials, conveyance, royalty etc.as per direction of Engineer- in -charge.	18.75	Cum.	1333.10	24996.00
14	Turfing the slopes of teh embankments with compact Dub grass with initial lifts and lead as per direction of Engineer- in -charge.	60.00	sqm	18.20	1092.00
		Total=			4398399.00

(Rupees Forty three lakhs ninety eight thousand three hundred ninety nine)only.**My/ our quoted rate is _____ % (both figure & words) excess over /less than /equal to above estimated cost.****(Extra CGST & SGST will be paid as applicable)****The quoted rate is% (both in figure & words) excess over /less than / equal to the above estimated cost .****Notes :**

- (1) The contractor should not write anything except quoting of percentage and in case of anything else regarding tender rate mentioned, the tender liable for rejection.
- (2) Strike out which are not applicable .
- (3) CGST & SGST is applicable as per Govt. Guideline (as the above rates are **POST GST** Schedule of rates) .
- (4) quality of each item will be given top priority.

Signature of Contractor**Block Development Officer
Balisankara****Total -14 (Fourteen) Items only.**

No. of Correction

No. of Overwriting

No. of Interpolation

Approved for 14 (Fourteen) items only.**Block Development Officer
Balisankara**