

Name of the Work: Construction of CD with protection wall from Murkia to Khamanpada road, Bandega G.P.

Tender Call Notice No: 1191/ Date.26/07/2021 of 2021-22

Sl. No.	Description of work	No.or Qty.	Unit	Rate in Figures	Amount
1	2		4	5	6
1	Earth work in excavation for foundation for road work in hard soil or gravelly soil as per approved drawing and technical specifications as per clause 301 of MoRT&H specifications for Road and bridges works. (4th Revision)	460.12	Cum.	184.60	84938.00
2	Supplying & Filling foundation and plinth with sand including well watered & rammed including cost of all materials, T&P etc complete.	39.98	Cum.	319.40	12770.00
3	Cement Concrete (1:3:6) using 40mm size hard granite c.b. metal including hoisting laying using concrete mixture and vibrator including cost conveyance royalty of all materials and complete as directed by E.I.C.	235.76	Cum.	5085.60	1198981.00
4	Cement Concrete of M-15 grade with 20mm and down grade H.G.C.B. chips including hoisting, laying using concrete mixture, vibrator, waterin, curing and cost of all materials and labour, T&P centering shuttering etc complete but excluding cost of reinforcement complete.	70.40	Cum.	5048.60	355421.00
5	Cement Concrete of M-20 grade with 20mm and down grade H.G.C.B. chips including hoisting, laying using concrete mixture, vibrator, waterin, curing and cost of all materials and labour, T&P centering shuttering etc complete but excluding cost of reinforcement complete.				
A.	Bottom Slab	79.90	Cum.	5398.60	431348.00
B.	Vertical wall	77.60	Cum.	6482.20	503019.00
C.	Deck Slab	42.50	Cum.	6507.70	276577.00
6	Cement Concrete of M-30 grade with 20mm and down grade H.G.C.B. chips including hoisting, laying using concrete mixture, vibrator, waterin, curing and cost of all materials and labour, T&P centering shuttering etc complete but excluding cost of reinforcement complete.				
A.	Wearing Coat	9.40	Cum.	5645.00	53063.00
B.	Railing	36.30	Rmt.	1959.00	71112.00
7	Provision M.S. reinforcement for RCC work including cutting, bending, binding and tying the grills and placing in position uncoated HYSD bar reinforcement including cost of binding wire 18 to 20 gauge and carriage of steel.	142.60	Qtl.	7656.30	1091788.00
8	Providing weep holes in brick masonry/ plain/ Reinforced concrete abutment, wing wall/ return wall with 100mm dia AC pipe, extending through the full width of the structure etc complete.	76.15	Rmt.	114.90	8750.00
9	Providing fitting and fixing of 16mm bituminous expansion joint board for expension joints including all costs etc. complete.	6.30	Sqm.	823.30	5187.00
10	Metal spall backing in the rear of wall stening of weep holes of abutment and for deep drains etc complete.	65.00	Cum.	2337.00	151905.00
11	Cement Concrete (1:2:4) using 12mm size hard granite c.b. chips including hoisting laying using concrete mixture and vibrator including cost conveyance royalty of all materials and complete as directed by E.I.C.	1.37	Cum.	6341.30	8675.00
12	Regid and smooth centering and shuttering for RCC work including false work and dismantelling them after casting including cost of material etc comp.	504.06	Sqm.	99.90	50356.00
13	Earth work in hard soil or gravelly soil Within 50m initial lead and 1.5m lift including rough Dressing and breaking clods to maximum 5 to 7cm. Size and laying in layers not excluding to 0.30m thick or as per direction of E.I.C.	547.80	Cum.	153.80	84252.00
14	Rough stone dry packing in aprons and revetments with stones of 15cm to 30cm and above size granite of approved quality from approved quarry including cost and conveyance, royalties and taxes of all materials and labour with T&P required for the work complete as per the direction of E.I.C.	18.80	Cum.	1327.60	24959.00
15	Turfing the slopes of the embankment with compact Dub grass with initial lifts and lead as per the direction of the Engineer-in-charge.	60.00	Sqm.	18.10	1086.00
					4414187.00

(Rupees forty four lakhs fourteen thousand one hundred eighty seven)only.

My/ our quoted rate is _____ % (both figure & words) excess over /less than /equal to above estimated cost.

(Extra CGST & SGST will be paid as applicable)

Note:

- (1) The contractor should not write any thing except quoting of percentage and in case any thing else regarding tender rate mentioned , the tender is liable for rejection.
- (2) Strike out which are not applicable.

Signature of Contractor

Total -18 (Eighteen) Items only.

No. of Correction
No. of Overwriting
No. of Interpolation

Total -18 (Eighteen) Items only.

[Signature]
**Block Development Officer,
Balisankara**