

[Validate](#)[Print](#)[Help](#)

OFFICE OF THE MUNICIPAL COUNCIL:-SUNDARGARH

Bill of Quantities

Nature of Work:-Construction of Home Pipe Culvert in ward no 10

Estimated Cost:-Rs.56,000.00

Cost of Tender Paper:-Rs.448.00

EMD:- Rs.600.00

Time of Completion:- One Month

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	Earth work excavation of foundation in hard soil or gravelly soil within 50m. Initial lead and 1.5m. Initial lift including rough dressing and bracking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m. in depth and as per the direction of the engineer-in-charge.	5.40	cum	193.68	1045.87	INR One Thousand &Forty Five and Paise Eighty Seven Only
2	Filling in foundatin and plinth with sand watered and rammed	1.85	cum	283.78	524.99	INR Five Hundred & Twenty Four and Paise Ninety Nine Only
3	PCC (1:4:8) with 40 mm size HBGS metal including all cost of materials, labour, conveyance, royalty, T & P,water for curing etc.all complete	1.43	cum	4468.78	6390.36	INR Six Thousand Three Hundred & Ninety and Paise Thirty Six Only
4	PCC / RCC (1:2:4) with 12 mm size CBHGC including hosting and laying all cost of materials, labour, conveyance, royalty, Tools and Plants water for curing etc.all complete,	3.93	cum	6172.34	24257.30	INR Twenty Four Thousand Two Hundred & Fifty Seven and Paise Thirty Only
5	Rigid and smooth centering and shuttering for CC / RCC works including false works and dismantling them after casting including cost of materials complete in ground floor	11.26	sqm	101.63	1144.35	INR One Thousand One Hundred & Forty Four and Paise Thirty Five Only
6	Laying reinforcement cement Concrete Pipe NP#/ Prestressed Concrete Pipe on first class	6.00	mtr	2453.45	14720.70	INR Fourteen Thousand Seven Hundred & Twenty and Paise Seventy Only
7	Dismantling brick or stone masonry in lime or cement mortar under 3.00 mtr height including stacking the useful materials for reuse and removing the debris within 50 metres lead.	5.40	cum	1127.40	6087.96	INR Six Thousand &Eighty Seven and Paise Ninety Six Only

8	Cost of Primer,Paint,Painting & Letter writing over Disply board	1.00	no	2000.00	2000.00	INR Two Thousand Only
Total in Figures					56171.53	INR Fifty Six Thousand One Hundred & Seventy One and Paise Fifty Three Only
Quoted Rate in Figures						
Quoted Rate in Words						

No. of Correction:-
No. of Over Writings:-
No. of Interpolations:-

Signature of Contractot

Executive Officer
Sundargarh Municipality