



# ପଞ୍ଚାୟତ ସମିତିକାର୍ଯ୍ୟାଳୟ, କୋଇଡା, ଜିଲ୍ଲା- ସୁନ୍ଦରଗଡ଼, ଓଡ଼ିଶା

At /Po- koira, District- Sundargarh, State-Odisha  
Pin- 770048, email: ori-koira@nic.in

Letter No.....742

Date 27.03.2023

## Tender Call Notice No ...03.../2022-23

Sealed Tenders are invited from the interested bidder for the civil work under BDO, Koira of Sundargarh District. The detail of **works, eligibility, estimated cost ,EMD, cost of tender paper** has been uploaded in the district website [www.sundergarh.nic.in](http://www.sundergarh.nic.in). The bidder should be **C or B class contractor**. They have to submit the bid document to the undersigned in the address of **office of the the B.D.O., Koira, At./P.O. Koira, Pin-770048, Dist- Sundargarh (Odisha)** through Registered Post / Speed Post only on or before **21/04/2023, upto 01:00 PM**. The sale of tender paper will be from dated **28/03/2023** to dated **19/04/2023** in the district website [www.sundergarh.nic.in](http://www.sundergarh.nic.in). The authority reserves the right to cancel or reject the entire process without assigning any reason thereof. The tender will be opened on dated **24.04.2023 at 10.00 AM** in the office of the undersigned in the presence of the bidders or his/her representatives.

Yours faithfully,

  
Block Development Officer,  
Koira  


## Bill of Quantity (BOQ)

**Construction of New Subcentre (HWC) Building at Malda of Koira Block of Sundargarh District under OMBADC for the year 2022-23**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil or gravelly soil including dressing and leveling the bed. initial leads and lifts as per the direction of Engineer-in-charge.	90.99	Cum	199.60	18161.61
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete as per the direction of Engineer-in-charge.	105.30	Cum	697.40	73436.22
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T&P etc complete as per the direction of Engineer-in-charge.	17.24	Cum	5142.10	88649.81
4	C.C. (1:2:4) with 12mm and down grade C.B. chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and including cost, carriage, royalty, cost of all labour T.&P. etc complete as per the direction of Engineer-in-charge.	1.95	Cum	6466.70	12610.07
5	R.C.C. M-20 grade with 20mm and down grade C.B. chips including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P centering shuttering etc complete but excluding th cost of reinforcement complete as per the direction of Engineer-in-charge.				
<b>Ground Floor</b>					
5.01	Column base and footing	14.68	Cum	5424.90	79637.54
5.02	Plinth band (Grade beam)	4.81	Cum	5784.30	27822.49
5.03	Lintel	2.77	Cum	9017.20	24977.65
5.04	Lintel (First Floor)	1.82	Cum	9856.00	17937.92
5.05	Chajja (Ground Floor)	8.60	Sqm	823.20	7079.52
5.06	Chajja (First Floor)	7.67	Sqm	925.10	7095.52
5.07	Column in Superstructure, Beam (Ground Floor)	8.57	Cum	11319.60	97008.98
5.08	Column in Superstructure, Beam (First Floor)	6.69	Cum	12618.40	84417.10
5.09	Column in Superstructure, Beam (Second Floor)	2.51	Cum	14171.30	35569.97
5.1	Roof slab (Ground Floor)	12.26	Cum	9639.80	118183.95
5.11	Roof slab (First Floor)	9.94	Cum	10602.20	105385.87
5.12	Roof slab (Second Floor)	1.55	Cum	11752.90	18217.00

*[Signature]*  
24.3/23