



ପଞ୍ଚାୟତ ସମିତିକାର୍ଯ୍ୟାଳୟ, କୋଇଡା, ଜିଲ୍ଲା- ସୁନ୍ଦରଗଡ଼, ଓଡ଼ିଶା

At /Po- koira, District- Sundargarh, State- Odisha
Pin- 770048, email: ori-koira@nic.in

Letter No---743

Date: 27.03.2023

To

The DIO, NIC
Sundargarh


Sub:- Uploading the details of tender for civil works.

Sir,

With reference to subject cited above you are requested to upload the details of tender enclosed herewith as early as possible in the district website www.sundergarh.nic.in.

Encl:- Details of tender for civil works.

Yours faithfully


27/3/23
Block Development Officer
Koira

Memo No:---744

Date:- 27.03.2023

Copy submitted to the Collector &DM, Sundargarh for kind information.


27/3/23
Block Development Officer
Koira

Bill of Quantity (BOQ)

Construction of New Subcentre (HWC) Building at Malda of Koira Block of Sundargarh District under OMBADC for the year 2022-23

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil or gravelly soil including dressing and leveling the bed. initial leads and lifts as per the direction of Engineer-in-charge.	90.99	Cum	199.60	18161.61
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete as per the direction of Engineer-in-charge.	105.30	Cum	697.40	73436.22
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T&P etc complete as per the direction of Engineer-in-charge.	17.24	Cum	5142.10	88649.81
4	C.C. (1:2:4) with 12mm and down grade C.B. chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and including cost, carriage, royalty, cost of all labour T.&P. etc complete as per the direction of Engineer-in-charge.	1.95	Cum	6466.70	12610.07
5	R.C.C. M-20 grade with 20mm and down grade C.B. chips including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P centering shuttering etc complete but excluding th cost of reinforcement complete as per the direction of Engineer-in-charge.				
Ground Floor					
5.01	Column base and footing	14.68	Cum	5424.90	79637.54
5.02	Plinth band (Grade beam)	4.81	Cum	5784.30	27822.49
5.03	Lintel	2.77	Cum	9017.20	24977.65
5.04	Lintel (First Floor)	1.82	Cum	9856.00	17937.92
5.05	Chajja (Ground Floor)	8.60	Sqm	823.20	7079.52
5.06	Chajja (First Floor)	7.67	Sqm	925.10	7095.52
5.07	Column in Superstructure, Beam (Ground Floor)	8.57	Cum	11319.60	97008.98
5.08	Column in Superstructure, Beam (First Floor)	6.69	Cum	12618.40	84417.10
5.09	Column in Superstructure, Beam (Second Floor)	2.51	Cum	14171.30	35569.97
5.1	Roof slab (Ground Floor)	12.26	Cum	9639.80	118183.95
5.11	Roof slab (First Floor)	9.94	Cum	10602.20	105385.87
5.12	Roof slab (Second Floor)	1.55	Cum	11752.90	18217.00

[Signature]
24.3/23