

NAME OF THE WORK- CONSTRUCTION OF CLASS ROOM AT VESAJA PATEL HIGHER SECONDARY SCHOOL, HEMGIR,DUDUKA G.P. OF HEMGIR BLOCK

TENDER SCHEDULE

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Earth Work in exavation of foundation in ordinary soil within initial leads of 50m & lifts of 1.5m including dressing and levelling of bed etc. and adding contractor's profit and over head charges, etc. complete in all respect	cum	52.56	206.80	10869.00
2	Supplying & filling foundation and plinth with course sand well watered and rammed including cost, cost of all labour, carriage, royalty, etc complete.	cum	48.19	507.40	24452.00
3	Cement Concrete (1:3:6) using 4cm size hard granite C.B. metal approved quality from approved quarry including cost, carriage, royalty, cost of all labour. etc complete.	Cum	20.300	5847.90	118712.00
4	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 2 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
	Below Plinth	Cum	15.770	5384.40	84912.00
5	Brick work with Fly ash Bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ± 2 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage and royalty of all materials, cost of all labour, etc complete.				
	Ground Floor Qty.	Cum	22.930	5417.80	124230.00
6	R.C.C. work of M-20 grade with 20mm and down grade black hard granite (crusherbroken) stone chips including hoisting and laying	cum	34.550	6245.80	215792.00
7	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.				
	Ground Floor	Qtl	34.550	8886.10	307015.00
8	Supplying, fitting and fixing tile Printed in floors of approved make conformaing to IS:13755 laid on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
	Vetrified tiles (600x600)mm				
	Ground Floor Qty.	Sqm	95.45	1112.00	106140.00
9	2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size black hard granite chips for old & New work.	Sqm	113.90	346.60	39478.00
10	Fixing tiles in skirting and risers of steps on 12mm thick CP (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.				

	Vitrified tiles plain(600mmx600)				
	Ground Floor Qty.	Sqm	7.37	1210.70	8922.86
11	Fixing cheqred tile in floors,treads or steps on 20 mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
	Cheqred tiles				
	Ground Floor Qty.	Sqm	23.65	634.90	15015.00
12	12mm thick C.P.(1:6) on brick masonry to the smooth surface including watering, curing, cost, carriage, royalty of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor Qty.	Sqm	98.940	165.30	16355.00
13	16mm thick C.P. (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, etc complete as per the direction of E.I.C.				
	Ground Floor Qty.	Sqm	271.250	232.80	63147.00
14	Laabour charges for fitting,fixing of MS Door>window with Grill as per approved design including cost of labours etc compl.	Sqm	12.960	94.30	1222.00
15	Rigid,smooth centering and shuttering for RCC Work than dismantling after casting etc compl.				
a	Columns Base & Footings	Sqm	16.560	234.09	3877.00
b	Plinth	Sqm	14.290	234.09	3345.00
c	Beam and Column	Sqm	31.070	1011.90	31440.00
d	Lintel	Sqm	29.020	527.23	15300.00
e	Slab and chhaja	Sqm	146.970	672.63	98856.00
16	Painting two coats with approved paint on old iron work with approved enamel paints of approved colour, shade over a coat of primer including sand papering, polishing the surface, cost, conveyances of all materials and cost of all labour etc, complete as per specification & direction of Engineer-in-charge.				
	Ground Floor Qty.	Sqm	3.42	150.60	515.00
17	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade exculding cost of paint				
	Ground Floor Qty.	Sqm	271.25	88.20	23924.00
18	Priming 1 coat with wall primer water bond cement primer including all labour, materials etc. complete.				
	Ground Floor Qty.	Sqm	370.19	65.90	24396.00
19	Wall painting two coat with any approved weather coat paint including cost of all materials, labour and T&P require for the work etc. complete as directed by the E.I.C.				
	Ground Floor Qty.	Sqm	98.94	81.30	8044.00
20	Finishing wall surface with one coat of Cement based wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour etc. complete.				
	Ground Floor Qty.	Sqm	370.19	71.30	26395.00

21	Supplying, fitting and fixing of Two Track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutter and all fitting and fixtures including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
	Ground Floor Qty.	Sqm	5.76	5010.60	28861.00
22	Supplying, fitting and fixing of 32mm thick flush door shutter with approved quality of 30mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including cost of all materials, etc. required for the work all complete as per direction of E.I.C.				
	Ground Floor Qty.	Sqm	5.04	10775.30	54308.00
23	Cost of grill	kg	147.6	57.60	8502.00
24	Display Board and other unforeseen items				3000.00
	Total				1467024.86
				or say	1467025.00

The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender document will be rejected.

My/Our quoted rate is _____%(Figure) _____ (In words)

*Less than/Excess over/ Equal to the amount put to tender.

Total number of Items:..... Number of Corrections:..... Number of interpolation:..... Number of over writings:..... E.M.D Funnished/EMD Exempted (A)Demand Draft No..... (B)Ammount Rs..... Copy of PAN card:furnished/not furnished Copy of GST Registration:furnished/not furnished Copy of Contractor's Liccence:furnished/not furnished Copy of Experience certificate:furnished/not furnished Total No of sheets in the Tender Papers:.....	
---	--

Full Signature of Contractor

Signature of the Bidder/Tenderer

Signature of the B.D.O
Hemgir