

BILL OF QUANTITIES

NAME OF WORK :- REPAIR AND RENOVATION OF OF URBAN EDUCATION COMPLEX,VEDVYAS

Sl no	Item of Work or supply	Quantity	Unit	Rate	Amount
1	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper,labour,T&P etc.As per direction of Engineer-in -charge				
	GF	2602.40	SQM	72.40	188414
	1ST Floor	2022.36	SQM	74.10	149857
	2nd Floor	85.49	SQM	75.71	6472
2	Painting two coats of enamel paint on Doors and windows with all cost,labour,T&P etc. complete. As per direction of engineer- in -charge				
	GF	318.29	SQM	150.60	47935.08
	1ST Floor	332.20	SQM	154.30	51258
3	Finishing to the exposed surfaces of Wall with weather coat of any approved shade on new work two coat to give an even shade including cost of weather coat, all labour,materials, T&P etc complete.as direction of Engineer- in- charge				
	GF	849.70	SQM	81.30	69080.55
	1ST FLOOR	688.38	SQM	84.10	57893
	2nd Floor	89.65	SQM	87.10	7809
4	Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778 as window frame,section No-4095,4096 and 9777,3994 as shutter frame with rubber beading locking arrangement including all fitting,cost of all materials, including cost of 5mm thick black glass,all taxes ,labours,T&P etc completed as per direction of Engineer -in- harge	13.86	SQM	4277.70	59289
5	2.50cm thick grading concrete (1:2:2) on roof slab with 6mm size hard grainite(CB) chips on new work of approved quality from approved quarry including laying, hire charges of concrete mixture,curing, cost of all materials , water -proofing compounds ,carriage,royalty ,cost of all labour, T&P etc completed and as per direction of Engineer- in charge	589.37	SQM	351.40	207105

6	Providing and laying water proofs with polymeric Bitumin membrane)(plastic felt) of 2.25 kg/sqm and 4.00 mm thk consisting of layers having center core of 20 mm microns thermoplastic high molecular high density polyethylene H.M.H.DP.E film of grade 2504 including priming the surface with bituminous primer @ 0.3 kg /sqm providing a coat of hot blown bitumin of 1.32 kg/ sqm applying and laying plastic felt membrane with 10 cm overlap adhered to blown bitumin of 85/25 or 90/15 grade and covered with a layer of hot blown bitumen 2 1.20 kg / sqm etc . complete as per the direction of the engg.in.charge	796.59	SQM	333.90	265981
7	Cement Concrete (1:2:4) using 12mm size H.G.(CH)chips of approved quality from approved quarry including including hoisting, laying, hire charges of concrete mixture,vibrator watering,curing, cost, carriage,royalty ,cost of all labour, T&P etc completed but excluding cost of reinforcement and as per direction of Engineer- in charge	3.90	CUM	6510.30	25390.36
8	12mm thick C.P. in cement mortar in C.B.(1:6) over brick masonry to the smooth surface including watering,curing, cost ,carriage.royalty and taxes of all materials ,cost of labour, T&P etc completed as per direction of Engineer-in -charge.	321.23	Sqm	147.90	47510
9	cost of all material taxes, labour,T&P etc complete	879.30	KG	75.00	65947.50
10	Labour charges for fixing door ,windows, ventilators	19.55	Sqm	94.3	1843
11	Supplying,fitting& fixing of PPGL sheet(pre-printed galvanised sheet)of 0.50 mm thk in roof with fitting fixing of wind ties including cost ,carriage,& taxes of all materials cost of labour for fixing & cost of fitting material and drilling holes in wind ties including cost of carriage,royalty,cost of all labour,T&P etc. as per direction of engineer -in -charge.	63.20	SQM	747.00	47210
12	Brick work with Fly Ash bricks 23cmx11cmx8cm size having crushing strength not less than 75kg/cm2 with dimensional tolerance + - 8 percent in cement mortar (1:6)in Super structure including watering,curing, cost, carriage,royalty ,cost of all labour, T&P etc complete as per direction of Engineer- in charge				
	GF	11.83	CUM	4901.60	57986

	1ST FLOOR	5.94	CUM	5520.10	32789
13	Priming one coat with wall primer water bond cement primer to give an even shade including cost of weather coat, cost of all labour, materials, T&P etc complete as per direction of engineer-in-charge.				
	GF	3975.73	SQM	65.90	262001
	1st Floor	2710.74	SQM	67.50	182975
	2nd Floor	175.13	SQM	69.10	12101
14	Finishing plastered surfaces of walls with wall putty & marking smooth to Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete painting as per direction of engineer -in-charge				
	GF	3975.73	SQM	71.30	283470
	1st Floor	2710.74	SQM	72.80	197342
	2nd Floor	175.13	SQM	74.20	12995
15	Priming one coat with primer on iron work with any approved paint including cost of primer , all labour, materials, T&P etc complete as per direction of engineer-in-charge.				
	GF	318.29	SQM	60.20	19161
	1st Floor	332.20	SQM	62.80	20862
	2nd Floor	175.13	SQM	65.50	11471
16	Dismantling and Removing doors, Windows, and Ventilators including removal of frame, hinges, fastening and stacking the same for reuse and removing the debris within 50m lead as per direction of engineer-in-charge.				
	GF	17.20	SQM	343.80	5913
	2nd Floor	2.34	SQM	377.80	884
17	Removing old Lime or Cement Plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead as per direction of engineer -in-charge				
	GF	236.00	SQM	43.09	10169
18	Careful removing the bolt and nut including stacking the useful material for reuse and removing the debris within 50m lead as per direction of engineer-in charge.				
	GF	63.20	SQM	78.20	4943.12
			Sub-Total	Rs.	2414057

19	Add extra for PH items (To be paid as per actual)		LS		193089
20	Add extra for Electrification(To be paid as per actual)		LS		193089
21	Display board with writing charges		Ls		5000
			Sub-Total	Rs.	2804793.00
22	GST@18%				504863
23	Add for photgraphy				300


3309956

limited to say

Rs.

3310000

(Rupees Thirty Three Lakhs Ten Thousand Only)



Junior Engineer
Lathikata Block



Asst. Exe Engineer
Lathikata Block



Block Development Officer
Lathikata Block

My quoted Rate is%(both Figure & Word)Excess over /Less then /Equal to above estimated Cost .

Signature of the Contractor

Note

1- The Contractor should not write anything except quoting of percentage and incase of anything regarding tender

2- Strick out which are not applicable

Total:-23 (Twenty three) Items only

No. of correction:-

No.of overwriting:-

No .of Interpolation:-

Approved for 23 (Twenty Three) Items only

Signature of the Contractor