

TENDER SCHEDULE

Name of the Work= Renovation of Talsara Kata at Talsara, Talsara G.P..

Tender Call Notice No: 616 / Date. 13/2/24

Sl. No.	Description of work	No.or Qty.	Unit	Rate in Figures	Amount
1	2	3	4	5	6
1	Excavation of any approved type of soil by mechanical means loading into and transportation by mechanical means and unloading the same within initial lead of 1Km including rough dressing the earth etc. complete as per the direction of Engg-in-charge.	5000.00	Cum.	82.70	413500.00
2	Fine dressing and turffing the slopes of the Dam or dyke with compact Dub grass with initial lifts and 5 Km lead as per the Direction of the Engineer in charge.	1329.00	Sqm.	28.30	37611.00
3	Rough stone dry packing in aprons and revetment with hard granite stone (15cm to 30cm)	59.40	Cum.	2107.50	125186.00
4	Earth work in excavation foundation in Hard soil within initial lead and lift including rough dressing and bracking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3mt. In depth and as per the direction of Engg.-in-charge.	87.26	%Cum.	20472.31	17864.00
5	Filling in foundation and plinth with excavated materials including watering and ramming as directed by the department	75.60	%Cum.	11373.51	8598.00
6	Filling in foundation and plinth with sand including watering and ramming etc all complete.	21.29	Cum.	1089.70	23199.00
7	C.C. (1:3:6) with 25mm (40mm to 20mm) size h.g.c.b. metal per one cum with all complete work.	157.27	Cum.	5735.10	901959.00
8	C.C. (1:2:4) with 12mm size HGCB Chips for 1cum work with all complete work.	3.79	Cum.	7097.80	26901.00
9	Rigid smooth centering and shuttering for RCC work including false work and dismantling them after casting (mass concrete)	313.14	Sqm.	231.60	72523.00



Name of the Work= Renovation of Talsara Kata at Talsara, Talsara G.P..

Tender Call Notice No: _____ / Date. _____.

Sl. No.	Description of work	No.or Qty.	Unit	Rate in Figures	Amount
1	2	3	4	5	6
10	Providing weep holes in Brick masonry/ Plain/ Reinforced concrete abuttment, wing wall/ return wal with 100 mm dia AC/PVC pipe, extended through the full width of the structure with slope of 1V:20H towards drwaing face. Complete as per drawing and Technical	226.80	Rmt.	108.70	24653.00
11	Cost of Information Board (initial and Final)	1.00	Set	LS	8000.00
Total=					1659994.00

(Rupees sixteen lakhs fifty nine thousand nine hundred ninety four)only.**(Extra Cess, CGST & SGST will be paid as applicable)**

The quoted rate is% (both in figure & words) excess over /less than / equal to the above estimated cost .

Notes :

- (1) The contractor should not write anything except quoting of percentage and in case of anything else regarding tender rate mentioned, the tender liable for rejection.
- (2) Strike out which are not applicable .
- (3) CGST & SGST is applicable as per Govt. Guideline (as the above rates are POST GST Schedule of rates .
- (4) quality of each item will be given top priority.

Signature of Contractor
**Block Development Officer,
Balisankara****Total -11 (Eleven) Items only.**No. of Correction
No. of Overwriting
No. of Interpolation**Approved for 11 (Eleven) items only.**
**Block Development Officer,
Balisankara**