

Name of the work :-

Completion of Upstairs Madri Kalo Smruti Sadan at  
Bhojpur, Sublaya GP, Subdega of Sundargarh District

Estimated Cost :- Rs. 2542146

Cost of tender paper :-

SI No	Description of Items.	Quantity	Unit	Rate per unit (In Rs.)	Total Amount (In Rs.)
1	Supplying all labour & T&P for dismantling and removing R.C.C. columns beams slab staircase landing lintels including stacking the useful materials for reuse and removing the debris within 50m lead etc all complete as per the direction of Engineer -in - charge.	1.86 cum	Each cum.	Rs. 1361.00	Rs. 2531.00
2	Supplying all labour, materials and T&P for providing lifting, hoisting and laying R.C.C. of M-20 Grade to base of columns and footing, columns, beams, plinth band, lintels, chajja, shaft, fins, roof slabs, balconies, stair cases, parapets, window sills, lofts, railing, jally, copping or in places as shown in the drawing for all floors with 20mm and down graded size black hard crusher broken ships of approved quality from approved quarry including mixing and vibro compacting to proper shape and size, level and plumbs and finishing the exposed surfaces smooth (if required providing plaster with cement mortar (1:4) wherever necessary without any extra cost) including rigid smooth centering and shuttering, scaffolding, watering (excluding reinforcement bars) and curing for required period including cost of all material, labour, conveyance, royalty, loading and unloading, sundries, tools and plants etc. complete as per the direction of the Engineer in Charge. (1st Floor)	6.190 cum.	Each cum.	Rs. 17774.60	Rs. 110025.00
b)	Lintel band	6.71 cum.	Each cum.	Rs. 14857.00	Rs. 99690.00
c)	Chajja	27.05 cum.	Each cum.	Rs. 1281.20	Rs. 34656.00
d)	Stair case	3.06 cum.	Each cum.	Rs. 15713.70	Rs. 48084.00
e)	Roof beam	20.29 cum.	Each cum.	Rs. 15774.60	Rs. 320067.00
e)	Roof beam	64.81 cum.	Each cum.	Rs. 14086.80	Rs. 912966.00
3	Supplying all labour, materials and T&P for finishing wall surface of walls with Acrylic wall putty (Water based ) of approved make and finished smooth and even surface to receive painting with cost of scaffolding staging charges including cost, royalty, carriage & conveyance of all materials to the work site etc. all complete as per the direction of Engineer - in - charge.	631.89 sqm	Each sqm.	Rs. 78.30	Rs. 49477.00
4	Supplying all labour, materials and T&P for priming wall surface one coat with water bound or wall primer any approved make with cost of scaffolding staging charges including cost, royalty, carriage & conveyance of all materials to the work site etc. all complete as per the direction of Engineer - in - charge.	631.89 sqm	Each sqm.	Rs. 68.40	Rs. 43221.00

5	Supplying all labour, materials & T&P for fitting and placing uncoated HYSD bar reinforcement including cost, royalty, carriage & conveyance of all materials to the work site etc. all complete as per the direction of Engineer - in - charge.	92.15 qntl.	Each qntl.	Rs. 8901.80	Rs. 820301.00
6	Supplying all labour and T&P for electrification to the building (to be paid as per actual) including cost, royalty, carriage & conveyance of all materials to the work site etc. all complete as per the direction of Engineer - in - charge.	1 job	Each job.	Rs. 96128.00	Rs. 96128.00
7	Supplying all labour and T&P for construction of project pillar as per including cost, royalty, carriage & conveyance of all materials to the work site etc. all complete as per the direction of Engineer - in - charge.	1 no	Each no.	Rs. 5000.00	Rs. 5000.00

Total Rs. 2542146.00  
Or say Rs. 2542146.00

Items 7 (Seven) only.

P. S. D. S.  
15.02.24

Junior Engineer  
Subdega Block

15/02/24

Assistant Executive Engineer  
Subdega Block

15.02.24

Block Development Officer  
Subdega Block