

GOVERNMENT OF ODISHA



PANCHAYATIRAJ & DRINKING WATER DEPARTMENT

PANCHAYAT SAMITI, LAHUNIPARA

BID DOCUMENT FOR

Name of the work: - Construction of AWC at Mahulpada Dharani Sahi,
Mahulpada GP of Lahunipara Block of Sundargarh
District under OMBADC for the year 2023-24.

Block- Lahunipara

Scheme:- OMBADC

Tender Cost- Rs. 2351712.00

11	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	258.90	Sqm	160.80	41631.00
12	16mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	358.50	Sqm	228.10	81774.00
13	12mm thick cement plaster in cement mortar (1:4) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	21.01	Sqm	183.20	3849.00
14	6 MM thick Cement plaster (1:4) over RCC with close deep chiping including cost convenance	93.70	Sqm	175.70	16463.00
15	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	69.00	Sqm	1161.70	80157.00
16	Fixing of vitrified printed Tiles 600x 600 in floors,tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing,polishing	7.70	Sqm	1269.30	9774.00
17	Fixing glazed tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	26.30	Sqm	931.80	24506.00
18	Fixing glazed tiles (30cmx30cm / 40cm x 40cm special plain/printed series ceramic tiles of premium grade having thickness 7 mm to 8mm confirming to IS 13755) in floors treads or steps and landing on 20 mm thick bed of cement mortar 1:4 (1cement : 4sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles.	3.60	Sqm	876.20	3154.00
19	Supplying, fitting and fixing Industrial Vitrified tile in floors of size 300mm x 300mm of approved make conformaing to IS : 4457 laid on 20 mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of	6.30	Sqm	1025.30	6459.00
20	Supplying, fitting and fixing Industrial Vitrified tile in dados of size 300mm x 300mm of approved make conformaing to IS : 4457 laid on 12 mm thick cement mortar (1:3) (1 cement : 3 course sand) including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	2.70	Sqm	1132.90	3059.00
21	Fixing Granite tiles above 0.40 Sqm. in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	3.30	Sqm	2791.30	9211.00
22	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T.& P. required for the works etc complete.	105.10	Sqm	363.80	38235.00
23	Priming 1 coat to M.S. doors and Windows including all labour, materials, T&P etc. complete.	14.20	Sqm	61.10	868.00

24	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of E.I.C.	14.20	Sqm	152.60	2167.00
25	Finishing wall surface with Acrylic wall putty(water based)of approved make and finished smooth and even surface to receive painting including cost of scaffolding	453.70	Sqm	76.80	34844.00
26	priming one coat with all primer water bond cement primer including all labour,material,T&P etc.complete	677.10	Sqm	66.80	45230.00
27	Finishing to the exposed surface wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of labours and T&P	353.00	Sqm	82.20	29017.00
28	Wall painting with two coats plastic emulsion paint of Approved shade on new work	324.10	Sqm	89.10	28877.00
29	Supplying, fitting and fixing of 32mm thick flush door shutter with approved quality of 30mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including cost of all door fittings and fixtures etc. complete	10.50	Sqm	10775.30	113141.00
30	Supplying , fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures.	10.44	Sqm	5010.60	52311.00
31	Supplying of M.S.sheet and angle welded doors and windows with all fittings of approved design and size at worksite including all cost of materials, loading, unloading, transporting charges & priming one coats with approved primer etc complete	230.30	Kg	57.60	13265.00
	B)FRP Door	3.15	Sqm	2000.00	6300.00
32	WPC choukath with any approved quality including fitting & fixing in position complete.(Section : 10cm x 7.5cm)	26.00	RMT	600.00	15600.00
33	Fitting, fixing of iron doors / windows shutter with frame of approved design and size with all labour and T&P required for the wok etc complete as per the direction of the Engineer-in-charge.	10.90	Sqm	94.30	1028.00
34	Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018.	12.00	Sqm	490.10	5881.00
35	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxses of all material, cost of all labour etc. complete in all respect. (in all floor)	25.00	KG	290.80	7270.00
36	Electrification 5% (To bepaid as per actual maintaining all formalities)				85317.00
37	PH Work 5% (To bepaid as per actual maintaining all formalities)				85317.00
38	Bore well				91252.00
39	Tranperancy pllar				5000.00
40	Office sign board after competition				5000.00
		TOTAL			2351712.00

41	Add GST 18%			423308.00
		GRAND TOTAL RS		2775020.00
	Total Estimated cost in Figures		say Rs	2775020.00
(Rupees Twenty seven lakhs seventy five thousand twenty) Only.				
	Quoted Amount		Rs	
	Quoted Rate in Works		Rs	

My quoted rate is
 (both in figures & words) Excess over/ Less than /equal to above estimated
 cost of Rs.....

Signature of the tenderer.

Note:

1. The bidders should not write anything excepting quoting of percentage and in case anything else regarding tender rate
2. Stricke out which are not applicable.

01. Total No. of Corrections.....
02. Total No. of Overwritings.....
03. Total No. of Interpolations.....
04. E.M.D. Furnished
- a) Pledged Rs.....
- b) Un-Pledged Rs.....
05. Pan Cardfurnished
06. GST.C.C.....furnished
07. Total No. of Tender Papers.....



**Block Development Officer
Lahunipara**