

GOVERNMENT ODISHA



PANCHAYATIRAJ & DRINKING WATER DEPARTMENT
OFFICE OF THE BLOCK DEVELOPMENT OFFICER LEPHRIPARA BLOCK,
SUNDARGARH

BIDS DOCUMENT FOR:-

Name of Work: - CONSTRUCTION OF MODEL ANGANWADI
CENTRE AT FITTINGPARA OF CHEHATENPALI G.P UNDER
LEPHRIPARA BLOCK


Tender Cost: - 20, 43,187/-

TENDER SCHEDULE

NAME OF THE WORK :- CONSTRUCTION OF MODEL ANGANWADI CENTRE AT CHHATENPALI FITTINGPARA ,					
Sl. No	Item of Work	Unit	Qty.	Rate	Amount
1	Earth work in excavation of foundation in hard soil or gravelly soil including dressing and leveling the bed and disposal of the excavated materials within initial leads and lifts as per direction of E.I.C.	cum	94.770	211.00	19,996.00
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete.	cum	50.400	1,079.30	54,397.00
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed	cum	23.900	5,480.80	1,30,991.00
4	Cement Concrete (1:2:4) using 12mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed	cum	3.260	6,978.90	22,751.00
5	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	CUM	31.810	5,292.70	1,68,361.00
6	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent in cement mortar (1:6) in Above Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	CUM	45.900	5,326.00	2,44,463.00
7	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent in cement mortar (1:4) in Above Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	CUM	3.000	5,560.10	16,680.00
8	R.C.C. M-20 grade with 20mm and down grade C.B. chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P centering shuttering etc compl	cum	34.100	5,965.40	2,03,420.00
9	Reinforcement for RCC Structures	QTL	35.510	8,875.70	3,15,176.00
10 (a)	Rigid smooth centering and shuttering for Column base and footings	SQM	21.900	234.70	5,140.00
(b)	Rigid smooth centering and shuttering for plinth band	SQM	20.500	234.70	4,811.00
(c)	Rigid smooth centering and shuttering for lintel band	SQM	30.400	529.40	16,094.00


 Block Development Office,
 Fittingpara

Sl. No	Item of Work	Unit	Qty.	Rate	Amount
(d)	Rigid smooth centering and shuttering for beams and column	SQM	47.900	1,022.00	48,954.00
(e)	Rigid smooth centering and shuttering for roof slab & chajja	SQM	138.000	676.90	93,412.00
11	12mm thick C.P. in C.M.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	SQM	258.900	162.10	41,968.00
12	16mm thick C.P. in C.M.(1:6) over brick masonry to the rough surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	SQM	358.500	229.70	82,347.00
13	12mm thick C.P. in C.M.(1:4) over brick masonry to the smooth surface with neat cement punning including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	SQM	21.010	183.60	3,857.00
14	6 mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chiping and slury treatment , watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	SQM	93.700	175.70	16,463.00
15	2.5 cm thick DPC in CC (1:2:4) using 12 mm size hgcb chips including all cost of materials , labour , carriage etc	SQM	20.200	324.00	6,545.00
16	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conformaing to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	SQM	69.000	1,155.00	79,695.00
17	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	SQM	7.700	1,260.60	9,707.00
18	Fixing glazed tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	SQM	26.300	923.10	24,278.00
19	Fixing glazed tiles (30cmx30cm / 40cm x 40cm special plain/printed series ceramic tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floors and treads of steps on 20mm thick cement plaster (1:4) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	SQM	3.600	869.60	3,131.00


 Block Development Office
 Sophipara

Sl. No	Item of Work	Unit	Qty.	Rate	Amount
20	Supplying fitting & Fixing industrial vitrified floor tiles (30cmx30cm) plain/printed series confirming to IS 4457 on 20mm thick cement plaster (1:4) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	SQM	6.300	1,018.60	6,417.00
21	Supplying fitting & Fixing industrial vitrified tiles in dadoes (30cmx30cm) plain/printed series confirming to IS 4457 on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	SQM	2.700	1,124.20	3,035.00
22	Supplying fitting & Fixing granite tiles above 0.40 sqm in floors treads or steps on 20 mm thick bed of cement mortar (1:4) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	sqm	3.300	2,784.70	9,190.00
23	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T.& P. required for the works etc complete.	SQM	105.100	344.10	36,165.00
24	Finishing walls with cement based wall putty & making smooth to receive painting including cost of scaffolding etc. with cost of all materials , labour T & P etc. complete .	SQM	453.700	76.80	34,844.00
25	Priming 1 coat MS door and windows including all labour, materials, T&P etc. complete.	SQM	14.200	61.10	868.00
26	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of E.I.C.	SQM	14.200	152.60	2,167.00
27	Priming 1 coat with wall primer water bound cement paint including all labour, materials, T&P etc. complete.	SQM	677.100	66.80	45,230.00
28	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete .	SQM	353.000	82.20	29,017.00
29	Wall painting with plastic emulson paint of approved shade on new work to give an even shade including cost of paint etc	SQM	324.100	89.10	28,877.00
30	Supplying fitting fixing 32 mm Flush door shutter with approved quality of 30 mm thick BWR block board pasted with 1 mm thick sunmica on both side of approved design and quality including cost of all door fittings and fixtures	SQM	10.500	10,775.30	1,13,141.00
31	Supplying fitting and fixing of two track UPVC sliding windows of aproved make with 6mm thick glass of approved quality complete with frame , shutters and all fittings	SQM	10.440	5,010.60	52,311.00

Handwritten signature
26.2.24

Block Development Office
: adhipara

Sl. No	Item of Work	Unit	Qty.	Rate	Amount
32	Supplying of MS sheet and angle welded doors and windows with all fittings of approved design and size at work site including cost of materials etc	Kg.	392.300	57.60	22,596.00
33	WPC chowkaths with any approved quality including fitting & fixing in position complete (section : 10 cm x 7.50 cm)	Rmt	26.000	600.00	15,600.00
34	Cost of FRP door for toilet (0.75 m x 2.10 m size)	SQM	3.150	2,000.00	6,300.00
35	Fitting fixing of iron door / window shutter with frame of approved design and size with all labour and T & P required for the work complete	SQM	17.400	94.30	1,641.00
36	Supplying and fixing of 60 mm thick factory made C.C interlocking paver Block of M-30 grade of approved mke design , colour and size made by Block making machine with proper compaction laid in required pattern etc	SQM	12.000	490.10	5,881.00
37	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	RM	25.000	290.80	7,270.00
38	Transparency pillar	Nos	1.000	5,000.00	5,000.00
39	Cost of Sign board after completion	Nos	1.000	5,000.00	5,000.00
					20,43,187.00

(Rupees Twenty lakhs forty three thousand one hundred eighty seven) only.

(Extra CGST & SGST will be paid as applicable)

The quoted rate is% (both in figure & words) excess over /less than / equal to the

Notes :

- (1) The contractor should not write anything except quoting of percentage and in case of anything else regarding
- (2) Strike out which are not applicable .
- (3) CGST & SGST is applicable as per Govt. Guideline (as the above rates are POST GST Schedule of rates .
- (4) quality of each item will be given top priority.

Signature of Contractor

[Signature]
Block Development Office,
Lephripara
Block Development Officer,
Lephripara

Total - 39 (thirty nine) Items only.

No. of Correction
No. of Overwriting
No. of Interpolation

Approved for 39 (Thirty nine) Items only.

[Signature]
Block Development Office,
Lephripara
Block Development Officer,
Lephripara