

BILL OF QUANTITY (BOQ)

Name of the work - "Construction of Model Anganwadi Center at D.Tankatola, Garjan GP Under Lathikata Block"

TENDER SCHEDULE

SL.NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE	AMOUNT(RS)
1	Earth work in excavation of foundation in hard soil Within initial load of 50m. and 1.5m. initial lift Including rough dressing and leveling the bed as directed by the Engineer-in-charge.	CUM	94.77	211.00	19996
2	Filling in Foundation and Plinth with sand well watered and rammed including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	CUM	50.40	521.50	26284
3	Cement Concrete(1:3:6) with 4 Cm. size H.G.C.B. metal including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	CUM	23.90	5367.10	128274
4	C.C (1:2:4) with 12mm and down grade C.B. chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C.	CUM	3.26	6909.00	22510
5	2.5 cm thick damp Proof Course in cement Concrete (1:2:4) using 12 mm size hgcb chips with all cost of materials, conveyance, labour, T&P etc. complete.	SQM	20.20	321.70	6498
6	Brick masonry work with Fly Ash bricks in cement mortar (1:6) F & P including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	CUM	31.81	5045.00	160476
7	Brick masonry work with Fly Ash bricks in cement mortar (1:6) in super structure including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	CUM	45.90	5078.40	233099
8	Brick masonry work with Fly Ash bricks in cement mortar (1:4) in super structure including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	CUM	3.00	5323.50	15971
9	RCC work of M 20 grade with 20 mm and down grade black hard granite (Crusher Broken) chips including hoisting and laying & royalty of materials etc. complete as per the direction of Engineer-in-charge.	CUM	34.10	5903.70	201316
10	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.	QTL	32.11	8875.70	284963
11	Rigid smooth centering and shuttering for RCC work including flase work and dismantling them after casting				
	(a) Column base footings	SQM	21.90	234.90	5145
	(b) Plinth Band	SQM	20.50	234.90	4815
	(c) Lintel Band	SQM	30.40	529.80	16106
	(d) Beam and Column	SQM	47.90	1022.60	48983
	(e) Roof slab, Chajja.	SQM	138.00	677.60	93509
12	12 mm. thick cement plaster with cement mortar (1:6) over brick work including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	SQM	258.90	155.00	40130
13	12mm thick C.P. in C.M.(1:4) over brick masonry to the smooth surface with neat cement punning including watering curing, cost, carriage, royalty, and taxes of all	SQM	21.01	177.40	3728
14	16 mm. thick cement plaster with cement mortar (1:6) over brick work including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	SQM	358.50	221.10	79264
15	6 mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chipping and slury treatment , watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	SQM	93.70	172.80	16191
16	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conformaing to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	SQM	69.00	1143.30	78888
17	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	SQM	7.70	1253.20	9650
18	Fixing glazed tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	SQM	26.30	915.80	24086
19	Fixing glazed tiles (30cmx30cm / 40cm x 40cm special plain/printed series ceramic tiles of premium grade having thickness 7 mm to 8mm confirming to IS 13755) in floors treads or steps and landing on 20 mm thick bed of cement mortar 1:4 (1cement : 4sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles.	SQM	3.60	857.90	3088
20	Supplying, fitting and fixing Industrial Vitrified tile in floors of size 300mm x 300mm of approved make conformaing to IS : 4457 laid on 20 mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	SQM	6.30	1006.90	6343
21	Supplying, fitting and fixing Industrial Vitrified tile in dadoses of size 300mm x 300mm of approved make conformaing to IS : 4457 laid on 12 mm thick cement mortar (1:3) (1 cement : 3 course sand) including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	SQM	2.70	1116.90	3016



22	Fixing Granite tiles above 0.40 Sqm. in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	SQM	3.30	2773.00	9151
23	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T. & P. required for the works etc complete.	SQM	105.10	340.10	35745
24	Priming 1 coat to M.S. doors and Windows including all labour, materials, T&P etc. complete.	SQM	14.20	61.10	868
25	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of	SQM	14.20	152.60	2167
26	Finishing surface of walls with Cement based wall putty & making smooth to receive painting including cost of scaffolding etc. with cost of all materials, labour T&P etc. complete.	SQM	453.70	76.80	34845
27	Priming 1 coat with wall primer water bond cement primer including all labour, materials, T&P etc. complete.	SQM	677.10	66.80	45230
28	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete.	SQM	353.00	82.20	29017
29	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc complete.	SQM	324.10	89.10	28877
30	Supplying, fitting and fixing of 32mm thick flush door shutter with approved quality of 30mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including cost of all door fittings and fixtures etc. complete	SQM	10.50	10775.30	113141
31	Supplying, fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures.	SQM	10.44	5010.60	52311
32	Supplying of M.S. Gate, M.S. sheet and angle welded doors and windows with all fittings of approved design and size at worksite including all cost of materials, loading, unloading, transporting charges & priming one coats with approved primer etc complete				
	a) M.S. Grill & M.S. Gate	KG	230.30	57.60	13265
	b) FRP Door D3	SQM	3.15	2000.00	6300
	c) WPC chokath with any approved quality including fitting & fixing in position complete. (Section : 10cm x 7.5cm)	RMT	26.00	600.00	15600
33	Fitting, fixing of iron doors / windows shutter with frame of approved design and size with all labour and T&P required for the work etc complete as per the direction of the Engineer-in-charge.	SQM	10.90	94.30	1028
34	Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018.	SQM	12.00	490.10	5881
35	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	KG	25.00	290.80	7270
36	Cost for Electrification (To be paid as per actual maintaining all formalities)	LS			79162
37	Cost for PH & Sanitary (To be paid as per actual maintaining all formalities)	LS			79162
38	Cost Of Transparency Board	LS			5000
39	Cost of Office Sign Board after completion of work.	LS			5000
40	Cost Of Site development, approach road, photography & other unforeseen items etc.	LS			700
SINKING OF 125MM x 100MM DIA TUBE WELL THROUGH FAST DRILLING SOPHISTICATED RIG (DTH)					
41	Supplying all Labour & T & P for drilling a perfectly vertical bore of specified dia for a specified depth below ground level through consolidated and unconsolidated rock with down the hole hammer drilling rigs or combination drilling rigs (650 cfm/ 2.00 psi) as required to suit the site condition as per the direction of Engineer-in-Charge including use of own rigs with its accessories, tools and plants and consumables etc. for lowering of 125mm dia PVC/GI pipes for housing fitted with socket and with or without well screen as per the necessity for soft, medium, hard and boulder formation (GI/PVC casing pipes if required to prevent collapse of over burden is to be provided by the contractor including lowering and withdrawing after completion of the tube well)				
	00 mtr to 30.00 mtr	Mtr	30.00	680.00	20400
	30 mtr to 90.00 mtr	Mtr	60.00	560.00	33600
42	Labour for Lowering the 125mm dia PVC/G.I. pipes with or without soltted pipes as per the necessity from ground level and fitted up in perfectly vertical position including cutting and threading pipe and soltted pipe and supplying and fixing all joints materials, tools and plants etc. complete and keeping the top of the casing pipe threaded including plugging tube wells to prevent entry of foreign materials from above.	Mtr	30.00	121.00	3630

43	clear and adequate discharge is obtained from the tube well including supply and use of all necessary equipment and labour as per the direction of Engineer-in- Charge	No	1 00	3622 00	3622
44	Cost of submersible Pump 1 HP Including all fitting and fixing in position, cost of cable wire, rope wire, HDPE, panel board etc. complete.	No	1 00	30000 00	30000
	Total 1 to 44(Amount put to tender)				2193298
	Contingency @1%				21933
	GST (18%)				394794
	G.TOTAL				2610025
		Limited to Say RS			2610000

(Rupees twenty six lakhs ten thousand) only

L. Swain
Junior Engineer
Lathikata Block

[Signature]
Asst. Exe Engineer
Lathikata Block

[Signature]
Block Development Officer
Lathikata Block

The tenderer are required to put their percentage of rate in the blank space given below, falling which the tenderer document will be rejected.

my/our quoted rate is _____%(figure)_____ (in words)

*Less than/Excessover/Equal to the amount put to tender.

Total number of items.....	
Number of corrections.....	
Number of interpolation.....	
Number of over writing.....	
E.M.D. Furnished/E.M.D. Exempted	
(A)Demand Draft No.....	
(B)Amount RS.....	
Copy PAN card furnished/not furnished	
Copy of GST Registration furnished/not furnished	
Copy of contractor Licence:furnished/not furnished	
Copy of Experience certificate:furnished/not furnished	
Total No. of sheets in the Tender Paper.....	

(Full Signature Of Contractor)

Signature Of Contractor

Signature Of Contractor