

Bill of Quantity

Upgradation of Kukuridihi Sub centre for NQAS under Subdega block for the year 2024-25 (Under DMF)					
Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation hard soil or gavelly soil including dressing and levelling the bed within initial leads and lifts as per direction of Engineer-in-charge.	30.71	Cum	269.70	8282.49
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost of all materials, T&P etc complete as per direction of Engineer-in-charge.	9.90	Cum	524.40	5191.56
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B metal including hoisting laying using concrete mixture and vibrators including cost of all materials labour T.&P. etc complete as per direction of Engineer-in-charge.	8.99	Cum	5768.10	51855.22
4	Cement Concrete (1:2:4) with 12mm and down grade C.B. chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and including cost, carriage, royalty, cost of all labour T.&P. etc complete as per direction of Engineer-in-charge.	8.31	Cum	7365.00	61203.15
5	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance \pm 2 percent in cement mortar (1:6) in F&P including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per direction of Engineer-in-charge.	2.07	Cum	5538.20	11464.07
6	16mm thick Cement Plaster in cement mortar (1:6) over brick masonry to the smooth surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of Engineer-in-charge.	21.75	Sqm	264.70	5757.23
7	Supplying fitting, fixing fully glazed aluminum framed fixed windows (Ventilator) using 15 micron anodized OEL aluminum section 2082 as out section, 9139 as mullion section, 4124 as a shutter section frame with tapered clip of section 4125, aluminum angle , rubber beading, etc. as per the direction of Engineer-in-charge.	27.65	Sqm	6624.90	183178.49

8	Providing and fitting of zinc coated wire mesh for windows, door and ventilators including cost of all materials, labour T&P etc. complete as per direction of Engineer-in-charge.	27.65	Sqm	372.20	10291.33
9	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size 32 mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, labour, T&P etc. required for the complete in all respect as per the direction of Engineer-in-charge.	157.50	Kgs	342.40	53928.00
10	Providing fitting and fixing of Informatory Sign Board using high efficiency full cube retro reflective sheeting on white colour bonded on to 4 mm aluminium composite panel (0.25 + 3.5 + 0.25 pdvf coated) over which alphabets and number and reverse cut with computerised cutting plotter, the board shall be provided with frame made out of stainless pipe shall be mounted on vertical posts made out of 80 mm N.R, Stainless pipe as have installed including necessary excavation for foundation, concreting, reveting etc. necessary for fixing of the board including cost, conveyance, taxes of all materials, all labour and T&P, required for the work as per direction of the Engineer -In -Charge.	15.00	Sft	1904.40	28566.00
11	Providing fitting and fixing of AAM Nomenclature using high efficiency full cube retro reflective sheeting on white colour bonded on to 4 mm aluminium composite panel (0.25 + 3.5 + 0.25 pdvf coated) over which alphabets and number and reverse cut with computerised cutting plotter as per the direction of Engineer in Charge.	27.76	Sft	199.50	5538.12
12	Supply all material, Providing fitting & fixing of Aquaguard Sure Delight NXT RO+UV water purifier with wall hanging facility having storage of 6 liters etc. with internal water supply connection complete as per the direction of Engineer-in-charge.	1.00	Nos	11864.40	11864.40
13	Providing, Fitting, & fixing of 100mm dia PVC rain water pipe as per the direction of Engineer-in-charge.	20.00	Rmt	382.70	7654.00
14	Construction of 1.20m dia Sharp pit & deep burial pit as per the direction of Engineer-in-charge.	2.00	Nos	17556.70	35113.40

15	Providing Colour & Branding of Health Wellness Centre in weather coat colour with all labour, material, T&P, taxes etc complete as per the direction of Engineer in Charge.	92.97	Sft	63.50	5903.60
16	Providing Colour & Branding of Health Wellness Centre door, window border in weather coat colour with all labour, material, T&P, taxes etc complete as per the direction of Engineer in Charge.	330.12	Rft	62.30	20566.48
Total 16 (Sixteen) items		Total Estimated Cost		5,06,358.00	
				(Rupees Five Lakh Six Thousand Three Hundred Fifty Eight) Only	

My quoted rate is % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

- 1 The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.
- 2 Strick out which are not applicable.

Total :- 16 (Sixteen) Items only

No. of correction :-

No.of overwriting :-

No. of Interpolation :-

Approved for 16 (Sixteen) Items only

Full signature of the Contractor with date.

**Chief District Medical & Public Health Officer,
Sundargarh**