

ଓଡ଼ିଶା ସରକାର



ପଞ୍ଚାୟତ୍ତରାଜ ଓ ପାନୀୟଜଳ ବିଭାଗ,
ଓଡ଼ିଶା
ପଞ୍ଚାୟତ ସମିତି କାର୍ଯ୍ୟାଳୟ, କୁତ୍ରା

BIDS DOCUMENT FOR:-

**Name of Work:-Construction of Multy Purpose Community-
cum- Cultural Building at Telighana,
Kandeimunda GP, Kutra Block**

Tender Cost: - Rs. 21,75,650 /-

TENDER SCHEDULE

Name of the Work: Construction of Multy Purpose Community- cum- Cultural Building at Telighana, Kandeimunda GP

Tender Amount : Rs. 21,75,650/- (Rupees Twenty one lakh seventy five thousand six hundred fifty) only

Scheme: - Welfare of Minority Communities

Name of the Work:- Construction of Multy Purpose Community- cum- Cultural Building at Telighana, Kandeimunda GP					
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil or gravelly soil including dressing and leveling the bed and disposal of the excavated materials within initial leads and lifts as per direction of E.I.C.	48.20	cum	270.90	13,057.00
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete.	46.50	cum	1,002.80	46,630.00
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C.	11.60	cum	6,067.80	70,386.00
4	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	11.40	CUM	5,720.00	65,208.00
5	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent in cement mortar (1:6) in Above Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.				-
	(i) Ground Floor	20.20	cum	5,753.30	116,217.00
	(ii) First Floor	17.40	cum	6,124.10	106,559.00
	(iii) Second Floor (Head room)	7.60	cum	6,550.50	49,784.00
6	Brick masonry work with Fly Ash bricks in cement mortar (1:4) in super structure including cost of carriage, royalty of all materials etc complete as per the direction of E.I.C. (Ground Floor)	1.70	CUM	5,973.80	10,155.00

Signature of Contractor

Block Development Officer, Kutra


7	R.C.C. M-20 grade with 20mm and down grade C.B. chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P etc complete but excluding cost of reinforcement complete.				-
	(i) Ground Floor	32.90	cum	6,189.70	203,641.00
	(ii) First Floor	18.80	cum	6,309.30	118,615.00
	(iii) Second Floor	4.10	cum	6,446.90	26,432.00
8	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.				-
	(i) Ground Floor	28.00	Qtl.	8,678.00	242,984.00
	(ii) First Floor	16.00	Qtl.	8,710.70	139,371.00
	(iii) Second Floor	3.50	Qtl.	8,745.10	30,608.00
9	Rigid smooth centering shuttering for R.C.C.work including all cost etc complete				-
(i)	(Ground Floor)				
a	Column base footings	12.71	SQM	247.70	3,149.00
b	Plinth Band	22.75	SQM	247.70	5,635.00
c	Lintel Band	28.98	SQM	570.80	16,543.00
d	Beam and Column	54.59	SQM	1,189.90	64,958.00
e	Roof slab,Chajja	87.19	SQM	755.70	65,893.00
f	Stair case	20.35	SQM	1,043.70	21,241.00
(ii)	First Floor				
a	Lintel Band	19.73	SQM	684.90	13,513.00
b	Beam and Column	51.41	SQM	1,427.80	73,397.00
c	Roof slab,Chajja	87.05	SQM	906.80	78,935.00
d	Stair case	20.35	SQM	1,252.40	25,488.00
(iii)	Second Floor				
a	Lintel Band	8.40	SQM	821.90	6,907.00
b	Beam and Column	6.85	SQM	1,713.40	11,740.00
c	Roof slab,Chajja	26.48	SQM	1,088.20	28,812.00
10	12mm thick C.P. in C.M.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.				
a	Ground Floor	122.80	SQM	191.10	23,467.00
b	First Floor	99.10	SQM	198.70	19,691.00
c	Second Floor	43.80	SQM	206.70	9,053.00

Signature of Contractor


 Block Development Officer, Kutra

11	16mm thick C.P. in C.M.(1:6) over brick masonry to the rough surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.				
a	Ground Floor	181.10	SQM	274.60	49,732.00
b	First Floor	103.40	SQM	281.50	29,096.00
c	Second Floor	39.10	SQM	288.50	11,274.00
12	2.5 cm thick A.S. Flooring with cement concrete (1:2:4) using 12mm size CB chips including curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc. complete as per direction of E.I.C.				
a	Ground Floor	68.20	SQM	405.40	27,648.00
b	First Floor	62.50	SQM	419.40	26,213.00
13	12mm thick C.P. in C.M.(1:4) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.				
a	Ground Floor	11.30	SQM	211.50	2,390.00
b	First Floor	10.60	SQM	216.10	2,291.00
14	Fixing glazed tiles (30cmx30cm / 40cm x 40cm special plain/printed series ceramic tiles of premium grade having thickness 7 mm to 8mm confirming to IS 13755) in floors treads or steps and landing on 20 mm thick bed of cement mortar 1:4 (1cement : 4sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including cost of tiles.	8.00	SQM	908.40	7,267.00
15	Fixing glazed tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	33.50	SQM	986.60	33,051.00
16	Cement washing one coat including curing cost of all labours and cost of all materials etc. complete as per the direction of E.I.C.				
a	Ground Floor	335.30	SQM	18.00	6,035.00
b	First Floor	254.30	SQM	18.40	4,679.00
c	Second Floor	97.70	SQM	18.70	1,827.00

Signature of Contractor


 Block Development Officer, Kutra

17	Distempering 2 coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper and labour, T&P etc, complete				
a	Ground Floor	212.50	SQM	86.60	18,403.00
b	First Floor	155.30	SQM	88.70	13,775.00
c	Second Floor	53.90	SQM	90.80	4,894.00
18	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete .				
a	Ground Floor	122.80	SQM	95.90	11,777.00
b	First Floor	99.10	SQM	99.50	9,860.00
c	Second Floor	43.80	SQM	103.20	4,520.00
19	Supplying of MS Sheet and angel welded door and windows with all fitting of approved design and size at work sites including all cost of materials ,loading unloading,trasporting charges and priming one coat with approved primer etc. complete				-
a	Door	321.30	Kg	70.20	22,555.00
b	Window	850.50	Kg	68.00	57,834.00
c	Grill	345.60	Kg	57.60	19,907.00
d	Collapsible gate	1.00	Nos	10,000.00	10,000.00
e	PVC door including fixing in position lumpsum	3.15	SQM	1,500.00	4,725.00
20	Priming 1 coat to M.S doors and windows including all labour, materials, T&P etc. complete.				
a	Ground Floor	38.70	SQM	73.60	2,848.00
b	First Floor	61.60	SQM	76.80	4,731.00
c	Second Floor	5.00	SQM	80.30	402.00
21	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of E.I.C.				
a	Ground Floor	38.70	SQM	182.00	7,043.00
b	First Floor	61.60	SQM	186.70	11,501.00
c	Second Floor	5.00	SQM	191.50	958.00

Signature of Contractor


 Block Development Officer, Kutra

22	20mm thick CP in cm (1:4) over concrete surface to the smooth surface including curing, cost of carriage, royalty and Taxes of all materials, cost of all labour, T&P, etc complete as per the direction of the E.I.C.				
a	First Floor	55.10	SQM	305.50	16,833.00
b	Second Floor	21.70	SQM	312.50	6,781.00
23	Fitting, fixing of iron doors/window shutter with frame with approved design and size with all labours with T & P etc.	58.00	SQM	94.30	5,469.00
24	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	85.00	Kg	297.20	25,262.00
25	Display Board	2	Nos		6,000.00
				Say	21,75,650.00

(Rupees Twenty one lakh seventy five thousand six hundred fifty) only


4/1/25
Junior Engineer
KUTRA BLOCK


4/1/25
Asst. Executive Engineer
KUTRA BLOCK


Block Development Officer
KUTRA BLOCK

My quoted rate is % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

1. The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.
2. Strick out which are not applicable.

Total: - 25 (Twenty five) Items only

No. of correction:-

No. of overwriting:-

No. of Interpolation:-

Approved for 25 (Twenty five) Items only

Full Signature of the Contractor with date

Block Development Officer
Kutra

Signature of Contractor

Block Development Officer, Kutra