

**BOQ**

NAME OF WORK :-		CONSTRUCTION OF NEW GRAM PANCHAYAT OFFICE OF DUDUKA G.P.			
NAME OF GP :-		DUDUKA			
Sl No	Items of work	Quantity	Unit	Rates in Rs	Amount in Rs
1	2	3	4	5	6
1	Earth Work in hard soil or gravelly soil within 50 m. initial lead and 1.5 m initial lift including rough dressing & breaking clods to maximum 5 cm to 7 cm & laying in layer not exceeding 0.30 m in depth etc.complete.	108.60	CUM	270.90	29420.00
2	Filling in foundation and plinth with sand watered and rammed including cost, carriage, royalties and taxes etc. all complete	81.90	CUM	1773.90	145282.00
3	Cement Concrete (1:3:6) with 4 cm size hard granite metal including cost,carriage,royalties and taxes of all materials etc.	20.30	CUM	6617.30	134331.00
4	Brick work with Fly Ash bricks 23cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm2 with dimensional tolerance ±8 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	58.70	CUM	5955.00	349559.00
5	Brick work with Fly ash . Bricks, in cement mortar (1:6) for super structure including cost, carriage, royalties and taxes of all materials etc. complete.	52.8	CUM	5988.3	316182
1ST FLOOR		16.10	CUM	6359.10	102382.00
6	Brick work with Fly Ash bricks 23cm x 12cm x 8cm size having crushing strength not less than 35Kg/cm2 with dimensional tolerance ±8 percent in cement mortar (1:4) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	2.80	CUM	6208.80	17385.00
7	R.C.C. work of M-20 grade with 20mm and down grade black h.g.(c.b.)chips including hoisting and laying with all cost,TC&Royalty etc.	67.70	CUM	6704.90	453922.00
1ST FLOOR		5.10	CUM	6824.50	34805.00
8	Labour for MS Reinforcement for RCC work including cutting, bending, binding & tying the grills and placing in position including cost of binding wire 18 to 20 gauge including cost of MS Rod.	64.30	QNTL	8665.30	557179.00
1ST FLOOR		4.30	QNTL	8698.10	37402.00
9	Rigid & smooth centering and shuttering for RCC works including false work and dismantling then after casting including cost of materials complete in ground floor including cost, carriage, royalties and taxes of all materials etc.		CUM		
i	Coloumn Base footing & Mass concrete	25.01	SQM	247.70	6195.00

*Handwritten signature and date: 21.1.20*

Fixing che  
thick cen  
pigment  
complete  
17

ii	plinth bend	40.34	SQM	247.70	9991.00
iii	Beam/ Column in super structure	120.69	SQM	1189.90	143611.00
iv	Lintel	71.50	SQM	570.80	40812.00
v	Chajja & Roof Slab	226.77	SQM	755.70	171370.00
vi	in fins	19.68	SQM	1061.90	20898.00
vii	Stair Case	13.66	SQM	1043.70	14253.00
	<b>1ST FLOOR</b>				
i	Beam/ Column in super structure	18.48	SQM	1427.80	26386.00
ii	Lintel	8.83	SQM	684.90	6048.00
iii	Chajja & Roof Slab	23.90	SQM	906.80	21673.00
iv	in fins	2.43	SQM	1274.20	3096.00
10	12 mm thick cement plaster (1:6) for brick work including cost, carriage, royalties and taxes of all materials etc.	219.80	SQM	202.70	44553.00
	1ST FLOOR	145.20	SQM	210.30	30536.00
11	16 mm thick cement plaster (1:6) for brick work including cost, carriage, royalties and taxes of all materials etc.	460.40	SQM	288.50	132825.00
	1ST FLOOR	40.30	SQM	295.40	11905.00
12	Fixing verified tiles (600mmx600nn) plain in floors treads steps and landing on 20mm thick bed of cement mortar (1:4) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including all cost ,required for the work all complete as per direction of E.I.C	137.10	SQM	1174.10	160969.00
13	Fixing verified tiles in (600mmx600nn) printed dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles Data for 10Sqm	18.30	SQM	1352.90	24758.00
14	Fixing Vitrified industrial tiles (size 300mmx300mm) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	52.90	SQM	1216.50	64353.00
	1ST FLOOR	1.60	SQM	1236.40	1978.00
15	Fixing Vitrified Industrial tiles in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	29.60	SQM	1090.90	32291.00
	1ST FLOOR	6.20	SQM	1104.10	6845.00
16	Fixing Chequered tiles in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	6.80	SQM	697.30	4742.00

*Handwritten signature and date: 21.1.25*

17	Fixing chequered tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including all cost	2	SQM	840.6	1681
18	Finishing wall surface with wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour T&P etc. complete.	847	SQM	89.8	76060.6
	1ST FLOOR	185.5	SQM	91.6	16991.8
19	Priming 1 coat with wall primer water bond cement primer including all labour, materials, T&P etc. complete.	844.9	SQM	79.3	67001
	1ST FLOOR	200.7	SQM	81.3	16317
20	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete .	219.8	SQM	95.9	21079
	1st FLOOR	145.2	SQM	99.5	14447
21	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc complete.	560.9	SQM	102.8	57661
	1ST FLOOR	40.3	SQM	104.9	4227
22	Painting two coats on doors, windows with all cost etc complete	18.3	SQM	182	3331
	1ST FLOOR	3.1	SQM	186.7	579
23	Priming 1 coat with primer on iron work including all labour, materials, T&P etc. complete.	18.3	SQM	73.5	1345.05
	1ST FLOOR	3.1	SQM	75.5	234
24	Labour charges for fitting, fixing M.S. gates (M.S. Door, collapsible gates) as per approved design including cost of all labour, T&P etc. complete.	9.8	SQM	94.3	924
25	Labour charges for fitting, fixing M.S. , Window with grills, as per approved design including cost of all labour, T&P etc. complete.	26.1	SQM	16.4	428
	Cost of MS Doors & windows	899.1	KG	57.6	51788
26	Supplying fitting fixing of P.V.C. door of approved quality including cost of all materials labour T&P etc complete.	69.4278	SFT	171.7	11920.75
27	Supplying, fitting and fixing of 32mm thick flush door shutter with approved quality of 30mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including cost of all door fittings and fixtures etc. complete	16.4	SQM	10775.3	176715
28	Supplying , fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures.	21.06	SQM	5010.6	105523

*Handwritten signature and date:*  
21.1.25

29	Supplying, fitting, fixing up window(sliding type) made up of aluminium Section 9778 as windows frame, section No. 4095, 4096 and 9777, 3994 as shutter frame with rubber beeding incuding locking arrangement including all fitting including cost of materials all taxes labour, T&P etc. complete as per direction of Engineer-in-charge excluding cost of glass.	2.88	SQM	4626.9	13325
30	Supplying, fitting, and fixing of stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mmx32mmx2mm @0.90mtr C/C and stainless square pipe bracing of size 32mmx32mmx2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc. With cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect	16.3	SQM	3113.9	50757
31	Add for internal & external Electrifications etc	As per actual voucher (GST will be provided extra)			192459.00
32	Add for PH Sanitary				192459.00
33	Transparency board 1 nos		LS		3000.00
34	office sign board after completion of work		LS		3000.00
35	Add site development, approach road, dressing, photography & unforeseen item		LS		1000.00
				<b>Total</b>	<b>4242190.20</b>

OR SAY **4242190.00**

The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender document will be rejected.

My/Our quoted rate is \_\_\_\_\_ % (figure) \_\_\_\_\_ (in words)

\*Less than/Excess over/ Equal to the amount put to tender.

Total number of Items: ..... Number of Corrections: ..... Number of interpolation: ..... Number of over writings: ..... E.M.D Funnished/EMD Exempted (A) Demand Draft No ..... (B) Ammount Rs ..... Copy of PAN card furnished/not furnished Copy of GST Registration: furnished/not furnished Copy of Contractor's Licencence: furnished/not furnished Copy of Experience certificate: furnished/not furnished Total No of sheets in the Tender Papers: .....	Full Signature of Contractor
---	------------------------------

*[Handwritten signature]*  
21.1.24