

(4)

BOQ

NAME OF WORK :-		CONSTRUCTION OF PEO QTR WITH TOILET, GP GODOWN, COMPOUND WALL			
NAME OF GP :-		DUDUKA			
Sl No	Items of work	Quantity	Unit	Rates in Rs	Amount in Rs
1	2	3	4	5	6
1	Earth Work in hard soil or gravelly soil within 50 m. initial lead and 1.5 m initial lift including rough dressing & breaking clods to maximum 5 cm to 7 cm & laying in layer not exceeding 0.30 m in depth etc. complete.	151.20	CUM	270.90	40960.00
2	Filling in foundation and plinth with sand watered and rammed including cost, carriage, royalties and taxes etc. all complete	84.90	CUM	1773.90	150604.00
3	Cement Concrete (1:3:6) with 4 cm size hard granite metal including cost, carriage, royalties and taxes of all materials etc.	31.00	CUM	6617.30	205136.00
4	Brick work with Fly Ash bricks 23cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm ² with dimensional tolerance ± 8 percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	61.10	CUM	5955.00	363851.00
5	Brick work with Fly ash . Bricks, in cement mortar (1:6) for super structure including cost, carriage, royalties and taxes of all materials etc. complete.	93.4	CUM	5988.30	559307.00
6	C.C. (1:2:4) with 12mm and down grade C.B. chips approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C.	3.60	CUM	8174.60	29429.00
7	R.C.C. work of M-20 grade with 20mm and down grade black h.g.(c.b.)chips including hoisting and laying with all cost, TC&Royalty etc.	69.70	CUM	6704.90	467332.00
8	Labour for MS Reinforcement for RCC work including cutting, bending, binding & tying the grills and placing in position including cost of binding wire 18 to 20 gauge including cost of MS Rod.	65.90	QNTL	8665.30	571043.00
9	Rigid & smooth centering and shuttering for RCC works including false work and dismantling then after casting including cost of materials complete in ground floor including cost, carriage, royalties and taxes of all materials etc.		CUM		
i	Coloumn Base footing & Mass concrete	56.59	SQM	247.70	14017.00
ii	plinth bend	53.32	SQM	247.70	13207.00
iii	Beam/ Column in super structure	135.64	SQM	1189.90	161398.00
iv	Lintel	53.63	SQM	570.80	30612.00
v	Chajja & Roof Slab	170.54	SQM	755.70	128878.00

10	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T.& P. required for the works etc complete.	142.10	SQM	411.50	58474.00
11	12 mm thick cement plaster (1:6) for brick work including cost, carriage, royalties and taxes of all materials etc.	586.51	SQM	202.70	118886.00
12	16 mm thick cement plaster (1:6) for brick work including cost, carriage, royalties and taxes of all materials etc.	680.50	SQM	288.50	196324.00
13	Fixing verified tiles (600mmx600nn) plain in floors treads steps and landing on 20mm thick bed of cement mortar (1:4) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including all cost ,required for the work all complete as per direction of E.I.C	46.60	SQM	1174.10	54713.00
14	Fixing verified tiles in (600mmx600nn) printed dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles Data for 10Sqm	29.20	SQM	1352.90	39505.00
15	Fixing Vitrified Industrial tiles in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	19.40	SQM	1090.90	21163.00
16	Fixing glazed tile tile tiles in (300mmx300nn) dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete excluding cost of precast tiles Data for 10Sqm	46.60	SQM	1015.40	47318.00
17	Finishing wall surface with wall putty (water based) of approved make and finished smooth & even surface to receive painting including cost of scaffolding etc. with cost of all materials, labour T&P etc. complete.	494.6	SQM	89.80	44415.00
18	Priming 1 coat with wall primer water bond cement primer including all labour, materials, T&P etc. complete.	1276.5	SQM	79.30	101226.00
19	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete .	864.5	SQM	95.90	82906.00
20	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc complete.	196.1	SQM	102.80	20159.00
21	Painting two coats on doors, windows with all cost etc complete	69.5	SQM	182.00	12649.00
22	Priming 1 coat with primer on iron work including all labour, materials, T&P etc. complete.	69.5	SQM	73.50	5108.00
23	Labour charges for fitting, fixing M.S. gates (M.S. Door, collapsible gates) as per approved design including cost of all labour, T&P etc. complete.	33.9	SQM	94.30	3197.00
24	Labour charges for fitting, fixing M.S. , Window with grills, as per approved design including cost of all labour, T&P etc. complete.	8.50	SQM	16.40	139.00
25	Cost of MS Doors & windows	392.4	KG	70.20	27546.00
a	grill door, ventilater,grill	191.2	KG	57.60	11013.00

Handwritten signature
21.1.25

b	window	666.9	KG	68.00	45349.00
c	collapsible gate	LS			15000.00
26	Supplying fitting fixing of P.V.C. door of approved quality including cost of all materials labour T&P etc complete.	81.93896	SFT	171.70	14069.00
27	2.5cm thick A.S. flooring with cement concrete (1:2:4) using 12mm size C.B. chips including curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	49	SQM	419.00	20531.00
28	12 mm thick C.P. in C.M.(1:4) over brick masonry to the smooth surface including curing cost of carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of Engg-in -charge.	14.7	SQM	223.10	3280.00
29	Distemping 2 coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper and labour, T & P. etc complete.	215.9	SQM	86.60	18697.00
30	Add for internal & external Electrifications etc	As per actual voucher (GST will be provided extra)			174592.00
31	Add for PH Sanitary				117923.00
32	Tube well	LS (As per actual measurement)			245000.00
33	Add site development, approach road ,dressing,photography & unforeseen item				2355.00
				Total	4237311.00

The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender document will be rejected.

My/Our quoted rate is _____%(Figure) _____ (In words)

*Less than/Excess over/ Equal to the amount put to tender.

Total number of Items:..... Number of Corrections:..... Number of interpolation:..... Number of over writings:..... E.M.D Funnished/EMD Exempted (A)Demand Draft No..... (B)Ammount Rs..... Copy of PAN card:furnished/not furnished Copy of GST Registration:furnished/not furnished Copy of Contractor's Liccence:furnished/not furnished Copy of Experience certificate:furnished/not furnished Total No of sheets in the Tender Papers:.....	
---	--

Full Signature of Contractor

Signature of the Bidder/Tenderer

Signature of the B.D.O
Hemgir