

### Tender Schedule

#### Construction of Addl. Class room at Govt. Primary School, Murkila , Bandega GP

Sl. No.	Name of the Item	Unit	Quantity	Unit Rate (Rs.)	Amount (Rs.)
1	Earth work in excavation of foundation in hard soil Within initial lead of 50m.and 1.5m.initial lift Including rough dressing and leveling the bed as directed by the Engineer-in-charge.	Cum.	47.200	270.90	12786.00
2	Filling in Foundation and Plinth with sand well watered and rammed including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	Cum.	44.300	1116.00	49439.00
3	Cement Concrete(1:3:6)with 4 Cm..size H.G.C.B. metal including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	Cum.	16.200	6256.60	101357.00
4	Brick masonry work with Fly Ash bricks in cement mortar (1:6) F & P including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	Cum.	11.900	5606.10	66713.00
5	Brick masonry work with Fly Ash bricks in cement mortar (1:6) in super structure including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	Cum.	18.100	5639.50	102075.00
6	RCC work of M 20 grade with 20 mm and down grade black hard granite (Crusher Broken) chips including hosting and laying & royalty of materials etc. complete as per the direction of Engineer-in-charge.	Cum.	35.200	6229.70	219285.00
7	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.	Qtl.	31.700	8782.50	278405.00
8	Rigid smooth centering and shuttering for RCC work including flase work and dismantling them after casting.				
a	Column base footings	Sqm.	13.700	247.70	3393.00
b	Plinth Band	Sqm.	16.000	247.70	3963.00
c	Lintel Band	Sqm.	27.300	570.80	15583.00
d	Beam and Column	Sqm.	65.000	1189.90	77344.00
e	Roof slab, Chajja.	Sqm.	127.800	755.70	96578.00
9	12 mm. thick cement plaster with cement mortar (1:6) over brick work including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	Sqm.	148.700	189.10	28119.00
10	16 mm. thick cement plaster with cement mortar (1:6) over brick work including cost, carriage & royalty of materials etc. complete as per the direction of Engineer-in-charge.	Sqm.	114.100	272.20	31058.00
11	6 mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chiping and slury treatment , watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	Sqm.	115.900	208.10	24119.00

  
 Block Development Officer  
 Balisankara

12	Supplying, fitting and fixing vitrified tile (Plain) in floors of size 600mm x 600mm of approved make conforming to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	Sqm.	81.800	1145.70	93718.00
13	Fixing Vitrified tiles (size 600mmx600mm) (Plain) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqm.	6.810	1272.20	8664.00
14	Supplying, fitting and fixing vitrified Industrial tile in floors on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	Sqm.	15.600	1062.60	16577.00
15	Fixing Vitrified industrial tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqm.	1.350	1189.00	1605.00
16	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T. & P. required for the works etc complete.	Sqm.	95.300	391.30	37291.00
17	Priming 1 coat with red oxide primer to M.S. doors and Windows including all labour, materials, T&P etc. complete.	Sqm.	30.400	73.50	2234.00
18	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of E.I.C.	Sqm.	30.400	182.00	5533.00
19	Finishing surface of walls with Cement based wall putty & making smooth to receive painting including cost of scaffolding etc. with cost of all materials, labour T&P etc. complete.	Sqm.	378.700	89.80	34007.00

  
 Block Development Officer  
 Balisankara

20	Priming 1 coat with wall primer water bond cement primer including all labour, materials, T&P etc. complete.	Sqm.	378.700	79.30	30031.00
21	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete.	Sqm.	148.700	95.90	14260.00
22	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc complete.	Sqm.	230.000	102.80	23644.00
23	Fitting, fixing of iron doors / windows shutter with frame of approved design and size with all labour and T&P required for the wok etc complete as per the direction of the Engineer-in-charge.	Sqm.	9.430	94.30	889.00
24	Supplying of M.S.sheet and angle welded doors and windows with all fittings of approved design and size at worksite including all cost of materials, loading, unloading, transporting charges & priming one coats with approved primer etc complete				
	M.S. Doors, windows and ventilator etc.	Kg.	396.000	88.23	34939.00
25	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless aquare pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	Rmt.	12.500	3113.90	38924.00
<b>Sub-Total (A)</b>					<b>1452533.00</b>
26	Add for Transparency Board. (5'x5') size	No.	1		3500.00
<b>G.TOTAL</b>					<b>1456033.00</b>

**(Rupees Fourteen Lakhs Fifty Six Thousand Thirty Three) Only.  
( Extra Cess, CGST & SGST will be paid as applicable )**

The Tenderer are required to put their percentage of rate in theblank space givenbelow, falling which the

**My/Our quoted rate is \_\_\_\_\_ % ( both in figure & Notes :**

- (1) The contractor should not write anything except quoting of percentage and in case of anything else
- (2) Strike out which are not applicable .
- (3) CGST & SGST is applicable as per Govt. Guideline. ( as the above rates are POST GST Schedule of
- (4) Quality of each item will be given top priority.

**Signature of Contractor**

  
**Block Development Officer,**  
**Balisankara**  
**Block Development Officer**  
**Balisankara**

**Total -25 (Twenty Five) Items only.**

No. of Correction : \_\_\_\_\_  
No. of Overwriting : \_\_\_\_\_  
No. of Interpolation : \_\_\_\_\_

**Approved for 25 (Twenty Five) items only.**

**Signature of Contractor**

  
**Block Development Officer,**  
**Balisankara**  
**Block Development Officer**  
**Balisankara**