

GOVERNMENT OF ODISHA



PANCHAYATIRAJ & DRINKING WATER DEPARTMENT

PANCHAYAT SAMITI, LAHUNIPARA

BID DOCUMENT FOR

**Name of the Work:- Construction of Kalyan Mandap near
G.P Office, Fuljhar.**

Block: - Lahunipara

Scheme: - 2024-25

Tender Cost: - 30, 00,000/-

10	12mm thick cement plaster in cement mortar (1:6) over brick masonry including watering,curing,cost,conveyance,taxes & royalty complete etc.Ground floor	234.26	Sqm	157.20	36826.00
11	6 MM thick Cement plaster (1:4) over RCC with close deep chipping including cost conveyance	119.360	Sqm	173.00	20649.00
12	Fixing Vitrified printed tiles in dados skirting and risers of steps on 12 mm. thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete.	4.75	Sqm	1246.60	5921.00
13	Fixing of vitrified printed Tiles 600x 600 in floors,tread or steps and landing on 20mm thick C.M(1:4) jointed with cement slurry mixed with pigment to match the shades including cost of rubbing,polishing	72.14	Sqm	1139.30	82189.00
14	Fixing ceramic floor tiles in floors, treads of steps and landing on 25mm. thick bed of cement mortar 1:1 (1 Cement : 1 Sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles	5.67	Sqm	856.60	4857.00
15	Fixing tiles in dados skirting and risers of steps on 12 mm. thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including rubbing and polishing complete including cost of precast tiles.	12.96	Sqm	912.50	11826.00
16	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T.& P. required for the works etc complete.	98.60	Sqm	354.40	34944.00
17	Finishing wall surface with Acrylic wall putty(water based)of approved make and finished smooth and even surface to receive painting including cost of scaffolding	310.14	Sqm	75.50	23416.00
18	priming one coat with all primer water bond cement primer including all labour,material,T&P etc.complete	584.00	Sqm	66.20	38661.00
19	Wall painting with two coats plasticemulsion paint of Approved shade on new work	310.14	Sqm	88.30	27385.00
20	Finishing walls with weather coat paint of approved shade on new work 2 coats to give an even shade.	273.86	Sqm	81.40	22292.00
21	Manufacturing and supplying of M.S. door, window, M.S. grill, collapssible gate including all cost all taxes and carriage of materials to work site etc.complete the work. (To be paid as per actual)	662.04	Kg	57.00	37736.00
22	Supplying, fitting and fixing of 32mm thick flush door shutter with approved quality of 30mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including cost of all door fittings and fixtures etc. complete	3.78	Sqm	10668.61	40327.00

23	Supplying , fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures.	8.91	Sqm	4960.67	44200.00
24	Supplying all labour, materials and T&P for enamel painting two coats to Doors, windows & M.S. Grill including cost, conveyance and carriage etc all complete as per the direction of Engineer - in - charge.	38.55	Sqm	151.10	5825.00
25	Supplying fitting and fixing of fiber door with Iron frame including cost, all taxes and carriage etc all complete as per the direction of Engineer - in - charge. (To be paid as per actual)	3.15	Sqm	2500.00	7875.00
26	sinking of 125x100mm dia Borewell through ODEX rig	1.00	no	228039.00	228039.00
27	Fitting, fixing of iron doors / windows shutter with frame of approved design and size with all labour and T&P required for the wok etc complete as per the direction of the Engineer-in-charge.	27.54	Sqm	94.30	2597.00
		TOTAL			2105941.00
28	Add 9.60% of Estimated cost towards Electricfiction				202052.00
29	Add 9.60% of Estimated cost water supply and sanitation				202052.00
				Rs	2510045.00
30	Add GST 18%				451808.00
				Rs	2961853.00
31	Add labour cess	1	1	29604.00	29619.00
32	Add towards cost of Display board	1	1	10000.00	10000.00
		GRAND TOTAL RS			3001472.00
				say Rs	3000000.00
Total Estimated cost in Figures					
					(Rupees Thirty lakhs) Only.
Quoted Amount				Rs	
Quoted Rate in Works				Rs	

My quoted rate is (both in figures & words) Excess over/ Less than /equal to above estimated cost of Rs.....

Signature of the tenderer.

Note:
1. The bidders should not write anything excepting quoting of percentage and in case anything else
2. Stricke out which are not applicable.

01. Total No. of Corrections.....

Approved for

- 02. Total No. of Overwritings.....
- 03. Total No. of Interpolations.....
- 04. E.M.D. Furnished
.....
 - a) Pledged
Rs.....
 - b) Un-Pledged
Rs.....
- 05. Pan Cardfurnished
- 06. V.A.T.C.C.....furnished
- 07. Total No. of Tender Papers.....


Block Development Officer
Lahunipara

Sold to

Sri.....
Class of contractor on payment of Rs. (Rupees
.....) only vide Money Receipt No.
Dated.....


Block Development Officer
Lahunipara