

4

Name of the Work "Construction of Office Building with Market complex for Grampanchayat Level federations at Sanaghumuda G.P. of Hemgir Block.

TENDER SCHEDULE

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work excavation in foundation in hard soil within initial lead 50m. & lift 1.5 m. including rough dressing, breaking clods, laying in layers. Etc. Complete	cum	72.40	270.90	19613.00
2	Filling F & P with sand, well watered and rammed with cost, carriage and royalty etc. complete	cum	81.50	1596.00	130074.00
3	Cement Concrete in (1:3:6) using 40mm. Size H.G. metal including laying compacting, Curing with cost, carriage and royalty etc. complete	cum	22.40	5916.50	132530.00
4	R.C.C. M-20 Grade With 20mm and down Grade C.B. Chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator watering, curing and cost of all materials and labour, T & P etc Complete but excluding cost of reinforcement complete.	cum	46.80	5910.80	276625.00
5	Labour for straightening , Cutting, bending & binding the M.S. Road including cost of binding wire and cost of MS Road	Qtnl	46.80	8782.50	411021.00
6	Rigid and smooth centering and shuttering for R.C.C. work and dismantling then after casting including cost of all materials complete				
	(A) Shutter for Sub structure	Sqmt	22.30	247.50	5519.00
	(B) Plinth Band	Sqmt	21.00	247.50	5198.00
	(C) Column & Beam	Sqmt	69.40	1189.30	82537.00
	(D) Lintel Band	Sqmt	33.30	570.30	18991.00
	(E) Roof Slab & Chajja	Sqmt	166.80	755.00	125934.00
7	Brick work with Fly Ash Bricks 23cm x 12cm x 8cm size having crushing strength not less than 75kg/cm ² with dimensional tolerance ± 8 Percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	cum	24.50	5835.70	142975.00
8	Fly ash Brick Masonry in C.M. (1:6) with all Finishing, Curing in superstructure etc. complete	cum	22.10	5869.00	129705.00
9	Fly ash Brick Masonry in C.M. (1:4) with all Finishing, Curing in superstructure etc. complete	cum	2.40	6055.70	14534.00
10	16mm thick C.P. in C.M. (1:6) over brick masonry to the rough surface including watering, curing cost, Carriage, royalty and taxes of all materials, cost of all labour, T&P etc. etc complete as per the direction of E.I.C.	Sqmt	319.60	280.90	89776.00
11	12mm thick C.P. in C.M (1:6) Over brick Masonry to the smooth surface including watering, Curing, cost, carriage, royalty and taxes of all materials, cost of all labour T&P etc. complete as per the direction of E.I.C.	Sqmt	173.10	196.30	33980.00

12	6mm thick cement plaster (1:4) to RCC surfaces finisher smooth including closed deep chipping and slurry treatment, watering, curing cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	Sqmt	95.00	211.70	20112.00
13	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conforming to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	Sqmt	100.40	1208.50	121333.00
14	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqmt	9.80	1332.00	13054.00
15	Fixing Industrial tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including cost of tiles.	Sqmt	26.90	1072.10	28839.00
16	Fixing Vitrified industrial tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqmt	40.60	1195.60	48541.00
17	Finishing to the surfaces of wall with Two coat Wall Putty of any approved shade for inside and Out side wall	Sqmt	414.60	89.80	37231.00
18	Finishing to the interier surfaces of wall with Two Coat Emulsion Paint of any approved shade for Out side wall	Sqmt	414.60	102.80	42621.00
19	Priming 1 coat with wall primer water bond cement primer including all labour, Materials, T&P etc Complete	Sqmt	587.70	79.30	46605.00
20	Finishing to the exposed surfaces of wall with weather coat of any approved shade for Out side wall	Sqmt	173.10	95.90	16600.00
21	Supplying of M.S. Window made out of M.S. Angle frame, M.S. Flat, Sheet Etc. of approved section & Design Electrically welded properly with all necessary locking arrangement, and 1 coat red oxide primer including cost of all materials, labour T&P, Carriage of materials to site etc. complete				
	A) M.S. rolling shutter	KG	356.90	67.70	24162.00
	B) M.S. Door	KG	433.00	70.20	30396.00
	C) M.S. Window	KG	674.40	68.00	45859.00
	D) M.S. Grill	KG	18.00	57.60	1037.00
22	Supplying ,Fitting and fixing of PVC Door of approved quality etc Completed.	Sqmt	4.40	2000.00	8800.00

23	Priming 1 coat over Door and Window primer including all labour, Materials, T&P etc Complete	Sqmt	91.80	73.50	6747.00
24	Enamel paint two coat for Door and Window	Sqmt	91.80	182.00	16708.00
25	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	Rmt	10.65	3113.90	33163.00
26	Fixing M.S. angle and Door and Window etc Completed.	Sqmt	37.60	94.30	3546.00
27	2.5cm thic grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken Granite chips on new work including watering curing cost of all materials water-proofing compounds, T&P required for the works etc complete	Sqmt	130.60	389.40	50856.00
28	Add for PH Work				140667.00
29	Add for Electrification work				140667.00
30	Transpaarency Board				2966.10
31	Add towards cost of fire Fighting arrangement				4661.00
32	Add towards Rain water Hearvesting System (Recharge Pit)				12711.86
33	Add for Antitermite treatment in foundation trenches and flooring with approved Chemical				6779.66
					2523674.62
				Limited to	2523600.00

The tenderer are required to put their percentage of rate in the blank space given below, failing which the tenderer document will be rejected.

My/Our quoted rate is _____%(Figure)_____ (in words)

*Less than/Excessover/Equal to the amount put to tender

Total number of items..... Number of corrections..... Number of interpolation..... Number of over writing..... E.M.D Furnished /E.M.D Exampted (A)Demand Draft No..... (B)Amount Rs..... Copy PAN card furnished /not furnished Copy of GST Registration:furnished /not furnished Copy of contractor Licenence:furnished /not durnished copy of Experience certificate:furnished/not furnished Total No of sheets in the Tender paper.....	
---	--

Full Signature of Contractor

Signature of the Bidder/Tenderer

Signature of the B.D.O
Hemgir