

ଓଡ଼ିଶା ସରକାର



ପଞ୍ଚାୟତ୍ତରାଜ ଓ ପାନୀୟଜଳ ବିଭାଗ,  
ଓଡ଼ିଶା  
ପଞ୍ଚାୟତ ସମିତି କାର୍ଯ୍ୟାଳୟ, କୁତ୍ରା

**BIDS DOCUMENT FOR:-**

**Name of Work:-Construction of GPLF Office Building with  
Market Complex at Biringatoli, Biringatoli  
GP, Kutra Block**

**Tender Cost: - Rs. 21,57,520 /-**

## TENDER SCHEDULE

**Name of the Work:** Construction of GPLF Office Building with Market Complex at Biringatoli, Biringatoli GP

**Tender Amount :** Rs. 21,57,520/- (Rupees Twenty one lakh fifty seven thousand five hundred twenty) only

**Scheme: -** Construction of GPLF Office Building with Market Complex 2024-25

Name of the Work:-Construction of GPLF Office Building with Market Complex at Biringatoli, Biringatoli GP					
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil or gravelly soil including dressing and leveling the bed and disposal of the excavated materials within initial leads and lifts as per direction of E.I.C.	72.4	cum	270.90	19,613.00
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete.	81.5	cum	1,016.00	82,804.00
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C.	22.4	cum	5,774.30	129,344.00
4	Brick work with Fly Ash bricks 23cm x 12cm x 8cm size having crushing strength not less than 75Kg/cm <sup>2</sup> with dimensional tolerance $\pm 8$ percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	24.5	CUM	5,635.20	138,062.00
5	Brick masonry work with Fly Ash bricks in cement mortar (1:6) in super structure including cost of carriage, royalty of all materials etc complete as per the direction of E.I.C.	22.1	CUM	5,668.60	125,276.00
6	Brick masonry work with Fly Ash bricks in cement mortar (1:4) in super structure including cost of carriage, royalty of all materials etc complete as per the direction of E.I.C.	2.4	CUM	5,855.20	14,052.00

*Jm*  
28/3/25

Signature of Contractor

Block Development Officer, Kutra

7	R.C.C. M-20 grade with 20mm and down grade C.B. chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P etc complete but excluding cost of reinforcement complete.	46.8	CUM	5,777.60	270,392.00
8	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.	46.8	Qntl	8,782.50	411,021.00
g	Rigid smooth centering shuttering for R.C.C.work including all cost etc complete				-
a	Column base footings	22.3	SQM	247.70	5,524.00
b	Plinth Band	21	SQM	247.70	5,202.00
c	Lintel Band	33.3	SQM	570.80	19,008.00
d	Beam and Column	69.4	SQM	1,189.90	82,579.00
e	Roof slab,Chajja	166.8	SQM	755.70	126,051.00
10	12mm thick C.P. in C.M.(1:6) over brick masonry to the smooth surface including watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	173.1	SQM	187.60	32,474.00
11	16mm thick C.P. in C.M.(1:6) over brick masonry to the rough surface including watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	319.6	SQM	270.40	86,420.00
12	6 mm thick cement plaster (1:4) to RCC surfaces finished smooth including closed deep chiping and slury treatment , watering, curing cost, carriage, royalty, and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	95	SQM	207.40	19,703.00
13	2.5cm thick grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken granite chips on new work including watering curing cost of all materials, water-proofing compounds, T. & P. required for the works etc complete.	130.6	SQM	382.00	49,889.00
14	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conformaimg to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	100.4	SQM	1,187.00	119,175.00

*Jho 28/3/25*

Signature of Contractor

Block Development Officer, Kutra

15	Fixing Vitrified coloured/printed tiles (size 600mmx600mm) (Plain) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	9.8	SQM	1,314.00	12,877.00
16	Fixing industrial verified tiles in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	26.9	SQM	1,050.70	28,264.00
17	Fixing industrial verified tiles in dado skirting and risers of steps and on 12mm thick bed of cement plaster 1:3 (1cement : 3sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	40.6	SQM	1,177.70	47,815.00
18	Priming (Red Oxide) 1 coat to M.S doors and windows including all labour, materials, T&P etc. complete.	91.8	SQM	73.50	6,747.00
19	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of E.I.C.	91.8	SQM	182.00	16,708.00
20	Finishing surface of walls with Cement based wall putty & making smooth to receive painting including cost of scaffolding etc. with cost of all materials, labour T&P etc. complete.	414.6	SQM	89.80	37,231.00
21	Priming 1 coat with wall primer water bond cement primer including all labour, materials, T&P etc. complete.	587.7	SQM	79.30	46,605.00
22	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete .	173.1	SQM	95.90	16,600.00
23	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc complete.	414.6	SQM	102.80	42,621.00
24	Supplying, fitting and fixing MS iron door, window & grills as per approved design and quality including cost of all cost of materials and labour etc complete as per direction of Engineers in charge.				
	(a) MS Rolling shutters	356.9	Kg	67.70	24,162.00
	(b) M.S Door	433	Kg	70.20	30,396.00
	(c) M.S Window	674.4	Kg	68.00	45,859.00

Signature of Contractor

Block Development Officer, Kutra

	(d)M.S Grill	18	Kg	57.60	1,037.00
	(e)PVC Door	4.4	SQM	2,000.00	8,800.00
25	Labour charges of Fitting,fixing of MS gates(M.S Door, Window with grill, Grills collapsible gates)as per approved design including cost of all labour with T & P etc.	37.6	SQM	94.30	3,546.00
26	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	10.65	Rmt	3,113.90	33,163.00
27	Cost of Fire fighting arrangement				5,000.00
28	Anti termite treatment in foundation, trenches and flooring with approved chemical				10,000.00
29	Display Board	1	Nos		3,500.00
				Say	2,157,520.00
<b>(Rupees Twenty One Lakh Fifty Seven Thousand five Hundred Twenty Only)</b>					

  
Junior Engineer  
KUTRA BLOCK

  
Asst. Executive Engineer  
KUTRA BLOCK

  
Block Development Officer  
KUTRA BLOCK


My quoted rate is ..... % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

1. The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.
2. Strick out which are not applicable.  
Total: - 29 (Twenty nine) Items only  
No. of correction:-  
No. of overwriting:-  
No. of Interpolation:-  
Approved for 29 (Twenty nine) Items only

Full Signature of the Contractor with date

Signature of Contractor

  
Block Development Officer  
Kutra  
  
Block Development Officer, Kutra