

ଓଡ଼ିଶା ସରକାର



ପଞ୍ଚାୟତ୍ତିରାଜ ଓ ପାନୀୟଜଳ ବିଭାଗ,
ଓଡ଼ିଶା
ପଞ୍ଚାୟତ ସମିତି କାର୍ଯ୍ୟାଳୟ, କୁତ୍ରା

BIDS DOCUMENT FOR:-

**Name of Work:-Construction of GPLF Office Building with
Market Complex at Gangajal, Gangajal GP,
Kutra Block**

Tender Cost: - Rs. 21,80,705 /-

TENDER SCHEDULE

Name of the Work: Construction of GPLF Office Building with Market Complex at Gangajal, Gangajal GP

Tender Amount : Rs. 21,80,705/- (Rupees Twenty one lakh eighty thousand seven hundred five) only

Scheme: - Construction of GPLF Office Building with Market Complex 2024-25

Name of the Work:- Construction of GPLF Office Building with Market Complex at Gangajal, Gangajal GP					
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil or gravelly soil including dressing and leveling the bed and disposal of the excavated materials within initial leads and lifts as per direction of E.I.C.	72.40	cum	270.90	19,613.00
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete.	81.50	cum	1,134.30	92,445.00
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C.	22.40	cum	5,957.40	133,446.00
4	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size in cement mortar (1:6) in Foundation and Plinth including cost of carriage & royalty and taxes of all materials etc complete as per the direction of E.I.C.	24.50	CUM	5,658.90	138,643.00
5	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size in cement mortar (1:6) in Super Structure including cost, carriage, royalty and taxes of all materials etc complete as per the direction of E.I.C.	22.10	cum	5,692.20	125,798.00
6	Brick masonry work with Fly Ash bricks in cement mortar (1:4) in super structure including cost of carriage, royalty of all materials etc complete as per the direction of E.I.C. (Ground Floor)	2.40	CUM	5,878.80	14,109.00
7	R.C.C. M-20 grade with 20mm and down grade C.B. chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P etc complete but excluding cost of reinforcement complete.	46.80	cum	5,949.20	278,423.00

Signature of Contractor

[Handwritten Signature]
Block Development Officer, Kutra

8	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.	46.80	Qtl.	8,782.50	411,021.00
9	Rigid smooth centering shuttering for R.C.C.work including all cost etc complete				-
a	Column base footings	22.30	SQM	247.70	5,524.00
b	Plinth Band	21.00	SQM	247.70	5,202.00
c	Lintel Band	33.30	SQM	570.80	19,008.00
d	Beam and Column	69.40	SQM	1,189.90	82,579.00
e	Roof slab,Chajja	166.80	SQM	755.70	126,051.00
10	12mm thick C.P. in C.M.(1:6) over brick work including cost, carriage & royalty of materials etc complete as per the direction of E.I.C.	173.10	SQM	189.40	32,785.00
11	16 mm thick C.P. in C.M.(1:6) over brick work including cost, carriage & royalty of materials etc complete as per the direction of E.I.C.	319.60	SQM	272.60	87,123.00
12	6mm thick C.P. in C.M.(1:4) to RCC surfaces finished smooth including closed deep chipping and slury treatment watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	95.00	SQM	208.30	19,789.00
13	2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size CB chips including curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc. complete as per direction of E.I.C.	130.60	SQM	386.20	50,438.00
14	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conformaing to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement: 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the	100.40	SQM	1,189.50	119,426.00
15	Supplying, fitting and fixing vitrified tile Coloured/Printed tiles (size 600mm x 600mm) in dados skirting & rises on 12mm thick cement mortar (1:3) and filling joints with neat cement slurry mixed with pigment to match the shade of the tiles including all cost, carriege, royalty & taxes of all materials, cost of all labours T&P etc complete.	9.80	SQM	1,315.80	12,895.00

Signature of Contractor

Dr. 28/3/25

 Block Development Officer, Kutra

16	Fixing industrial verified tile in floors treads or steps and on 20mm thick bed of cement mortar 1:4 (1cement : 4 sand) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete	26.90	SQM	1,053.10	28,328.00
17	Fixing vetrified industrial tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete	40.60	SQM	1,179.40	47,884.00
18	Priming (Red Oxide) 1 coat to M.S doors and windows including all labour, materials, T&P etc. complete.	91.80	SQM	73.50	6,747.00
19	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of E.I.C.	91.80	SQM	182.00	16,708.00
20	Finishing of walls with Cement based wall putty & making smooth to receive painting including cost of scaffolding etc. with cost of all materials, labours T&P etc. complete	414.60	SQM	89.80	37,231.00
21	Priming 1 coat with wall primer water bond cement primer including all labour, materials, T&P etc.	587.70	SQM	79.30	46,605.00
22	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete .	173.10	SQM	95.90	16,600.00
23	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade including cost of paint etc. complete	414.60	SQM	102.80	42,621.00
24	Supplying, fitting and fixing M.S. Iron Door, windows & grills as per approved design and drawing including all cost of materials and labour etc. complete as per direction of E.I.C.				-
a	M.S. Rolling Shutter	356.90	Kg	67.70	24,162.00
b	M.S. Door (Double leaf)	146.30	Kg	70.20	10,270.00
c	M.S. Door (Single leaf)	286.70	Kg	70.20	20,126.00
d	M.S. Window	674.40	Kg	68.00	45,859.00
e	M.S.Grill	18.00	Kg	57.60	1,037.00

Signature of Contractor


 Block Development Officer, Kutra

f	PVC door D2	4.40	SQM	2,000.00	8,800.00
25	Labour Charges for fitting, fixing M.S. Gates (MS Door, Window with grills, collapsible gates) as approved designed including cost of all labour, T&P etc. complete	37.60	SQM	94.30	3,546.00
26	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	10.65	Rmt	3,113.90	33,163.00
27	Cost of Fire fighting arrangement				5,200.00
28	Anti termite treatment in foundation, trenches and flooring with approved chemical				8,000.00
29	Display Board	1	Nos		3,500.00

Say **2,180,705.00**

(Rupees Twenty one Lakhs eighty thousand seven hundred five only)


Junior Engineer
KUTRA BLOCK


Asst. Executive Engineer
KUTRA BLOCK


Block Development Officer
KUTRA BLOCK

My quoted rate is % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

1. The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.

2. Strick out which are not applicable.

Total: - 29 (Twenty nine) Items only

No. of correction:-

No. of overwriting:-

No. of Interpolation:-

Approved for 29 (Twenty nine) Items only

Full Signature of the Contractor with date


Block Development Officer
Kutra

Signature of Contractor


Block Development Officer, Kutra