

ଓଡ଼ିଶା ସରକାର



ପଞ୍ଚାୟତ୍ତରାଜ ଓ ପାନୀୟଜଳ ବିଭାଗ,
ଓଡ଼ିଶା
ପଞ୍ଚାୟତ ସମିତି କାର୍ଯ୍ୟାଳୟ, କୁତ୍ରା

BIDS DOCUMENT FOR:-

Name of Work:-Construction of GPLF Office Building with
Market Complex at Katang, Katang GP, Kutra
Block

Tender Cost: - Rs. 21,46,616 /-

TENDER SCHEDULE

Name of the Work: Construction of GPLF Office Building with Market Complex at Katang, Katang GP

Tender Amount : Rs. 21,46,616/- (Rupees Twenty one lakh fourty six thousand six hundred sixteen) only

Scheme: - Construction of GPLF Office Building with Market Complex 2024-25

Name of the Work:- Construction of GPLF Office Building with Market Complex at Katang, Katang GP					
Sl. No	Item of Work	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation in hard soil or gravelly soil including dressing and leveling the bed and disposal of the excavated materials within initial leads and lifts as per direction of E.I.C.	72.40	cum	270.90	19,613.00
2	Supplying & filling foundation and plinth with sand well watered and rammed including cost, cost of all labour, carriage, royalty, taxes, T&P etc complete.	81.50	cum	1,055.40	86,015.00
3	Cement Concrete (1:3:6) using 40mm size hard granite C.B. metal approved quality from approved quarry including hoisting laying using concrete mixture and vibrators including cost, carriage, royalty, cost of all labour T.&P. etc complete and as directed by E.I.C.	22.40	cum	5,603.90	125,527.00
4	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size in cement mortar (1:6) in Foundation and Plinth including cost of carriage & royalty and taxes of all materials etc complete as per the direction of E.I.C.	24.50	CUM	5,589.20	136,935.00
5	Brick work with Fly Ash bricks 23cm x 11cm x 8cm size in cement mortar (1:6) in Super Structure including cost, carriage, royalty and taxes of all materials etc complete as per the direction of E.I.C.	22.10	cum	5,622.50	124,257.00
6	Brick masonry work with Fly Ash bricks in cement mortar (1:4) in super structure including cost of carriage, royalty of all materials etc complete as per the direction of E.I.C. (Ground Floor)	2.40	CUM	5,809.20	13,942.00
7	R.C.C. M-20 grade with 20mm and down grade C.B. chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator, watering, curing and cost of all materials and labour, T&P etc complete but excluding cost of reinforcement complete.	46.80	cum	5,617.80	262,913.00

Signature of Contractor


Block Development Officer, Kutra

8	Providing M.S. reinforcement for R.C.C. work including cutting, bending, binding and tying the grills and placing in position including cost of binding wire 18 to 20 gauge and cost and carriage of steel. etc. complete.	46.80	Qtl.	8,782.50	411,021.00
9	Rigid smooth centering shuttering for R.C.C.work including all cost etc complete				-
a	Column base footings	22.30	SQM	247.70	5,524.00
b	Plinth Band	21.00	SQM	247.70	5,202.00
c	Lintel Band	33.30	SQM	570.80	19,008.00
d	Beam and Column	69.40	SQM	1,189.90	82,579.00
e	Roof slab, Chajja	166.80	SQM	755.70	126,051.00
10	12mm thick C.P. in C.M.(1:6) over brick work including cost, carriage & royalty of materials etc complete as per the direction of E.I.C.	173.10	SQM	188.20	32,577.00
11	16 mm thick C.P. in C.M.(1:6) over brick work including cost, carriage & royalty of materials etc complete as per the direction of E.I.C.	319.60	SQM	271.10	86,644.00
12	6mm thick C.P. in C.M.(1:4) to RCC surfaces finished smooth including closed deep chipping and slury treatment watering, curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	95.00	SQM	207.70	19,732.00
13	2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size CB chips including curing, cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc. complete as per direction of E.I.C.	130.60	SQM	379.30	49,537.00
14	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement: 4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the	100.40	SQM	1,183.90	118,864.00
15	Supplying, fitting and fixing vitrified tile Coloured/Printed tiles (size 600mm x 600mm) in dados skirting & rises on 12mm thick cement mortar (1:3) and filling joints with neat cement slurry mixed with pigment to match the shade of the tiles including all cost, carriage, royalty & taxes of all materials, cost of all labours T&P etc complete.	9.80	SQM	1,310.70	12,845.00
16	Fixing industrial vitrified tile in floors treads or steps and on 20mm thick bed of cement mor	26.90	SQM	1,047.50	28,178.00

Signature of Contractor

Shr 2013/25
Block Development Officer, Kutra

17	Fixing industrial verified tile in dado skirting and on 12mm thick bed of cement mor (1:3) jointed	40.60	SQM	1,174.30	47,677.00
18	Finishing surface of wall with cement based wall putty including cost of Scaffolding with cost of material and labour, T&P etc, complete	414.60	SQM	89.80	37,231.00
19	Priming 1 coat with wall primer including all labour and material	587.70	SQM	79.30	46,605.00
20	Wall painting 2 coats with plastic emulsion paint on new work including cost of paint	414.60	SQM	102.80	42,621.00
21	Finishing to the exposed surfaces of wall with weather coat of any approved shade on new work 2 coats to give an even shade including cost of weather coat all cost of all labours and T&P etc. complete .	173.10	SQM	95.90	16,600.00
22	Supplying of MS Sheet and angel welded door and windows with all fitting of approved design and size at work sites including all cost of materials ,loading unloading,trasporting charges and priming one coat with approved primer etc. complete				-
a	Door (doble Leaf)	146.30	Kg	70.20	10,270.00
a	Door (Single Leaf)	286.70	Kg	70.20	20,126.00
a	M.S Rolling shutter	356.90	Kg	67.70	24,162.00
b	Window	674.40	Kg	68.00	45,859.00
c	Grill	18.00	Kg	57.60	1,037.00
e	PVC door including fixing in position lumpsum	4.40	SQM	2,000.00	8,800.00
23	Priming 1 coat to M.S doors and windows including all labour, materials, T&P etc. complete.	91.80	SQM	73.50	6,747.00
24	Painting 2 coats with any approved paint in iron works including sand papering, polishing surfaces, cost of paints, cost of all labour, T&P, etc complete in all floors as per direction of E.I.C.	91.80	SQM	182.00	16,708.00
25	Fitting,fixing of iron doors/window shutter with frame with approved design and size with all labours with T & P etc.	37.60	SQM	94.30	3,546.00

Tho 28/12/25

Signature of Contractor

Block Development Officer, Kutra

26	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless square pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	10.65	Rmt	3,113.90	33,163.00
27	Cost of Fire fighting arrangement				5,000.00
28	Anti termite treatment in foundation, trenches and flooring with approved chemical				10,000.00
29	Display Board	1	Nos		3,500.00

Say **2,146,616.00**

(Rupees Twenty one Lakhs forty six Thousand six hundred sixteen only)


Junior Engineer
KUTRA BLOCK


Asst. Executive Engineer
KUTRA BLOCK


Block Development Officer
KUTRA BLOCK

My quoted rate is % (both figure & word) Excess over / Less than / Equal to above estimated cost.

Note

1. The Contractor should not write anything except quoting of percentage and incase of anything regarding tender.
2. Strick out which are not applicable.

Total: - 29 (Twenty nine) Items only

No. of correction:-

No. of overwriting:-


No. of Interpolation:-

Approved for 29 (Twenty nine) Items only

Full Signature of the Contractor with date


Block Development Officer
Kutra

Signature of Contractor


Block Development Officer, Kutra