

**Name of the Work "Construction of Additional Class Room at Govt U.P. School
Bandhapali of Laikera G.P. of Hemgir Block.**

BOQ

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work excavation in foundation in hard soil within initial lead 50m. & lift 1.5 m. including rough dressing, breaking clods, laying in layers. Etc. Complete	cum	45.80	270.90	12407.00
2	Filling F & P with sand, well watered and rammed with cost, carriage and royalty etc. complete	cum	63.30	1596.00	101027.00
3	Cement Concrete in (1:3:6) using 40mm. Size H.G. metal including laying compacting, Curing with cost, carriage and royalty etc. complete	cum	14.80	6042.70	89432.00
4	R.C.C. M-20 Grade With 20mm and down Grade C.B. Chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator watering, curing and cost of all materials and labour, T & P etc Complete but excluding cost of reinforcement complete.	cum	31.80	6029.20	191729.00
5	Labour for straightening , Cutting, bending & binding the M.S. Road including cost of binding wire and cost of MS Road	Qtnl	31.8	8782.50	279284.00
6	Rigid and smooth centering and shuttering for R.C.C. work and dismantling then after casting including cost of all materials complete				
	(A) Shutter for Sub structure	Sqmt	12.92	247.70	3200.00
	(B) Column & Beam	Sqmt	53.40	1189.90	63541.00
	(C) Lintel Band	Sqmt	25.20	570.80	14384.00
	(D) Roof Slab & Chajja	Sqmt	112.00	755.70	84638.00
7	Brick work with Fly Ash Bricks 23cm x 12cm x 8cm size having crushing strength not less than 75kg/cm2 with dimensional tolerance + 8 Percent in cement mortar (1:6) in Foundation and Plinth including watering curing, cost of carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	cum	17.80	5978.50	106417.00
8	Fly ash Brick Masonry in C.M. (1:6) with all Finishing, Curing in superstructure etc. complete	cum	17.40	6011.80	104605.00
9	16mm thick C.P. in C.M. (1:6) over brick masonry to the rough surface including watering, curing cost, Carriage, royalty and taxes of all materials, cost of all labour, T&P etc. etc complete as per the direction of E.I.C.	Sqmt	141.40	280.90	39719.00
10	12mm thick C.P. in C.M (1:6) Over brick Masonary to the smooth surface including watering, Curing, cost, carriage, royalty and taxes of all materials, cost of all labour T&P etc. complete as per the direction of E.I.C.	Sqmt	129.2	196.30	25362.00
11	6mm thick cement plaster (1:4) to RCC surfaces finisher smooth including closed deep chipping and slurry treatment, watering, curing cost, carriage, royalty and taxes of all materials, cost of all labour, T&P etc complete as per the direction of E.I.C.	Sqmt	70.30	211.70	14883.00

12	Supplying, fitting and fixing vitrified tile (Printed) in floors of size 600mm x 600mm of approved make conforming to IS : 13755 laid on 20 mm thick cement mortar (1:4) (1 cement :4 course sand) and filling joints with white cement of approved quality including cost of all materials, labour T&P etc. required for the work all complete as per direction of E.I.C. (For New work only)	Sqmt	73.30	1212.50	88876.00
13	Fixing Vitrified tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles Including cost, carriage, cost of all labour etc. complete.	Sqmt	3.90	1336.00	5210.00
14	Fixing Industrial tiles (20cmx30cm / 20cm x 20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shades of the tiles Including cost of tiles.	Sqmt	13.80	1076.10	14850.00
15	Fixing Vitrified industrial tiles (size 600mmx600mm) (Printed) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost, carriage, cost of all labour etc. complete.	Sqmt	5.30	1199.60	6358.00
16	Finishing to the surfaces of wall with Two coat Wall Putty of any approved shade for inside and Out side wall	Sqmt	211.70	89.80	19011.00
17	Finishing to the interier surfaces of wall with Two Coat Emulsion Paint of any approved shade for Out side wall	Sqmt	211.70	102.80	21763.00
18	Priming 1 coat with wall primer water bond cement primer including all labour, Materials, T&P etc Complete	Sqmt	340.90	79.30	27033.00
19	Finishing to the exposed surfaces of wall with weather coat of any approved shade for Out side wall	Sqmt	129.20	95.90	12390.00
20	Supplying of M.S. Window made out of M.S. Angle frame, M.S. Flat, Sheet Etc. of approved section & Design Electrically welded properly with all necessary locking arrangement, and 1 coat red oxide primer including cost of all materials, labour T&P, Carriage of materials to site etc. complete	KG	81.00	57.60	4666.00
21	Supplying ,Fitting and fixing of 32 mm thick flush Door shutter with approved quality of 30 mm thick BWR block board pasted with 1mm thick sunmica on both side of approved design and quality including the cost of all Door fitting and Fixture etc Completed.	Sqmt	4.40	10775.30	47411.00
22	Supplying ,Fitting and fixing of two track UPVC Sliding window of approved make with 6mm thick glass of approved quality complete with frame shutter and fitting and Fixture etc Completed.	Sqmt	3.20	5010.60	16034.00
23	Priming 1 coat over Door and Window primer including all labour, Materials, T&P etc Complete	Sqmt	1.60	73.50	118.00
24	Enamel paint two coat for Door and Window	Sqmt	1.60	182.00	291.00

25	Supplying, fitting and fixing of stainless steel of 304 grade in hand railing using 50 mm dia of 2 mm thick circular pipe with Balustrade of size 32 mm x 32mm x 2mm @ 0.90 mtr C/C and stainless aquare pipe bracing of size case as per approved design and specification, buffing, polishing etc. with the cost, conveyance taxes of all material, cost of all labour etc. complete in all respect. (in all floor)	Rmt	15.50	3113.90	48265.00
26	Fixing M.S. angle and Door and Window etc Completed.	Sqmt	3.20	94.30	302.00
27	2.5cm thic grading concrete (1:2:2) on roof slab with 6mm size hard crusher broken Granite chips on new work including watering curing cost of all materials water- proofing compounds, T&P required for the works etc complete	Sqmt	85.70	391.60	33560.00
28	Add for Electrification work (as per actual voucher excluding GST)				41178.00
29	Transparency Board (LS)				2542.37
30	Add towards cost of fire Fighting arrangement (as per actual voucher excluding GST)				3389.00
31	Add towards Rain water Hearvesting System (Recharge Pit) (as per actual voucher excluding GST)				8474.57
32	Add for Anti-termite treatment in foundation trenches and flooring with approved Chemical (as per actual voucher excluding GST)				4237.28
33	Black Board 12' x 4' Size, side development & photography (as per actual voucher) excluding GST)				4322.03
					1540909.25
				Limited to	1540900.00

The tenderer are required to put their percentage of rate in the blank space given below, failing which the tenderer document will be rejected.

My/Our quoted rate is _____%(Figure) _____(in words)

*Less than/Excesover/Equal to the amount put to tender

Total number of items.....	
Number of corrections.....	
Number of interpolation.....	
Number of over writing.....	
E.M.D Furnished /E.M.D Exampted	
(A)Demand Draft No.....	
(B)Amount Rs.....	
Copy PAN card furnished /not furnished	
Copy of GST Registration:furnished /not furnished	
Copy of contractor Licenence:firnished /not durnished	
copy of Experience certificate:furnished/not furnished	
Total No of sheets in the Tender paper.....	

ull Signature of Contracto

Signature of the Bidder/Tenderer

Signature of the B.D.O
Hemgir